

ADDENDUM COVER SHEET

Addendum No. 1

Martin Luther King Jr. Drive Trail Improvements

Philadelphia Redevelopment Authority

Issue Date: September 23, 2020

ITEM:

1. Addition of a Project Bid Tabulation Sheet. (See attached). This Sheet must be completed with your bid. It is intended to provide the PRA with a breakdown of where costs are coming from. The project will still be awarded to the Contractor with the lowest Total Base Bid as detailed in the Bid Proposal Form.
 - Please note – the Bid Opening has not been extended. Sealed Bids will be received at 10:00 AM, Tuesday, September 29, 2020 at MLK Drive and Sweet Briar Drive, Philadelphia, PA 19131 and will be opened immediately thereafter.

CONTRACTOR'S BID

MLK Drive Trail Rehabilitation

Contractor: _____

Date: _____

Item No	Description	Quantity	Unit	Unit Cost	Total Cost
4-1041	INSPECTION SERVICES (PHILA STREETS DEPT)	5	DAY	\$	\$
0201-0001	CLEARING AND GRUBBING	1	LS	\$	\$
0203-0001	CLASS 1 EXCAVATION	3,058	CY	\$	\$
0203-0004	CLASS 1B EXCAVATION	921	CY	\$	\$
0212-0014	GEOTEXTILE, CLASS 4, TYPE A	74	SY	\$	\$
0350-0106	SUBBASE 6" DEPTH (NO. 2A)	11,940	SY	\$	\$
0413-0195	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, < 0.3 MILLION ESALS, 9.5 MM MIX, 1 1/2" DEPTH, SRL-L	23,028	SY	\$	\$
0413-0297	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, 3 TO < 10 MILLION ESALS, 9.5 MM MIX, 1 1/2" DEPTH, SRL-E	53	SY	\$	\$
0413-6030	SUPERPAVE ASPHALT MIXTURE DESIGN, BINDER COURSE, PG 64S-22, < 0.3 MILLION ESALS, 25.0 MM MIX, 3" DEPTH	11,734	SY	\$	\$
0413-6055	SUPERPAVE ASPHALT MIXTURE DESIGN, BINDER COURSE, PG 64S-22, 3 TO < 10 MILLION ESALS, 19.0 MM MIX, 2 1/2" DEPTH	53	SY	\$	\$
0460-0001	BITUMINOUS TACK COAT	23,080	SY	\$	\$
0491-0012	MILLING OF BITUMINOUS PAVEMENT SURFACE, 1 1/2" DEPTH, MILLED MATERIAL RETAINED BY CONTRACTOR	11,295	SY	\$	\$
0501-0028	PLAIN CEMENT CONCRETE PAVEMENT, 8" DEPTH	40	SY	\$	\$
0608-0001	MOBILIZATION	1	LS	\$	\$
0630-0001	PLAIN CEMENT CONCRETE CURB	283	LF	\$	\$
0676-0001	CEMENT CONCRETE SIDEWALK	187	SY	\$	\$
0695-0002	DETECTABLE WARNING SURFACE, CAST IRON	100	SF	\$	\$
0703-0025	NO. 57 COARSE AGGREGATE	18	CY	\$	\$
0802-0001	TOPSOIL FURNISHED AND PLACED	1,316	CY	\$	\$
0806-0113	TEMPORARY SHORT-TERM, ROLLED EROSION CONTROL PRODUCT, TYPE 2D	224	SY	\$	\$
0810-0052	SELECTIVE TREE REMOVAL	17	EACH	\$	\$
0849-0010	ROCK CONSTRUCTION ENTRANCE	2	EACH	\$	\$
0850-0034	ROCK, CLASS R-6	8	CY	\$	\$
0855-0003	PUMPED WATER FILTER BAG	2	EACH	\$	\$
0860-0000	INLET FILTER BAG FOR TYPE M INLET	70	EACH	\$	\$
0867-0012	COMPOST FILTER SOCK, 12" DIAMETER	15,873	LF	\$	\$
4901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	\$	\$
0931-0001	POST MOUNTED SIGNS, TYPE B	53	SF	\$	\$
0935-0001	POST MOUNTED SIGNS, TYPE F	35	SF	\$	\$

Item No	Description	Quantity	Unit	Unit Cost	Total Cost
0941-0001	RESET POST MOUNTED SIGNS, TYPE B	1	EACH	\$	\$
0960-0001	4" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	3,607	LF	\$	\$
0960-0002	4" YELLOW HOT THERMOPLASTIC PAVEMENT MARKINGS	828	LF	\$	\$
0960-0021	24" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	555	LF	\$	\$
0960-0255	WHITE HOT THERMOPLASTIC LEGEND, "YIELD LINE", 12" X 18" TRIANGLE	18	LF	\$	\$
0960-2001	BLUE HOT THERMOPLASTIC LEGEND, "HANDICAP SYMBOL", 3' - 3" X 2'-11"	3	EACH	\$	\$
0963-0001	PAVEMENT MARKING REMOVAL	500	SF	\$	\$
9000-1000	PAINT EXISTING STEEL RAILING	1,520	LF	\$	\$
9000-1001	STEEL RAILING REPAIR	78	LF	\$	\$
9000-1002	TREE TRIMMING ALONG TRAIL	1	LS	\$	\$
9000-1003	SPLIT RAIL FENCE	208	LF	\$	\$
9000-1004	12" WIDE POLYMER DIRECTIONAL INDICATOR TILE	22	EACH	\$	\$
9000-1005	REPLACE CENTER GATE POST	2	EACH	\$	\$
9000-1006	SEEDING	525	LB	\$	\$
9000-1007	TREE PROTECTION	7,529	LF	\$	\$
9000-1008	REPAIR OF WOOD SLAT FENCE	30	LF	\$	\$
9000-1009	WHITE PREFORMED THERMOPLASTIC LEGEND, "BICYCLE ARROW", 6'-0" X 2'-0"	10	EACH	\$	\$
9000-1010	8" HDPE FRENCH DRAIN	119	LF	\$	\$
9000-1011	CLEAN EXISTING INLET	1	EACH	\$	\$
9000-1012	FILL ABANDONED INLET	1	EACH	\$	\$
9000-1013	COLLAPSIBLE BOLLARD	2	EACH	\$	\$

TOTAL BID \$