

**SUBJECT:** County: Philadelphia  
Project: Alley Retaining Wall 7-038  
Between Jefferson St. & Nassau St., from 61<sup>st</sup> St. to  
63<sup>rd</sup> St.

**TO:** All Contractors

**FROM:** Mark N. Washington, Chief Design Engineer, City of Philadelphia

Following is the Utility Clearance (Form D-419) with the Utility Clearance Assurance statement for the above project. This project is scheduled for a **January xx, 2025** letting. This certifies that all written responses from all known utilities within the project limits have been received, and are on file as of October 23, 2024. Therefore; it is recommended that a certification of Utility Clearance be furnished.

### UTILITIES

Cooperate with the public utility companies and local authorities in the placement, replacement, relocation, adjustment, or reconstruction of their structures and facilities during construction. Contact all utility representatives at least fifteen (15) calendar days prior to starting operations.

<b>PRIOR</b>	Anticipated completion before the Notice to Proceed is issued. Actual or anticipated completion date shown.
<b>RESTRICTIVE</b>	To be completed by the utility or a string of utilities before operating without restriction. Number of calendar days will start after the notice to proceed is issued to the highway contractor and the contractor notifies the utilities.
<b>CONCURRENT</b>	Simultaneous with, but not restricting, the highway contractor's operation. Number of calendar days required.
<b>COORDINATED</b>	Phasing with specific construction operations and/or phasing with the operations of other utilities. Number of calendar days required after completion of a specific construction operation.
<b>NOT AFFECTED</b>	Identifies UTILITY with facilities in the construction area which are not anticipated to be affected. Specific information may be provided by the UTILITY.
<b>INCORPORATED</b>	Utility relocation work to be included into the prime highway construction contract to be completed by the highway contractor.
<b>CONDITIONAL RESTRICTIONS AND TIME REQUIREMENTS</b>	Identify conditions affecting the utility's ability to perform a certain type of utility relocation work, i.e., certain times of the day, week, or year that a facility cannot be shut down, acquisition of right-of-way by the State, or demolition of buildings.

### **PECO ENERGY COMPANY (PECO)**

CONTACT: Louis Robinson, telephone (215) 731-3283 at least Two (2) weeks prior to construction of temporary alley lights or new permanent alley lights.

COORDINATED - (Aerial):

- 1) STA. 0+64 to STA. 3+52. PECO will disconnect power to existing alley lights and connect to temporary alley lights.
- 2) STA. 0+64 to STA. 3+52. PECO will disconnect power to temporary alley lights and connect to new permanent alley lights.
- 3) Requests for Make Safe must be made a minimum of 10 weeks in advance via a Service & Meter Requests & forwarded to [PhilaNewBusiness@exeloncorp.com](mailto:PhilaNewBusiness@exeloncorp.com)

### **COMCAST**

CONTACT: Darren Marsteller, telephone (717) 405-4280 at least Two (2) weeks prior to construction. After construction begins there will be a Comcast contact to call for relocation of drops. At that time it will be determined how many days notice is needed to get a tech on site.

COORDINATED: Station 1+00 to 8+00 Comcast will relocate service drops for contractor during construction. The drops are running from the rear of Jefferson Street homes to customers on Nassau Street. Comcast tech will remove non-active drops and work with contractor on placement of active drops.

### **PHILADELPHIA GAS WORKS (PGW)**

CONTACT: Kevin Diep, telephone (215) 684-6235 at least Two (2) weeks prior to construction. Installation of sheeting or demolition of the existing retaining wall cannot begin until PGW has completed the relocation of the existing 3" gas main.

COORDINATED: Station 0+80 to 2+25 PGW will relocate an existing steel 3" gas main and 5 service laterals to the apartment buildings on Nassau Street.

### **VERIZON**

CONTACT: Brian Egolf, telephone (215) 370-8687 at least Two (2) weeks prior to construction. Former Verizon lines on the wooden poles in the alley have been disconnected and/or removed. The contractor will remove the abandoned wooden poles under the pay item for Clearing and Grubbing. After construction begins there will be a Verizon contact to call for relocation of any remaining drops. At that time it will be determined how many days notice is needed to get a tech on site.

COORDINATED: Station 0+00 to 8+00 Verizon will relocate any remaining service drops for contractor during construction. The drops are running from the rear of Jefferson Street homes to customers on Nassau Street. Verizon tech will remove non-active drops and work with contractor on placement of active drops.

**CITY OF PHILADELPHIA WATER DEPARTMENT (PWD)**

CONTACT: Mike Schramm, telephone (215) 685-6350.

NOT AFFECTED: The utility is not affected by the scope of this project

**All necessary arrangements have been made for all known utility relocation work to be undertaken and completed as required for proper coordination with the physical construction schedules. Any changes to the utility relocation work must be approved by the City of Philadelphia. Changes made for the contractor's convenience will be performed at the contractor's expense. Separate payment will not be made for the contractor's coordination, scheduling and oversight of the utilities.**

---

Signature of an Official of the Local Government Body or Sponsor

---

Date