



- . TOPOGRAPHIC INFORMATION TAKEN FROM A PLAN BY AMERICAN ENGINEERS GROUP, LLC ENTITLED "KINGSESSING RECREATION CENTER TOPOGRAPHIC SURVEY", SHEET NO. 1, DATED 03/12/2021.
- 2. BOUNDARY INFORMATION FROM GIS. BOUNDARY SURVEY NOT PERFORMED

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

SCALE: 1"=20'-0"

EXISTING LEGE	ND
	EXISTING PROPERTY LINE (APPROXIMATE) EXISTING RIGHT OF WAY LINE (APPROXIMATE) EXISTING BUILDING
	EXISTING CURB
	EXISTING SIDEWALK
	EXISTING EDGE OF MACADAM/GRAVEL
	EXISTING TRAFFIC MARKING
× ×	EXISTING FENCE
and the second s	EXISTING TREE
	EXISTING MAJOR CONTOUR
4	EXISTING MINOR CONTOUR
-0-	EXISTING SIGN
•	EXISTING BOLLARD
\mathcal{Q}	EXISTING UTILITY POLE
	EXISTING LIGHT
	EXISTING INLET
<i>S</i>	EXISTING SEWER
D	EXISTING STORM SEWER
W	EXISTING WATER LINE
UT	EXISTING UNDERGROUND TELEPHONE LINE
	EXISTING GAS LINE
UE	EXISTING UNDERGROUND ELECTRIC
OE	EXISTING OVERHEAD WIRES
	EXISTING UTILITY STRUCTURES

PROPOSED LEG	SEND
	PROPOSED BUILDING
M	PROPOSED DOOR
4 4	PROPOSED CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
Ψ Ψ Ψ	PROPOSED LANDSCAPED AREA
	PROPOSED UNIT PAVERS
	PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC)
••••••	PROPOSED SYNTHETIC TURF FIELD
2555555	PROPOSED ADA RAMP
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED WALL
	PROPOSED STOP BAR/PAVEMENT MARKING
O	PROPOSED FENCE
—	PROPOSED SIGN
	PROPOSED LIMIT OF DISTURBANCE
o	PROPOSED CONSTRUCTION FENCE

EXISTING LEGE	ND	PR0
	EXISTING PROPERTY LINE (APPROXIMATE) EXISTING RIGHT OF WAY LINE (APPROXIMATE)	
///////	EXISTING BUILDING	ه
	EXISTING CURB	·····
A	EXISTING SIDEWALK	
	EXISTING EDGE OF MACADAM/GRAVEL	
	EXISTING TRAFFIC MARKING	
××	EXISTING FENCE	
彩	EXISTING TREE	
	EXISTING MAJOR CONTOUR	
4	EXISTING MINOR CONTOUR	
<u> </u>	EXISTING SIGN	
•	EXISTING BOLLARD	
\mathcal{A}	EXISTING UTILITY POLE	
	EXISTING LIGHT	
	EXISTING INLET	
<i>s</i>	EXISTING SEWER	
D	EXISTING STORM SEWER	
<i>W</i>	EXISTING WATER LINE	
<i>UT</i>	EXISTING UNDERGROUND TELEPHONE LINE	
<i>UG</i>	EXISTING GAS LINE	
UE	EXISTING UNDERGROUND ELECTRIC	
OE	EXISTING OVERHEAD WIRES	
. ⊮ ″™ €⊛1050	EXISTING UTILITY STRUCTURES	

PROPOSED LEG	GEND
	PROPOSED BUILDING
M	PROPOSED DOOR
4. 4	PROPOSED CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
∇ ∇ ∇	PROPOSED LANDSCAPED AREA
	PROPOSED UNIT PAVERS
	PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC)
	PROPOSED SYNTHETIC TURF FIELD
9259252	PROPOSED ADA RAMP
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED WALL
	PROPOSED STOP BAR/PAVEMENT MARKING
O	PROPOSED FENCE
—	PROPOSED SIGN
	PROPOSED LIMIT OF DISTURBANCE
	PROPOSED CONSTRUCTION FENCE

SCALE: 1"=20'-0"

GRADING AND EARTHWORK NOTES:

- A GEOTECHNICAL ENGINEER IS REQUIRED TO INSPECT, TEST AND CERTIFY TO THE COMPACTION OF ALL LOAD BEARING FILLS. ALL EXISTING UNDERGROUND UTILITIES SHALL BE REMOVED OR RELOCATED. THE PREPARED SUBGRADE SHALL BE PROOF ROLLED WITH A ¹⁵ SMOOTH-DRUM VIBRATING ROLLER TO DELINEATE SOFT/UNSTABLE AREAS AND COMPACT SOILS DISTURBED DURING EXCAVATION OPERATIONS. AREAS WHICH EXHIBIT INSTABILITY SHALL BE UNDERCUT AND REPLACED WITH LOAD-BEARING FILL.
- BEDDING REQUIREMENTS SPECIFIED HEREIN ARE TO BE CONSIDERED AS MINIMUMS FOR RELATIVELY DRY, STABLE EARTH CONDITIONS. ADDITIONAL BEDDING SHALL BE REQUIRED FOR ROCK TRENCHES AND WET AREAS. CONTRACTOR SHALL HAVE THE RESPONSIBILITY O PROVIDE SUCH ADDITIONAL BEDDING AS MAY BE REQUIRED TO PROPERLY CONSTRUCT THE WORK

MINIMUM PAVEMENT GRADE SHALL BE 1.0% SLOPE UNLESS NOTED OTHERWISE.

- COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF THEORETICAL MAXIMUM DRY DENSITY (ASTM D698). BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS AND SHALL BE PLACED IN LIFTS NOT TO EXCEED 6 INCHES IN COMPACTED FILL THICKNESS. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- THE CONTRACTOR WILL INSURE THAT POSITIVE AND ADEQUATE DRAINAGE IS MAINTAINED AT ALL TIMES WITHIN THE PROJECT LIMITS. THIS MAY INCLUDE, BUT NOT BE LIMITED TO, REPLACEMENT OR RECONSTRUCTION OF EXISTING DRAINAGE STRUCTURES THAT HAVE BEEN DAMAGED OR REMOVED OR REGRADING AS REQUIRED BY THE ENGINEER. EXCEPT FOR THOSE DRAINAGE ITEMS SHOWN AT SPECIFIC LOCATIONS AND HAVING SPECIFIC PAY ITEMS IN THE DETAILED ESTIMATE. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COSTS INCURRED TO COMPLY WITH THIS REQUIREMENT.
- THE CONTRACTOR SHALL PROVIDE ANY AND ALL EXCAVATION AND MATERIAL SAMPLES NECESSARY TO CONDUCT REQUIRED SOIL TESTS. ALL ARRANGEMENTS AND SCHEDULING FOR THE TESTING SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- SOILS TESTING AND ON-SITE INSPECTION SHALL BE PERFORMED BY AN INDEPENDENT GEOTECHNICAL ENGINEER. THE SOILS ENGINEER SHALL PROVIDE COPIES OF TEST REPORTS TO THE CONTRACTOR, THE OWNER AND THE OWNER'S REPRESENTATIVE AND SHALL PROMPTLY NOTIFY THE OWNER, HIS REPRESENTATIVE AND THE CONTRACTOR, SHOULD WORK PERFORMED BY THE CONTRACTOR FAIL TO MEET THESE SPECIFICATIONS.
- CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES AROUND THE WORK AREA AND SHALL PROVIDE PROTECTION AGAINST WATER DAMAGE AND SOIL EROSION. MAXIMUM SIDEWALK CROSS SLOPE IS 2% AND MINIMUM SIDEWALK CROSS SLOPE IS 1.0%
- WITHIN THE CITY RIGHT OF WAY. 10. ELEVATIONS ARE BASED ON CITY OF PHILADELPHIA VERTICAL DATUM.
- 11. REFER TO GEOTECHNICAL REPORT FOR BELOW GRADE CONDITIONS AND SITE PREPARATION/ EXCAVATION REQUIREMENTS.
- 12. ALL UTILITY VALVES AND MANHOLE STRUCTURES WITHIN THE SIDEWALKS AND ROADWAYS SHALL BE ADJUSTED TO THE PROPOSED GRADES AS NECESSARY. CONTRACTOR SHALL COORDINATE WITH THE APPROPRIATE UTILITY COMPANY.
- 13. FILL CAN BE REUSED AS A COMPACTED FILL FOR BACKFILL, AS LONG AS IT IS FREE OF TRASH, ENVIRONMENTAL HAZARDS, AND OTHER DELETERIOUS MATERIAL. ADJUSTING MOISTURE CONTENT PRIOR TO FILL PLACEMENT SHOULD BE EXPECTED
- 14. ALL DIMENSIONS SHOWN ARE IN US SURVEY FEET (US) UNLESS DESIGNATED CITY OF PHILADELPHIA DISTRICT STANDARD MEASURE (DS).
- 15. THE DISTRICT STANDARD FOR CONVERSION IS U.S. = DS X 1.0025
- 16. DEMOLITION DEBRIS, ASSOCIATED WITH THE STRUCTURE TO BE REMOVED CONSISTING OF CONCRETE AND OTHER MASONRY PRODUCTS CAN BE CRUSHED AND REUSED IN NEW LOAD-BEARING FILL, PROVIDED IT IS FREE OF THE LIMITATIONS DESCRIBED IN NOTE #13
- 17. CONTROLLED/COMPACTED FILL SHALL BE PLACED IN EARLY STAGES OF CONSTRUCTION TO ALLOW FOR SITE SETTLEMENT DURING CONSTRUCTION OF BUILDING.

18. ALL SITE PREPARATION AND EARTHWORK OPERATIONS SHALL BE CARRIED OUT IN THE FULL-TIME PRESENCE OF A QUALIFIED REPRESENTATIVE OF THE GEOTECHNICAL ENGINEER. WHERE OBSTRUCTIONS SUCH AS CONCRETE, FOUNDATIONS, BRICK, AND WOOD ARE ENCOUNTERED ABOVE THE COMPRESSIBLE LAYERS, PRE-DRILLING FOR THE PVDs WILL BE REQUIRED; THEREFORE, CONSIDERABLE EXTRA COSTS COULD BE INVOLVED AND A CONTINGENCY FOR PREDRILLING SHOULD BE CARRIED IN THE CONSTRUCTION BUDGET

- THE RUBBLE FROM DEMOLITION SHOULD BE CRUSHED OR STAGED FOR REUSE AND IMPORTED FILL SHOULD NOT CONTAIN EXCESS OVERSIZE MATERIALS THAT WOULD PREVENT THE DIRECT PUSH INSTALLATION OF THE WICK DRAINS. GIVEN THE LIMITED WORK AREA, IT WILL BE IMPORTANT TO MAINTAIN POSITIVE DRAINAGE ACROSS THE SITE. A DRAINAGE BLANKET CONSISTING OF GRAVEL OR SAND WITH LESS
- THAN 10 PERCENT FINES SHOULD BE PLACED ACROSS THE WORK AREA BEFORE PLACING ALL OF THE FILL. THE BLANKET SHOULD BE AT LEAST 12 INCHES THICK AND SHOULD CONVEY WATER TO A PERIMETER DITCH. ALTERNATIVELY, OR IN COMBINATION WITH THE DRAINAGE BLANKET, HORIZONTAL STRIP DRAINS CAN BE ATTACHED TO THE VERTICAL
- ALL FILL MATERIALS, INCLUDING SURCHARGE SOILS, SHOULD BE PLACED IN 8- TO 10-INCH THICK LIFTS AND BE COMPACTED TO A MINIMUM OF 95 OF THE MAXIMUM DRY DENSITY IN GENERAL ACCORDANCE WITH ASTM D698. THE FILL SOILS SHOULD HAVE AN IN-PLACE WET WEIGHT OF ABOUT 125 TO 130 POUNDS PER CUBIC FOOT TO BE CONSISTENT WITH THE LOADINGS ASSUMED IN OUR ANALYSIS.
- . FOLLOWING THE STRIPPING OF ASPHALT AND ORGANIC MATERIALS, IF FILL MATERIALS ARE REQUIRED THE EXPOSED SUBGRADE SOILS SHOULD BE EVALUATED. IDEALLY, THE EVALUATION SHOULD CONSIST OF PROOFROLLING AND COMPACTING THE SOILS TO A DENSE AND UNYIELDING CONSISTENCY BY SEVERAL PASSES OF A LOADED TRIAXLE DUMP TRUCK, OFF-ROAD DUMP TRUCK, OR LARGE SMOOTH DRUM VIBRATORY COMPACTOR WITH A STATIC DRUM WEIGHT OF AT LEAST TEN TONS, ALTHOUGH SOME OTHER METHOD MAY BE DEEMED MORE APPROPRIATE BY THE GEOTECHNICAL ENGINEER DEPENDING ON THE PREVAILING WEATHER CONDITIONS. SOILS THAT ARE OBSERVED TO BE SOFT OR UNSTABLE DURING THE EVALUATION SHOULD BE SELECTIVELY OVER-EXCAVATED, AND THE RESULTANT EXCAVATIONS SHOULD BE BACKFILLED WITH CONTROLLED COMPACTED FILL
- 23. UPON SATISFACTORY EVALUATION OF THE SUBGRADE, STRUCTURAL FILL SHOULD BE PLACED IN LIFTS AND COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS INCLUDED IN THIS REPORT. THE MATERIALS WILL TYPICALLY NEED TO BE WITHIN 2 TO 3 PERCENTAGE POINTS OF THE OPTIMUM MOISTURE CONTENT BEFORE COMPACTIVE EFFORT IS APPLIED. OFF-SITE BORROW SHOULD GENERALLY MEET UNIFIED SOIL CLASSIFICATION SYSTEM (USCS) DESIGNATION SM, SP-SM, GP-GM, GM, OR GW AND BE APPROVED BY THE
- GEOTECHNICAL ENGINEER PRIOR TO USE. CONSIDERATION OF OFF-SITE BORROW MEETING OTHER USCS CLASSIFICATIONS WOULD BE MADE BY THE GEOTECHNICAL ENGINEER BASED ON THE LOCATION AND DEPTH TO WHICH THOSE MATERIALS ARE PLACED. 24. ALL STRUCTURAL FILL SHOULD BE CONSTRUCTED IN MAXIMUM 8-INCH THICK LOOSE LIFTS
- AND BE COMPACTED TO 95 PERCENT OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY, WITH MOISTURE CONTENTS WITHIN 3 PERCENTAGE POINTS OF OPTIMUM FOR COMPACTION. 25. ALL TEMPORARY SURCHARGE FILL SHALL BE CONSTRUCTED IN MAXIMUM 8-INCH THICK LOOSE LIFT AND BE COMPACTED TO 95 PERCENT OF THE STANDARD PROCTOR MAXIMUM
- DRY DENSITY, WITH MOISTURE CONTENTS WITHIN 3 PERCENTAGE POINTS OF OPTIMUM FOR COMPACTION. 6. FILL SUBGRADES AND EACH LIFT OF FILL SHOULD BE OBSERVED AND TESTED BY A SOILS TECHNICIAN ON A FULL-TIME BASIS, UNDER THE SUPERVISION OF A REGISTERED ENGINEER AS REQUIRED PER THE INTERNATIONAL BUILDING CODE. ALL COMPACTIVE EFFORT SHOULD BE VERIFIED BY IN-PLACE DENSITY TESTING. NEW FILLS CONSTRUCTED ON SLOPES STEEPER THAN 5H:1v (HORIZONTAL TO VERTICAL) SHOULD BE KEYED INTO EXISTING SLOPED FOR STABILITY CONSIDERATIONS. GTA RECOMMENDS THAT ALL PERMANENT

SLOPES SHOULD BE GRADED 3H:1V OR FLATTER. ALL FILL SLOPES STEEPER THAN 5H:1V

SHOULD GENERALLY BE PLACED AS STRUCTURAL FILL AND BE CONTROLLED AND COMPACTED TO MINIMUM DENSITIES AS SPECIFIED ABOVE. 27. POSITIVE DRAINAGE SHALL BE MAINTAINED ACROSS THE SITE DURING CONSTRUCTION TO PREVENT PONDING OF WATER, SINCE THE EXPOSED SUBGRADES COULD DESTABILIZE IN COMBINATION WITH CONSTRUCTION TRAFFIC AND PRECIPITATION FURTHERMORE HEAVY CONSTRUCTION TRAFFIC SHOULD GENERALLY BE RUN ON DESIGNATED HAUL ROADS DURING PERIODS OF WET WEATHER TO REDUCE THE POTENTIAL FOR DESTABILIZATION OF

MORE SUBGRADE AREAS THAN NECESSARY. IF THE SUBGRADE IS DISTURBED BY CONSTRUCTION TRAFFIC AND BECOMES UNSTABLE, UNDERCUTTING AND REPLACEMENT OF THESE SUBGRADE MATERIALS WILL LIKELY BE REQUIRED.

EXISTING LEGE	ND
	EXISTING PROPERTY LINE (APPROXIMATE) EXISTING RIGHT OF WAY LINE (APPROXIMATI
A · · · ·	EXISTING SIDEWALK
	EXISTING TRAFFIC MARKING
~~~^~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	EXISTING FENCE
A.	EXISTING TREE
5	EXISTING MAJOR CONTOUR
4	EXISTING MINOR CONTOUR
0	EXISTING SIGN
•	EXISTING BOLLARD
$\Sigma$	EXISTING UTILITY POLE
	EXISTING LIGHT
	EXISTING INLET
<i>s</i>	EXISTING SEWER
<i>D</i>	EXISTING STORM SEWER
<i>W</i>	EXISTING WATER LINE
<i>UT</i>	EXISTING UNDERGROUND TELEPHONE LINE
<i>UG</i>	EXISTING GAS LINE
UE	EXISTING UNDERGROUND ELECTRIC
OE	EXISTING OVERHEAD WIRES
. ⊮ ™™ €®1\$\$	EXISTING UTILITY STRUCTURES

PROPOSED LEGEND PROPOSED BUILDING M PROPOSED DOOR PROPOSED CONCRETE PAVEMENT PROPOSED ASPHALT PAVEMENT PROPOSED LANDSCAPED AREA PROPOSED UNIT PAVERS PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC) PROPOSED SYNTHETIC TURF FIELD PROPOSED ADA RAMP PROPOSED CURB PROPOSED DEPRESSED CURB PROPOSED WALL PROPOSED STOP BAR/PAVEMENT MARKING ------ PROPOSED FENCE PROPOSED SIGN ____ PROPOSED LIMIT OF DISTURBANCE PROPOSED CONSTRUCTION FENCE ------- 5 ------ PROPOSED MAJOR CONTOUR 6 — PROPOSED MINOR CONTOUR 6.45 PROPOSED SPOT ELEV. LP 6.00 PROPOSED LOW POINT ELEV. PROPOSED TOP OF CURB ELEV. TC 7.50 BC 7.00 PROPOSED BOTTOM OF CURB ELEV.

![](_page_6_Figure_35.jpeg)

![](_page_7_Figure_0.jpeg)

SCALE: 1"=20'-0"

	EXISTING PROPERTY LINE (APPROXIMATE)	
	EXISTING RIGHT OF WAY LINE (APPROXIMATI	
	EXISTING BUILDING	4. 4
	EXISTING CURB	
A	EXISTING SIDEWALK	Ţ, Ţ,
	EXISTING EDGE OF MACADAM/GRAVEL	
	EXISTING TRAFFIC MARKING	
××	EXISTING FENCE	
all and a second s	EXISTING TREE	1938 
5	EXISTING MAJOR CONTOUR	
4	EXISTING MINOR CONTOUR	
<del>.</del>	EXISTING SIGN	
•	EXISTING BOLLARD	(
à	EXISTING UTILITY POLE	-
\$ → Đ	EXISTING LIGHT	
	EXISTING INLET	o
<i>s</i>	EXISTING SEWER	<u> </u>
D	EXISTING STORM SEWER	6
<i>W</i>	EXISTING WATER LINE	6.
<i>UT</i>	EXISTING UNDERGROUND TELEPHONE LINE	LP
<i>UG</i>	EXISTING GAS LINE	TC
UE	EXISTING UNDERGROUND ELECTRIC	BC
OE	EXISTING OVERHEAD WIRES	
. ⊮ ™ (E) (W) (T) (S) (D)	EXISTING UTILITY STRUCTURES	

PROPOSED LEG	END
	PROPOSED BUILDING
M	PROPOSED DOOR
4. 4	PROPOSED CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
$\Psi$ $\Psi$ $\Psi$	PROPOSED LANDSCAPED AREA
	PROPOSED UNIT PAVERS
	PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC)
	PROPOSED SYNTHETIC TURF FIELD
F254252	PROPOSED ADA RAMP
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED WALL
	PROPOSED STOP BAR/PAVEMENT MARKING
O	PROPOSED FENCE
_	PROPOSED SIGN
	PROPOSED LIMIT OF DISTURBANCE
o	PROPOSED CONSTRUCTION FENCE
5	PROPOSED MAJOR CONTOUR
<u> </u>	PROPOSED MINOR CONTOUR
6.45	PROPOSED SPOT ELEV.
LP 6.00	PROPOSED LOW POINT ELEV.
TC 7.50	PROPOSED TOP OF CURB ELEV.
PC 7 00	

PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

![](_page_7_Figure_8.jpeg)

![](_page_8_Figure_0.jpeg)

GRADING PLAN DETAIL - PLAYGROUND SCALE: 1"=10'-0"

### EXISTING LEGEND

EWISD

PROPOSED LEGEND EXISTING PROPERTY LINE (APPROXIMATE) ► PROPOSED DOOR —— — — — — EXISTING RIGHT OF WAY LINE (APPROXIMATI EXISTING BUILDING EXISTING CURB EXISTING SIDEWALK EXISTING EDGE OF MACADAM/GRAVEL ----- EXISTING TRAFFIC MARKING ——×———×—— EXISTING FENCE 裕 EXISTING TREE ----- EXISTING MAJOR CONTOUR - EXISTING MINOR CONTOUR _ _ _ _ 4 _ _ _ _ _ -0-EXISTING SIGN EXISTING BOLLARD  $\mathcal{Q}$ EXISTING UTILITY POLE ☆ ় → 🖸 🛛 EXISTING LIGHT EXISTING INLET *—— s —— EXISTING SEWER — D — EXISTING STORM SEWER* ——— W ——— EXISTING WATER LINE TC 7.50 BC 7.00 ------ EXISTING GAS LINE ------ EXISTING UNDERGROUND ELECTRIC ------ EXISTING OVERHEAD WIRES EXISTING UTILITY STRUCTURES

### PROPOSED CONCRETE PAVEMENT PROPOSED ASPHALT PAVEMENT PROPOSED LANDSCAPED AREA PROPOSED UNIT PAVERS PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC) PROPOSED SYNTHETIC TURF FIELD PROPOSED ADA RAMP PROPOSED CURB PROPOSED DEPRESSED CURB PROPOSED WALL ------- PROPOSED FENCE PROPOSED SIGN —

PROPOSED BUILDING

PROPOSED STOP BAR/PAVEMENT MARKING ------- 5 ------ PROPOSED MAJOR CONTOUR 6 — PROPOSED MINOR CONTOUR PROPOSED SPOT ELEV. 6.45 LP 6.00

PROPOSED LOW POINT ELEV. PROPOSED TOP OF CURB ELEV.

PROPOSED BOTTOM OF CURB ELEV.

CALL BEFORE YOU DIG BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA CALL 1-800-242-1776

PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL OR BLAST PENNSYLVANIA ONE-CALL SYSTEM, INC. SERIAL NUMBER(S): 20212583952

![](_page_8_Figure_14.jpeg)

![](_page_9_Figure_0.jpeg)

NOT FOR CONSTRUCTION NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

![](_page_9_Picture_12.jpeg)

![](_page_10_Figure_0.jpeg)

SCALE: 1"=20'-0"

![](_page_10_Figure_2.jpeg)

- THE CONTRACTOR. 11. THE CONTRACTOR SHALL COORDINATE LOCATION AND INSTALLATION OF ALL UNDERGROUND UTILITIES AND APPURTENANCES TO MINIMIZE DISTURBANCE TO CURBING, PAVING, AND COMPACTED SUBGRADE.
- 12. UTILITY COORDINATION SHALL BE INCLUDED IN THE PROJECT SCHEDULE AND IT IS THE EXPLICIT RESPONSIBILITY OF THE CONTRACTOR TO ASSURE THAT THE PROJECT SCHEDULE INCLUDES THE NECESSARY RELOCATION. THE CONTRACTOR WILL NOT BE PAID ADDITIONALLY FOR THIS COORDINATION. THE CONTRACTOR SHOULD SEEK ASSISTANCE FROM ALL UTILITY COMPANIES TO LOCATE AND PROTECT THEIR FACILITIES.
- 13. CONTRACTOR SHALL EXCAVATE ONLY AS MUCH TRENCH WHICH PIPE CAN BE INSTALLED AND
- 14. ALL UNDERGROUND UTILITY TRENCHES SHALL BE BACKFILLED WITH SAFE CLEAN FILL.
- 15. ALL INLETS AND DRAINAGE STRUCTURES TO BE INSTALLED WITH TRAPS.
- 18. "D" PERMITS ARE REQUIRED FOR ANY EXISTING SERVICE CONNECTIONS TO BE ABANDONED,

- ADJUSTED TO THE PROPOSED GRADE, UNLESS OTHERWISE INDICATED.
- 21. CONTACT STREET LIGHTING ENGINEER, KRISTEN DEL ROSSI, AT (215) 686-5517 TO COORDINATE LED LIGHT FIXTURE REPLACEMENT.
- 22. FLOW PRESSURE TO ALL FIRE HYDRANTS SHALL HAVE MINIMUM 600 GALLONS PER MINUTE AT MINIMUM RESIDUAL PRESSURE OF 20 POUNDS PER SQUARE INCH.
- HYDRANTS BE IN ANY WAY DAMAGED DURING CONSTRUCTION, THESE SHOULD BE REPAIRED ) THE SATISFACTION OF THE PWD INSPECTOR OR REPLAC
- 24. CONTRACTOR TO PROVIDE TEMPORARY LIGHTING FOR ANY STREET LIGHTS THAT ARE TEMPORARILY REMOVED OR TAKEN OUT OF SERVICE DURING CONSTRUCTION.
- 16. MAINTAIN AND PROTECT EXISTING INLETS. SHOULD EXISTING INLETS BE IN ANYWAY DAMAGED DURING CONSTRUCTION, THESE SHOULD BE REPAIRED TO THE SATISFACTION OF THE PWD INSPECTOR OR REPLACED PER PWD STANDARDS. CONTRACTOR MUST COMPLY WITH EROSION AND SEDIMENT CONTROL REQUIREMENTS
- AND 25 PA CODE CHAPTER 102 . SUFFICIENT EROSION AND SEDIMENTATION CONTROL MEASURES WILL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR AS TO PREVENT STANDING WATER OR SEDIMENTATION OF STORMWATER SYSTEMS. GREEN STORMWATER INFRASTRUCTURE SYSTEMS DETERMINED BY PWD TO BE INADEQUATELY PROTECTED AND THEREBY COMPROMISED
- REPLACEMENT) AT NO ADDITIONAL COST TO PWD. ). CONTRACTOR IS REQUIRED TO UNDERTAKE NECESSARY MEASURES TO PREVENT SEDIMENT FROM LEAVING THE WORK SITE, TO PREVENT EROSIVE CONDITIONS, AND TO SUPPRESS DUST ON THE SITE AND SURROUNDING AREAS. CONTRACTOR MUST COVER AND SURROUND STOCKPILES WITH EROSION CONTROL MEASURES TO ENSURE SEDIMEN
- CONTRACTOR IS HAND DIGGING OR EXCAVATING, CONTRACTOR MUST SWEEP WORK SITE AT THE END OF EACH WORK DAY. THE CITY MAY REQUIRE THE CONTRACTOR / OWNER TO CLEAN CITY-OWNED INLETS AND SYSTEMS AFFECTED BY NONCOMPLIANT OR FAILED E&S CONTROLS.
- OR WITHIN THE WORK AREA. INLET PROTECTION MEASURES MUST BE INSPECTED DAILY TO ENSURE PROPER PLACEMENT, AND MAINTAINED, POSITIONED OR REPLACED AS NEEDED TO ENSURE PROPER FUNCTION AND TO PREVENT FLOODING. REFER TO PWD GUIDANCE FOR APPROPRIATE MATERIALS AND PROTECTION METHODS FOR OPEN-MOUTH INLETS, HIGHWAY GRATE INLETS, TRENCH DRAINS AND CURB-CUT INLETS.
- ANY MATERIALS ON THE STREET. . ORIFICE SHOULD NOT BE DRILLED PRIOR TO AUTHORIZATION BY PWD. PWD WILL REVIEW THE RESULTS OF THE DOUBLE RING INFILTROMETER TESTS CONDUCTED AFTER SMP
- 23. EROSION CONTROL MATTING SHALL BE PLACED OVER ALL SOIL SURFACES NOT STABILIZED BY PLANTING.

PROPOSED LEG	SEND
	PROPOSED BUILDING
M	PROPOSED DOOR
4	PROPOSED CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
$\psi$ $\psi$ $\psi$	PROPOSED LANDSCAPED AREA
	PROPOSED UNIT PAVERS
	PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC
	PROPOSED SYNTHETIC TURF FIELD
2222222	PROPOSED ADA RAMP
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED STOP BAR/PAVEIVIENT MARKING
<u> </u>	
5	PROPOSED MAJOR CONTOUR
6	PROPOSED MINOR CONTOUR
	PROPOSED STORM INLET
Ø	PROPOSED STORM MANHOLE
0	PROPOSED STORM CLEANOUT
	PROPOSED STORM SEWER
s	PROPOSED SANITARY SEWER
w	PROPOSED WATER LINE
——— F ———	PROPOSED FIRE LINE
UG	PROPOSED NATURAL GAS LINE
UT	PROPOSED CABLE/TELEPHONE LINE
UE	PROPOSED ELECTRIC LINE
	PROPOSED LIMIT OF DISTURBANCE
	PROPOSED NPDES PROJECT SITE BOUNDARY
	PROPOSED CONSTRUCTION FENCE
	PAVEMENT DISCONNECTION
	ROOFTOP DISCONNECTION

![](_page_10_Picture_26.jpeg)

NOT FARE GONSURESTURE WORK ON NYS NPDES PERMIT #PAC510302

### UTILITY NOTES:

- ALL PIPE LENGTHS AND DISTANCES BETWEEN STRUCTURES ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE ALONG A HORIZONTAL PLANE. ALL STORM DRAINAGE PIPE SHALL BE LAID ON SMOOTH CONTINUOUS GRADES WITH NO VISIBLE BENDS AT JOINTS.
- BEDDING REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS ARE TO BE CONSIDERED AS MINIMUMS FOR RELATIVELY DRY, STABLE EARTH CONDITIONS. ADDITIONAL BEDDING SHALL BE REQUIRED FOR ROCK TRENCHES AND WET AREAS. CONTRACTOR SHALL HAVE THE RESPONSIBILITY TO PROVIDE SUCH ADDITIONAL BEDDING AS MAY BE REQUIRED TO PROPERLY CONSTRUCT THE WORK.
- COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF THEORETICAL MAXIMUM DRY DENSITY (ASTM D698). BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS AND SHALL BE PLACED IN LIFTS NOT TO EXCEED 6 INCHES IN COMPACTED FILL THICKNESS.
- THE CONTRACTOR WILL INSURE THAT POSITIVE AND ADEQUATE DRAINAGE IS MAINTAINED AT ALL TIMES WITHIN THE PROJECT LIMITS. THIS MAY INCLUDE, BUT NOT BE LIMITED TO. REPLACEMENT OR RECONSTRUCTION OF EXISTING DRAINAGE STRUCTURES THAT HAVE BEEN DAMAGED OR REMOVED OR REGRADING AS REQUIRED BY THE ENGINEER, EXCEPT FOR THOSE DRAINAGE ITEMS SHOWN AT SPECIFIC LOCATIONS AND HAVING SPECIFIC PAY ITEMS IN THE DETAILED ESTIMATE. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COSTS INCURRED TO COMPLY WITH THIS REQUIREMENT.
- EXISTING UTILITY LATERALS FOR THE PREVIOUS USE ARE NOT TO BE REUSED.
- CONTRACTOR MUST APPLY FOR ALL UTILITY CONNECTION APPLICATIONS.
- CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY CONNECTION FEES.
- UTILITY CONNECTION AND UTILITY COMPANY DETAILS FOR RECONNECTION AND NEW SERVICE WERE NOT PROVIDED BY THE UTILITY COMPANIES. CONTRACTOR MUST OBTAIN ANY UTILITY DETAILS FOR RECONNECTION OF EXISTING SERVICES OR NEW SERVICE AND IS RESPONSIBLE FOR THE CONSTRUCTION OF EACH NEW SERVICE PER THE APPROPRIATE UTILITY COMPANY'S SPECIFICATIONS.
- 10. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES AND TO TAKE WHATEVER STEPS NECESSARY TO PROVIDE FOR THEIR PROTECTION. THE ENGINEER HAS DILIGENTLY ATTEMPTED TO LOCATE AND INDICATE ALL EXISTING FACILITIES ON THESE PLANS; HOWEVER, THIS INFORMATION IS SHOWN FOR THE CONTRACTOR'S CONVENIENCE ONLY. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS OF UTILITIES SHOWN OR NOT SHOWN. THE CONTRACTOR SHALL CONTACT THE UTILITY COMPANIES FOR EXACT LOCATION OF THEIR UTILITIES PRIOR TO STARTING CONSTRUCTION. IT SHALL BE THE SOLE RESPONSIBILITY OF
- **GREEN STORMWATER INFRASTRUCTURE NOTE** THE CONTRACTOR PERFORMING THE GREEN STORMWATER INFRASTRUCTURE INSTALLATION MUST BE PREQUALIFIED BY THE PHILADELPHIA WATER DEPARTMENT (PWD) CONTACT MS. TRISHA GRACE OF THE PROJECTS MANAGEMENT UNIT AT (215) 685-6336. THE APPROVED WORK SHALL BE DONE IN THE PRESENCE OF A PWD INSECTOR. THE CONTRACTOR PERFORMING THIS WORK IS TO NOTIFY THE PWD CONSTRUCTION DIVISION,1101 MARKET STREET, 2ND FLOOR , PHONE (215) 685-6345, AT LEASET 7 DAYS IN
- ADVANCE FOR ASSIGNMENT OF AN INSPECTOR TO THE JOB. 4. THE CONTRACTOR MUST PROVIDE OFFICE SPACE FOR USE BY THE PWD INSPECTOR DURING CONSTRUCTION. 5. APPROVAL OF THESE PLANS BY THE WATER DEPARTMENT IS STRICTLY LIMITED TO THE DESIGN OF GREEN STORMWATER INFRASTRUCTURE SHOWN WITHIN THE LIMITS OF THE CITY OF PHILADELPHIA PUBLIC RIGHT OF WAY. 6. CONTACT PWD-WATER TRANSPORTATION RECORDS, 1101 MARKET STREET, 2ND FLOOR,
- PHONE (215) 685-6271, FOR ADDITIONAL APPROVALS AND PERMITS REQUIRED FOR ALL SEWER CONNECTIONS TO EXISTING AND/OR PROPOSED PWD FACILITIES. FIELD-FABRICATED WYE BRANCHES AND BENDS ARE NOT PERMITTED 8. A LIST OF ALL MATERIALS AND SUPPLIERS MUST BE SUBMITTED TO THE PWD CONSTRUCTION BRANCH FOR APPROVAL 9. THE CONTRACTOR OR ENGINEER IS RESPONSIBLE FOR OBTAINING ALL ADDITIONAL
- PERMITS AND APPROVALS FROM ALL AFFECTED CITY AGENCIES AND UTILITIES. 10. PRIOR TO OBTAINING A BUILDING PERMIT, THE CONTRACTOR IS REQUIRED TO OBTAIN PWD STORMWATER MANAGEMENT APPROVAL, AND SEWAGE FACILITIES PLANNING (ACT 537) APPROVAL 11. ANY CHANGE TO, OR DEVIATION FROM, THE FINAL APPROVED DESIGN PLANS DURING
- CONSTRUCTION MUST BE APPROVED BY THE ASSIGNED PWD-CONSTRICTION DIVISION ENGINEER AND BY THE PWD DESIGN PROJECT ENGINEER. 12. PWD RESERVES THE RIGHT TO REQUEST ADDITIONAL BORINGS DURING CONSTRUCTION SHOULD THE SOIL EXCAVATED IN THAT AREA APPEAR TO BE UNSUITABLE. 13. ANY TRENCH WHERE THE CUT IS DEEPER THAN 10 FEET WILL REQUIRE A DETAILED SHORING PLAN PREPARED BY A REGISTERED PROFESSIONAL ENGINEER TO BE
- SUBMITTED TO PWD FOR APPROVAL BEFORE WORK CAN BEGIN. I. PLACE AND COMPACT BACKFILL IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR EXCAVATION, REFILLING, GRADING, LANDSCAPING AND REPAVING. 15. ALL SIDEWALK AND CURBING TO BE REPLACED IN KIND ALONG FULL LIMITS OF
- CONSTRUCTION TO NEXT EXISTING JOINT OR AS DIRECTED BY PWD. EXISTING LEGEND

	EXISTING PROPERTY LINE (APPROXIMATE) EXISTING RIGHT OF WAY LINE (APPROXIMATE
///////	EXISTING BUILDING
	EXISTING CURB
A	EXISTING SIDEWALK
	EXISTING EDGE OF MACADAM/GRAVEL
	EXISTING TRAFFIC MARKING
××	EXISTING FENCE
and the second s	EXISTING TREE
	EXISTING MAJOR CONTOUR
4	EXISTING MINOR CONTOUR
	EXISTING SIGN
•	EXISTING BOLLARD
$\mathcal{A}$	EXISTING UTILITY POLE
¢ ≻—Ø	EXISTING LIGHT
	EXISTING INLET
<i>s</i>	EXISTING SEWER
<i>D</i>	EXISTING STORM SEWER
<i>W</i>	EXISTING WATER LINE
<i>UT</i>	EXISTING UNDERGROUND TELEPHONE LINE
<i>UG</i>	EXISTING GAS LINE
UE	EXISTING UNDERGROUND ELECTRIC
OE	EXISTING OVERHEAD WIRES
GV VENT	

E (₩ T S D EXISTING UTILITY STRUCTURES

EXISTING TREES FOR PAVEMENT DISCONNECTION TREE CALIPER DIAMETER SPECIES (IN) HONEY LOCUST 23.50 BLACK GUM 9.70 BLACK GUM 15.20

![](_page_11_Figure_0.jpeg)

![](_page_11_Figure_2.jpeg)

![](_page_11_Figure_4.jpeg)

 $\frac{1}{5}$ 

.7

![](_page_12_Figure_0.jpeg)

![](_page_12_Figure_3.jpeg)

![](_page_12_Figure_4.jpeg)

![](_page_12_Picture_6.jpeg)

![](_page_13_Figure_0.jpeg)

![](_page_13_Figure_1.jpeg)

![](_page_13_Figure_3.jpeg)

![](_page_13_Figure_4.jpeg)

![](_page_13_Picture_6.jpeg)

![](_page_14_Figure_0.jpeg)

- SHORING SHALL BE INSTALLED IN DITCHES AND TRENCHES AS PER OSHA REGULATIONS OR AS REGULATED BY PWD. VIOLATION OF THIS PROVISION WILL RESULT IN A STOP WORK ORDER AND/OR PENALTIES PRESCRIBED BY LAW. (REFER TO PHILADELPHIA PLUMBING CODE 2004 SECTION P- 1503.2 SHORING). 10. FOR CONNECTIONS TO BRICK SEWER, CONSTRUCT A 2-FOOT WIDE BY 8-INCH HIGH, CONCRETE CUTOFF WALL TO THE SPRING LINE, ON
- BOTH SIDES OF THE WYE, 12-INCH FROM THE LOCATION TO CUT THE SEWER PIPE. 11. USE A MINIMUM OF 3,500 PSI CONCRETE FOR THE CONCRETE CUT-OFF WALL.
- 12. ALLOW AT LEAST 24 HOURS FOR THE CONCRETE TO CURE BEFORE CUTTING THE SEWER PIPE.
- 13. CUT THE SEWER PIPE SO THAT THE WYE SECTION WILL FIT IN TIGHTLY. 14. PREVENT ANY DEBRIS FROM FLOWING INTO THE SEWER.
- 15. CLEAN THE BOTTOM OF THE OPENED AREA FROM LOOSE AND SOFT SOIL IF NO CRADLE, AND PLACE STONE IN THE MIDDLE LEAVING 12 INCH BELOW THE JOINTS FOR CONCRETE COLLAR.
- 16. INSERT THE WYE SECTION IN PLACE IMMEDIATELY, SEAL THE JOINTS AND CONSTRUCT A 24-INCH CONCRETE COLLAR AROUND BOTH JOINTS. 17. USE A MINIMUM OF 3,500 PSI CONCRETE COLLAR, 12 INCH DEEP AND EXTENDING 24 INCH WIDE AROUND THE JOINT.
- 18. ALLOW AT LEAST 24 HOURS FOR THE CONCRETE TO CURE BEFORE BACKFILLING. 19. ANY OTHER PIPELINE EXPOSED AND UNDERMINED DURING THIS OPERATION MUST BE SUPPORTED IMMEDIATELY AND BACKFILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM) AFTER THE COMPLETION OF THE CONNECTION.

![](_page_14_Figure_8.jpeg)

![](_page_14_Figure_9.jpeg)

![](_page_14_Figure_11.jpeg)

**DETAIL-** ORIFICE PROTECTION N.T.S.

1/2" EXPANSION JOINT MATERIAL **DETAIL-** CONCRETE CURB WALL AT PLAYGROUND

N.T.S.

PLAYGROUND SURFACE

OR CONCRETE

CONCRETE CURB WALL

VARIES, SEE GRADING PLAN

![](_page_14_Figure_14.jpeg)

![](_page_14_Figure_15.jpeg)

![](_page_14_Picture_16.jpeg)

![](_page_14_Figure_17.jpeg)

![](_page_14_Picture_20.jpeg)

![](_page_15_Figure_0.jpeg)

![](_page_15_Figure_1.jpeg)

![](_page_15_Figure_2.jpeg)

![](_page_15_Figure_3.jpeg)

![](_page_15_Figure_4.jpeg)

DETAIL- 18F ENVIROHOOD FOR FLAT CONCRETE

DETAIL- CHAIN LINK FENCE N.T.S.

08/28/23 NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

![](_page_15_Picture_22.jpeg)

![](_page_16_Figure_0.jpeg)

# NOT FOR CONSTRUCTION NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

![](_page_16_Picture_22.jpeg)

![](_page_17_Figure_0.jpeg)

![](_page_17_Figure_1.jpeg)

![](_page_17_Figure_2.jpeg)

DETAIL- UNDERGROUND BASIN N.T.S.

![](_page_17_Picture_5.jpeg)

![](_page_17_Figure_6.jpeg)

![](_page_17_Figure_17.jpeg)

![](_page_17_Figure_18.jpeg)

![](_page_17_Figure_19.jpeg)

— HDPE ACCESS RISER

— HDPE ACCESS RISER

- 12" HDPE PIPE

INV. IN 70.87

- 24" END STONE

ELEV. 78.30

 $\mathbf{X}\mathbf{X}$ 

2.00'

LANDSCAPING -

ELEV. 78.30

PLAN VIEW N.T.S.

- SYNTHETIC TURF FIELD

ACF R-TANK SD 7

51.61'

55.61'

<u>SECTION B-B</u> N.T.S.

122.11'

SECTION A-A N.T.S.

В 🖛 – 24" HDPE PIPE INV. IN 69.44

![](_page_17_Figure_25.jpeg)

![](_page_17_Figure_26.jpeg)

![](_page_17_Figure_27.jpeg)

![](_page_17_Picture_28.jpeg)

HANDRAIL NOTES:

- 1. ALL HANDRAILS AND HARDWARE TO BE HOT DIPPED GALVANIZED, PRIMED AND PAINTED. COLOR TO BE DETERMINED BY OWNER, PER SPECIFICATIONS.

![](_page_18_Figure_6.jpeg)

![](_page_18_Figure_7.jpeg)

![](_page_18_Figure_8.jpeg)

![](_page_18_Figure_9.jpeg)

![](_page_18_Figure_10.jpeg)

![](_page_18_Figure_14.jpeg)

**DETAIL-** PLAYGROUND RAMP AND RAILING 1"=1'.

HANDRAIL NOTES:

1. ALL HANDRAILS AND HARDWARE TO BE HOT DIPPED GALVANIZED, PRIMED AND PAINTED. COLOR TO BE DETERMINED BY OWNER, PER SPECIFICATIONS. 2. CONTRACTOR TO FIELD VERIFY DIMENSIONS AND ELEVATIONS OF FINISHED RAMPS PRIOR TO FABRICATION OF HANDRAILS. 3. CONTRACTOR TO SUBMIT COMPLETE SHOP DRAWINGS FOR LAYOUT, HANDRAILS AND COMPONENTS.

![](_page_18_Picture_20.jpeg)

![](_page_19_Figure_0.jpeg)

![](_page_19_Figure_1.jpeg)

![](_page_19_Figure_2.jpeg)

![](_page_19_Figure_3.jpeg)

![](_page_19_Figure_4.jpeg)

![](_page_19_Figure_5.jpeg)

![](_page_19_Figure_6.jpeg)

![](_page_19_Figure_7.jpeg)

DETAIL- PLAYERS' BENCHES N.T.S.

![](_page_19_Picture_9.jpeg)

![](_page_19_Figure_10.jpeg)

**DETAIL-** TRANSITION FROM ASPHALT TO CONCRETE PAVING

![](_page_19_Picture_13.jpeg)

![](_page_20_Figure_0.jpeg)

![](_page_20_Figure_1.jpeg)

![](_page_20_Figure_3.jpeg)

![](_page_20_Figure_4.jpeg)

D C B B 3 001

![](_page_20_Figure_6.jpeg)

![](_page_20_Figure_7.jpeg)

![](_page_20_Picture_9.jpeg)

![](_page_21_Figure_0.jpeg)

SHADE STRUCTURE PAD AND POST FOUNDATIONS

Electronic Timer Control - ET1725C

Electronic Timer Control - 7-Day 2-Circuit Electronic Control, 120-277 VAC, 2-SPST, Indoor Metal Enclosure Item ET1725C

	PRODUCT DESCRIPTION								
	This series offers an easy way to upgrade from a basic mechanical time switch to an electronic time switch. These timers will allow for up-to-the-minute programming, battery backup for power loss, up to 28 events total, and automatic daylight saving time corrections without the need of user interaction. They come in standard 24-hour, 7-day and 7-day astronomic versions. FEATURES Selector switch to determine input voltage between 120-277 VAC								
(International States of London	<ul> <li>Up to 28 events total</li> </ul>								
	<ul> <li>To-the-minute accuracy</li> </ul>								
Contraction of States and States	<ul> <li>Temporary override or permanent manual override</li> </ul>								
	<ul> <li>Automatic Daylight Saving Time adjustment</li> </ul>								
	<ul> <li>Astronomic models enable dusk-to-dawn scheduling</li> </ul>								
<b>G</b> . <b>B</b>	APPLICATIONS								
	<ul> <li>Indeor Lighting Control</li> </ul>								
	► Timing/Scheduling ON/OFF								
	<ul> <li>Machinery &amp; Pump Controls</li> </ul>								
TECHNICAL DATA									
Seneral									
Aodel Number	ET1725C								
Description	7-Day 2-Circuit Electronic Control, 120-277 VAC, 2-SPST, Indoor Metal Enclosure								
IPC Code	078275109865								
Irand	Intermatio								
Country of Origin (Intermatic)	CHINA								
Varranty Period	t-Year limited								

Warranty Period	1-Year limited
Control Specifications	
Minimum ON/OFF Times	t min
Minimum Pulse Time	2 sec
Maximum Pulse Time	2 sec.
Maximum ON/OFF Times	Indefinițe
Maximum ON/OFF Operations	28
Setpoint Program Count	28
ON/OFF Operations	28
Operation Mode	7 day
Daylight Savings Adjustment	Automatic
Васкир Туре	Battery
Battery Type	AAA
Battery Service Type	Field Serviceable
Mechanical Specifications	
Enclosure Type	Indoor type 1 metz

PRODUCT CUT SHEET - LIGHT TIMER/DIMMER

Technical specifications and other information are subject to change without notice. Images can vary from original

![](_page_21_Figure_7.jpeg)

PRODUCT CUT SHEET - LED LIGHT FIXTURE

- SHADE STRUCTURE NOTES:
  - 1. COMFORT STATION SHADE STRUCTURE IS TO BE 20' OCTAGON SHELTER AS MANUFACTURED BY POLIGON (POLIGON.COM), MODEL #OTC20. - SINGLE TIER - STANDING SEAM ROOF
  - 2. THE LAYOUT PROVIDED IS FOR INFORMATION ONLY. REFER TO WRITTEN INSTALLATION INSTRUCTIONS FROM POLIGON FOR DETAILED LAYOUT PLAN, COLUMN SPACING, TEMPLATES, AND LAYOUT INSTRUCTIONS FOR THE COLUMNS AND ANCHORS.
  - 3. STEEL POWDERCOAT AND ROOF COLORS TO BE SELECTED BY OWNER.

![](_page_21_Figure_13.jpeg)

![](_page_21_Figure_14.jpeg)

![](_page_21_Figure_15.jpeg)

![](_page_21_Figure_16.jpeg)

# PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23 NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

Introduction The all new VCPG LED (Visually Comfortable Parking Garage) luminaire is designed to bring glare control, optical performance and energy savings into one package. The recessed lens design of VCPG LED minimizes high angle glare, while its precision molded acrylic lens eliminates LED pixilation and delivers the required		VCPGB05 YK H VCPGB05 YK H VCPGUBD5 DW VCPGUBD5 YK VCPGSRM U VCPGSC120	ND U Bird WHXD U Bird HXD U Bird DWHXD U Bird Surf Surf Safe	shroud for PM (spe shroud for PK with shroud for YK with ace mount kit, wit ace mount kit, wit ty cable 120"	ecity finish) scify finish) h Up-Light (s h no Up-Light (s h no Up-Light	specify finis pecify finis nt	5 h) 5 i) 1 i	VCPGWG U SLVSQ SLVRD VCPG YK DW SSXWBA DW VCPGHS.DW	VHXD U VHXD U HXD U	Wire guard Quick mour Quick mour Yoke mour Yoke mour RSX WBA w House side	nt pendant sv nt pendant sv t kit (specify i all bracket (s shield (specif	vivel kit, square vivel kit, round inish) pecify finish) y finish)	3 Or PA 4 No: 5 EB 6 E8 7 DA 8 No: 8 No: 8 No: 8 No: 9 State 8	nly vertical heigh V and SLVSQ of 1 inopies. et available with 34 WC and £10WH or WC & E10WH orly WG option not avai mtrols. eeds an nLight A e group. VCPG N . NPS devices.	t adjustm LVRD for Ny rated u available able with r Normal LTAIR2 P	ent. No i mountin p to 35°C with P1-P4 standaloon Power S IR and P	angle ad ng to ang ambient 4 package e or netwo ensing (I RH devi	justment. Us jied ceiling c rs. orked sensorsi NPS) device ces cannot a	
angle glare, while its eliminates LED pixila	s precision molded ation and delivers th	acrylic lens ne required	Perfor	mance D	ata	1						_							
minimums, verticals up-light module opt the luminaire and th	and uniformity. The tion reduces the cor e ceiling creating a	dedicated htrast between more visually	Lumen O	utput Lume with	n values are from a the tolerarices all	phetometric t owed by Ligh	tests perfor vting Facts.	ned in acco Contact fac	rdance with tory for per	IESNA LM formance da	79-08. Data ata on any c	is contidered onfigurations	I to be representat not shown here.	ive of the co	infigurations shown				
comfortable environ	fortable environment.		Parkage	WILL	type -	Lamens	LFW	Limmas	LPW	Lamoto	.70 CMD	Lumers	LEW-	2	Up-light Lu	men C	Output	t.	
The VCPG LED deliv	vers up to 87% in er	iergy savings			TSE	3,581	135	3,670	138	3,815	144	3,876	146		Up-light Option	Wa	ui (	luman	
when replacing 175V	W metal halide lumi	naires. With over	01	3714	T5M	3,620	136	3,710	140	3,856	145	3,917	347		UPL1	6,5	W	519	
peration), the VCP(	G LED luminaire pro	ovides significant	5.1	2/4	TSR	3,592	130	3,08	139	3,62/	199	3,588	140	1	UPL2	8.5	W	715	
naintenance savings over traditional luminaires.	minaires.			LANE	3,507	132	3,594	135	3,736	141	3,796	143							
					15E	4,577	135	4,691	138	4,876	744	4,954	146		Lumen Mul	tiplier	for 80	OCRI	
		Contract And Contractor	1.0		TSM	4,626	136	4,741	140	4,928	145	5,007	147			1			
LED V4 P4 40K	70CRI T5M MVC	LT SRM DNAXD	P2	34W	15W	4,591	135	4,705	139	4,891	144	4,968	241		300	Mult	74		
				LANE	4,482	132	4,594	135	4,775	132	4,851	143	-	SUK	.0.9	20			
					15E	5,808	134	5,952	137	6,187	143	6,286	145	-	35K	0.9	45		
	Vauraning				TSM	5,870	135	6,015	139	6,253	144	6,353	146		408	0.9	67		
			P3	43W	T5W	5,825	134	5,970	138	6,205	143	6,304	145		SOK	0.9	65		
For ordering with fuse	Shipped included				LSR	5,617	130	5,757	133	5,984	738	6,079	140						
120	PM Pendant mount standar	ndant mount standard (24-inch length supply leads)		-	TSE	7 301	131	5,829	134	7 874	140	0,133	142						
208	ordering with fuse Shipped included PM Pendant mount standard (24-inch length supply leads) SRM Surface mount (24-inch length supply leads) ARM Arm mount (use R5XWBA accessory to mount to a wall) Shipped separately VV Valorheading mount			TSM	7,470	133	7,656	136	7,958	141	8,085	144							
240		A accessory to mount to a wall)	.P4	56W	T5W	7,414	132	7,597	135	7,898	140	8,023	143						
177					T5R	7,149	127	7,326	130	7,615	135	7,737	137						
347	Shipped separately				LANE	7,238	129	7,418	132	7,711	137	7,834	139						
480	YK Yoke/trunnion mount				TSM	10,189	124	10,442	12/	10,854	132	11,027	134						
· · · ·		o (zmmith ingen oughly leads) ) length supply leads) BA accessory to mount to a wall)	95	870/	TSW	10,298	123	10,335	128	10,970	134	11,145	130						
					TSR	9,855	120	10,099	123	10,498	128	10,665	130						
	Links mount	Packaging			LANE	9,978	121	10,226	124	10,629	129	10,799	131						
	THE PERSON NEW YORK	a standard and			TSE	12,878	120	13,197	123	13,719	127	13,937	129						
	DWHXD White	(blank) Job Pack/Units	P		TSM	13,015	121	13,338	124	13,865	129	14,086	131						
or 8-15' mounting heights	DNAXD Natural	Iships as job nack of 18oxs	PG	108W	TSW	12,917	120	13,237	123	13,760	128	13,979	130						
ir 15-30 mounting heights	aluminum	per; balance in			15R	12,455	116	12,764	119	13,268	123	13,480	125						
x 8-15' mounting heights, ad 75% Loss autout	DELAD DIAL	units)			TSE	15.503	125	15.887	120	16,435	133	15,099	135						
for 15-30/mounties helphic	VOLAU DIALK	U Unit packs only	97	†22W	T5M	15,668	126	16,057	129	16,691	135	16,957	137						
nd 35% light output					TSW	15,549	125	15,935	129	16,564	134	16,828	136						
oled motion/attibient sensor-			Lumen Ar (LAT) Mul	nbient Ten tipliers	perature	5	Project	ed LEC	D Lume	n Main	tenanc projections	C for the platfo	(IT'S	Electric	cal Load		Que	unt (Å)	
bled motion/ambient sensor			Use these factors average ambient	to determine rela temperatures fro	tive lumen output n 0:40°C (32-104°F	for i	ESNA LM-8	0-08 and pr	ojected per	IESNA TM	21-171	a second		Tablage:	Watt 120V	2052	LAUV	100	34/10 -18
ghts and all 000 a literature must			Loblard	11000	Malthellas	1	lo calculate desired num	ber of oper	ating hours	below, For a	other lumen	maintenance	ne values,	P1	27W 0.22	0.13	0.12	0.10	0.08 0.0
valuiting heights ¹			0"0	32°F	.03	c	contact facto	ny.	-	a 1 -	in non	50.070 L	00.000	PZ	34W 0.28	0.16	0,14	0.13	0.10 0.0
ed, UL924 Listed motion/			10°C	50°F	.02		Lonnelle	ntermask	acim	1.0	0.97	0.94	0.89	P3	43W 0.37	0.21	0,18	0.16	0.13 0.0
mounting heights."			20*0	58°F	.01		and the second	Col Intel	20101		and I			P4	56W 0.48	0.28	0.24	0.21	0.16 0.1
			25°C	77"F	1									P5	82W 0,68	0.40	0.35	0.30	0.24 0.1
			30°C	6 F (	.99									P6	108W 0.91	0.57	0.45	0.39	0.32 0.1
			40 L	unit 1	.70									07	174W 1.02	0.50	0.51	DAA	0.17 0.2
	1													11	12497 1.05	0.09	1 4.31	1.444	1.0.31 1.1

Technical specifications and other information are subject to change without notice. Images can vary from original

Accessories

**Ordering Information Cont.** 

næ i	nput voltage between 120-277 VAC
na	nent manual override
Tin	ne adjustment
GU	sk-to-tawn scheuting
5	
s	
	ET1725C
	7-Bay 2-Circuit Electronic Control, 120-277 VAC, 2-SPST, Indoor Metal Enclosure
	078275109865
	Intermatio
	CHINA
	1-Year limited
	1 min
	2 sec
	2 sec
	Indefinite
	28
	28
	28
	7 day
	Automatic
	Battery
	дад
	Field Serviceable
	A COMPANY AND A CO

@ 02/27/2023 1/4

Tungsten Range(s)	5 A, 120-240 VAC	
Electronic Ballast Load Ratings Ranges	1 A, 120-277 VAC	
Magnetic Ballast (NO) Range(s)	20 A, 120-277 VAC	
Resistive (NO) Range(s)	28 A, 28 VDC, 30 A. 120/240 VAC	
Inductive Load Batings NO Ranges	30 A, 120/240 VAC	
Resistive Load Ratings Ranges	20 A, 28 VDC; 30 A, 120/240 VAC	
Tungsten (NO) Range(s)	5 A, 120/240 VAC	
Motor Load Ratings Ranges	1 HP, 120 VAC; 2 HP, 240 VAC	
Motor Load Ratings NO Ranges	T HP, 120 VAC; 2 HP, 240 VAC	
Electrical Specifications		
Voltage Selection Type	Selector Switch	
Wiring Option	Terminals	
Input Voltage Range(s)	120-277 VAC, 50/60 Hz	
Number of Circuits	2	
Switch Type	2xSPST, 1xDPST or Pulse	
Maximum Power Consumption (W)	6 W	
Electronic Series	ET1700 Series	
Packaging		
Unit Carton Dimensions (H x W x L) in	.3.131 x 5.251 x 8.001 in	
Environmental Specifications		
Temperature (operation)	-40 °F to 104 °F / (-40 °C to 40 °C)	
Standards and Certifications		
CSA Centrication	cCSAus	
Other Certifications and Compatibilities	Title 20	
Catifornia Proposition 65	Leat	

NTERMATIC

Electronic Timer Control - ET1725C

Product Dimensions (H x W x D) In

Knockey! Dimensions Bottom

Knockout Dimensions Back

Wire Size Min

Wire Size Max

Load Ratings

7.875 x 5.125 x 3.4375 in

(2) combination 1/2" - 3/4"

(1) combination 1/2" - 3/4"

W14 AWG

#8 AWG

![](_page_21_Picture_26.jpeg)

@ 02/27/2023 2/4

NOTES 1 P1-P6 not available with V8. P7 not available with V4.

![](_page_21_Figure_27.jpeg)

![](_page_22_Figure_0.jpeg)

SSING AVE IA, PA 19143	EXISTING LEGEND	PROPOSED LEG	END
500	EXISTING PROPERTY LINE (APPROXIMATE)		PROPOSE
	—— — — — — EXISTING RIGHT OF WAY LINE (APPROXIMATI	M	PROPOSE
ADEI PHIA	EXISTING BUILDING	4 4	PROPOSE
RECREATION	EXISTING CURB		PROPOSE
TREET, 10TH FLOOR	EXISTING SIDEWALK	$\vee$ $\vee$ $\vee$	PROPOSE
	EXISTING EDGE OF MACADAM/GRAVEL		PROPOSE
R:	EXISTING TRAFFIC MARKING		PROPOSE
SOICATES	——×———×—— EXISTING FENCE		PROPOSE
T STREET, SUITE 300	EXISTING TREE	Kosters.	PROPOSE
IA, PA 19103	TOP EXISTING THEE		PROPOSE
	EXISTING MAJOR CONTOUR		PROPOSE
ICES:	EXISTING MINOR CONTOUR		PROPOSE
	- EXISTING SIGN		PROPOSE
MERICAN ENGINEERS GROUP, LLC ENTITLED	EXISTING BOLLARD		PROPOSE
SING RECREATION CENTER TOPOGRAPHIC SURVEY",	C EXISTING UTILITY POLE	—	PROPOSE
. 1, DATED 03/12/2021.	☆ ፦—── EXISTING LIGHT	5	<b>PROPOSE</b>
		6	PROPOSE
	<i>s EXISTING SEWER</i>		PROPOSE
	────	O	PROPOSE
	——— w ——— EXISTING WATER LINE	0	PROPOSE
	EXISTING UNDERGROUND TELEPHONE LINE		PROPOSE
	UG EXISTING GAS LINE	S	PROPOSE
	UE EXISTING UNDERGROUND ELECTRIC	W	PROPOSE

<b>P</b> 1.	AN INDUSTRIAL WASTE PERMIT WILL BE REQUIRED SHOULD PUMPING TO CITY-OWNED INFRASTRUCTURE BECOME NECESSARY DURING CONSTRUCTION. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN. OVER LINDISTLIRBED VEGETATED AREAS
2.	INLET PROTECTION SHOULD BE PROVIDED FOR ALL INLETS OWNED BY PWD THAT ARE LOCATED WITHIN ONE BLOCK OF THE PROJECT SITE.
3. 4.	PWD IS NOT RESPONSIBLE FOR ANY CLEANING OR REPAIRS NEEDED ON CITY-OWNED INFRASTRUCTURE DUE TO FAILURE OF ANY EROSION AND SEDIMENT CONTROL PRACTICES. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY CLEANING OR REPAIRS NEEDED. INSPECTION AND MAINTENANCE OF ALL EROSION AND SEDIMENT BEST MANAGEMENT PRACTICES SHALL OCCUR ON A WEEKLY BASIS. BEFORE ANY ANTICIPATED PRECIPITATION EVENTS. AND
5.	AFTER ALL PRECIPITATION EVENTS. THE MAXIMUM HEIGHT FOR STOCKPILES AREAS SHALL BE 20 FEET. THE MAXIMUM SIDE SLOPE FOR STOCKPILE AREAS SHALL NOT EXCEED 2:1.
6.	THE ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED ON-SITE. A STOCKPILE SHALL BE MAINTAINED ON-SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
7.	FILTER FABRIC FENCE AND/OR COMPOST FILTER SOCK SHOULD BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE/SOCK SECTION SHOULD BE EXTENDED AT LEAST & FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. SUPPORT STAKES SHALL BE SPACED AT A MAXIMUM OF & FEET. OBJECTS OF CONSIDERABLE MASS (E.G. CONCRETE BLOCKS, SAND BAGS, ETC.) SHALL BE USED IMMEDIATELY DOWNSLOPE OF COMPOST FILTER SOCKS PLACED ON PAVED SURFACES IN LIEU OF STAKES TO HOLD THE SOCK IN PLACE. OBJECTS TO BE PLACED AT INTERVALS PER THE COMPOST FILTER SOCK MANUFACTURER'S SPECIFICATION OR PA DEP MAXIMUM SPACING OF 10' ON CENTER. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FILTER FENCE/FILTER SOCK.
8.	ANY FENCE/SOCK SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.
9.	EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS.
11.	APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY PWD AND PA DEP. UNTIL THE SITE IS STABILIZED, ALL E&S BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL E&S BMPS PRIOR TO ANY ANTICIPATED STORM EVENT, AFTER
12.	EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED, WILL BE REQUIRED. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING, AS WELL AS CUTS AND FILLS, SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. PWD SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. PWD MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
13.	AT LEAST THREE(3) DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
14.	ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING BY PWD AND THE PA DEP PRIOR TO IMPLEMENTATION.
15. 16.	AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING, AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE HAVE BEEN INSTALLED AND ARE FUNCTIONING
17.	AS DESCRIBED IN THIS E&S PLAN. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF REFORE CLEARING AND GRUBBING OPERATIONS REGIN
18.	A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO PWD AT THE TIME OF INSPECTION.
19. 20	ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL STATE, FEDERAL, AND LOCAL REGULATIONS. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF THREE TO FIVE INCHES SIX TO 12 INCHES ON COMPACTED SOILS PRIOR TO PLACEMENT OF TOPSOIL. AREAS
21	TO BE VEGETATED SHALL HAVE A MINIMUM FOUR INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF TWO INCHES OF TOPSOIL. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE, OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES, AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
22 23	ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED NINE INCHES IN THICKNESS. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF
24	SATISFACTORY FILLS. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.
25 26	FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED
27	METHOD. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED.
28	MMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN ONE YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN ONE YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.
29	PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
30	E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY PWD AND PA DEP.
32	PRACTICES. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE E&S BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON. SEDIMENT BASINS AND/OR TRAPS SHALL BE KEPT FREE OF ALL CONSTRUCTION WASTE, WASH WATER, AND OTHER DEBRIS HAVING POTENTIAL TO CLOG THE BASIN/TRAP OUTLET STRUCTURES
33	AND/OR POLLUTE THE SURFACE WATERS. DURING CONSTRUCTION, THE SELECTED CONTRACTOR IS EXPECTED TO FOLLOW THE PCSMP APPROVED BY PWD. NO CHANGE OR DEVIATION FROM THE APPROVED PCSMP IS PERMITTED WITHOUT PRIOR APPROVALEROM PWD
34	ALL WORK ASSOCIATED WITH PWD WATER CONVEYANCE AND SEWER INFRASTRUCTURE SHALL BE DONE IN ACCORDANCE WITH THE CITY OF PHILADELPHIA WATER DEPARTMENT "WATER MAIN STANDARD DETAILS AND CORROSION CONTROL SPECIFICATIONS", 1985 EDITION, AND "STANDARD DETAILS AND STANDARD SPECIFICATIONS FOR SEWERS", 1985 EDITION.
35	CONTACT PWD WATER TRANSPORT RECORDS (1101 MARKET STREET, 2ND FLOOR, PHONE: 215-685-6271) FOR ADDITIONAL APPROVALS AND PERMITS REQUIRED FOR ALL WATER SERVICES, METERS, AND CONNECTIONS TO THE EXISTING AND/OR PROPOSED PWD FACILITIES.
36 37	ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE PADEP'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET SEQ., 271.1, AND 287.1 ET SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE. A DUST CONTROL PERMIT WILL BE REQUIRED WHEN COMPLETELY DEMOLISHING A BUILDING OR STRUCTURE THAT IS MORE THAN THREE (3) STORIES, GREATER THAN FORTY (40) FEET TALL, OR ENCOMPASSES MORE THAN TEN THOUSAND (10,000) SQUARE FEET; COMPLETELY OR PARTIALLY DEMOLISHING ANY BUILDING OR STRUCTURE BY IMPLOSION; OR ENGAGING IN EARTHWORKS, DEFINED AS "CI FARING, GRUBBING, OR FARTH DISTURBANCE OF ANY LAND IN EXCESS OF 5 000 SQUARE FEET."
D	UST CONTROL MEASURES:
1. 2.	FUGITIVE DUST FROM CONSTRUCTION, DEMOLITION, AND EARTHWORKS ACTIVITIES MAY NOT BE VISIBLE AT THE POINT IT PASSES THE WORK SITE PROPERTY LINE.
3. 4.	APPLICATION OF WATER OR APPROVED DUST SUPPRESSANT TO A WORK SITE WITH ONGOING EXCAVATION, LAND CLEARING, DEMOLITION, OR OTHER EARTH DISTURBANCE RELATED ACTIVITIES TO SUPPRESS DUST FORMATION. GENERAL PROHIBITION AGAINST DRY ABRASIVE BLASTING OF EXTERIOR SURFACES OPEN TO THE OUTSIDE AIR WHEN TEMPERATURE IS ABOVE FREEZING.
5. 6	COVERING AND WETTING OF STOCKPILE EARTH, SAND, GRAVEL, AND OTHER SIMILAR CONSTRUCTION MATERIALS.
7.	DROPPED, AND / OR EXIT OF CHUTE MUST BE SEALED AGAINST THE TOP OF THE RECEIVING CONTAINER / DUMPSTER. ALL TEMPORARY PERIMETER FENCING AROUND MUST HAVE A DUST CONTROL FABRIC; MUST MEASURE A MINIMUM OF 5FT IN HEIGHT FROM THE BOTTOM OF THE FENCING.
8. 9	A 10 MILE PER HOUR SPEED LIMIT FOR ALL EQUIPMENT AND TRUCKS TRAVELING WITHIN THE WORK SITE.
10. <b>TI</b>	VEHICLE ACCESS POINTS MUST BE EQUIPPED WITH DUST SUPPRESSION MEASURES (I.E. WHEEL WASH SYSTEMS, RUMBLE GRATES, AND OR GRAVEL PADS).
1.	INLET PROTECTION SHALL BE APPLIED, AS DETAILED ON THE PLAN, TO EVERY INLET WHICH HAS BEEN CONSTRUCTED TO THE ROADWAY SUBBASE ELEVATION. INLET PROTECTION MUST BE PROVIDED FOR ALL CITY OWNED INLETS LOCATED WITHIN ONE CITY BLOCK OF THE PROJECT SITE.
2.	SILT FENCES/COMPOST FILTER SOCKS SHALL BE INSTALLED DOWNSLOPE OF ALL AREAS TO BE DISTURBED BEFORE ANY WORK BEGINS. SILT FENCE/COMPOST FILTER SOCKS AND ROCK FILTERS SHALL BE INSTALLED AS NEAR AS POSSIBLE TO THE LOCATIONS SHOWN ON THE PLAN. FILTER FABRIC/COMPOST FILTER SOCKS SHOULD BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION SHOULD BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. SUPPORT STAKES AND/OR OBJECTS OF CONSIDERABLE MASS SHALL BE SPACED AT A MAXIMUM OF 8 FEET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FILTER FENCE/FILTER SOCK.
3. ⊿	STOCKPILED TOPSOIL MOUNDS SHALL BE STABILIZED BY APPLYING TEMPORARY SEED AND A PERIMETER SILT FENCE/FILTER SOCK SHALL BE INSTALLED AROUND EACH MOUND. TEMPORARY SEEDING SHALL BE PER PENNDOT FORM 408, SECTION 804(B).
4.	CONSTANTLY MAINTAINED ON SITE. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.
5.	FREQUENT INSPECTION SHALL BE MADE ON THE FILTER FABRIC FENCE/COMPOST FILTER SOCK. DAMAGED FENCES/SOCK SHALL BE IMMEDIATELY REPLACED. SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHTS OF FENCE/SOCK. SILT FENCE/COMPOST FILTER SOCK WHICH HAS BEEN TOPPED OR UNDERMINED IS TO BE REPLACED WITH A ROCK FILTER OUTLET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.
<b>PI</b> 1.	ROCEDURE FOR STABILIZATION OF SOILS FOUND OR SUSPECTED TO BE CONTAMINATED: DISTURBED EARTH TO BE IMMEDIATELY STABILIZED WITH SEEDING THROUGH THE USE OF HYDROSEEDING TECHNIQUES AND HAY OR STRAW MULCHING TO CONTAIN CONTAMINATED SOILS.
2.	PLASTIC LINER TO BE INSTALLED BELOW TEMPORARY TOPSOIL STOCKPILES. TOPSOIL STOCKPILE TO BE STABILIZED WITH SEEDING AND TO BE COVERED BY A TEMPORARY DAILY COVER IMMEDIATELY PER THE REQUIREMENTS OF THE PADEP E&S GUIDELINES.
3. 4.	UTILIZE APPROVED PA DEP EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT SOIL FROM LEAVING THE SITE. METHODS INCLUDE, BUT ARE NOT LIMITED TO WHEEL WASH, SILT FENCE, INLET FILTER PROTECTION, ROCK CONSTRUCTION ENTRANCE, ETC.
Ρ	WD STANDARD SEQUENCE OF CONSTRUCTION NOTES:
1. 2	AT LEAST SEVEN (7) DAYS PRIOR TO ANY EARTH DISTURBANCE, THE INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) MUST BE CALLED TO SCHEDULE A PRECONSTRUCTION MEETING.
∠. 3.	ALL STONE THAT MAKES UP THE (SUBSURFACE DETENTION BASIN) MUST REMAIN FREE OF SEDIMENT. IF SEDIMENT ENTERS THE STONE, THE CONTRACTOR MAY BE REQUIRED TO REMOVE THE
4.	SEDIMENT AND REPLACE IT WITH CLEAN-WASHED STONE.
5.	AS SOON AS SLOPES, CHANNELS, DITCHES, AND OTHER DISTURBED AREAS REACH FINAL GRADE, THEY MUST BE STABILIZED. CESSATION OF ACTIVITY FOR FOUR (4) DAYS OR LONGER REQUIRES TEMPORARY STABILIZATION.
6. 7	THE NPDES NOTICE OF TERMINATION (N.O.T.) MUST BE SUBMITTED TO PA DEP UPON COMPLETION OF CONSTRUCTION (WHEN APPLICABLE).
1.	WATEN FUNIFED FROM WORK AREAD DOULD BE TREATED FOR SEDIMENT REMOVAL PRIOR TO DISCHARGING TO A "SURFACE WATER" (WHEN APPLICABLE).

**SEQUENCE OF CONSTRUCTION:** ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE AND SHALL BE COMPLETED IN COMPLIANCE WITH PHILADELPHIA WATER DEPARTMENT AND CHAPTER 102 REGULATIONS AT LEAST 7 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LAND OWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND A REPRESENTATIVE FROM THE PHILADELPHIA WATER DEPARTMENT TO SCHEDULE A PRE-CONSTRUCTION MEETING. ALSO, AT LEAST 3 WORKING DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM, INC. AT 1-800-242-1776 FOR BURIED UTILITY LOCATIONS. BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE PHILADELPHIA WATER DEPARTMENT AND PA DEPT. OF ENVIRONMENTAL PROTECTION (PADEP). THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 et seg. AND 287.1 et seg THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED. APPROVED BY THE PHILADELPHIA WATER DEPARTMENT AND PADEP AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL PROPOSED SOIL/ROCK SPOIL AND BORROW AREAS ON OR OFESITE 1. CONSTRUCTION WILL BEGIN UPON RECEIPT OF ALL REQUIRED PERMITS FROM CITY OF PHILADELPHIA AND PADEP. 2. PRIOR TO PROCEEDING WITH CONSTRUCTION. CONFIRM THE LOCATION AND ELEVATION OF ALL EXISTING UTILITIES. MAINTAIN AND PROTECT ALL EXISTING UTILITIES TO REMAIN AT ALL TIMES. 3. AS SOON AS SLOPES, CHANNELS, DITCHES, AND OTHER DISTURBED AREAS REACH FINAL GRADE, THEY MUST BE STABILIZED. CESSATION OF ACTIVITY FOR FOUR (4) DAYS OR LONGER REQUIRES TEMPORARY STABILIZATION. 4. WATER PUMPED FROM WORK AREAS SHOULD BE TREATED FOR SEDIMENT REMOVAL PRIOR TO DISCHARGING TO A "SURFACE WATER". 5. DISTURBANCE OF THE PROJECT SITE MUST BE KEPT TO THE ABSOLUTE MINIMUM. 6. ALL SOIL MOVEMENT SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND APPLICABLE MUNICIPAL, STATE, AND FEDERAL REGULATIONS. 7. EXISTING PEDESTRIAN TRAFFIC SHALL BE MAINTAINED OR PROPERLY DIRECTED AROUND THE SITE THROUGHOUT THE DURATION OF THE PROJECT. 8. DELINEATE LIMITS OF DISTURBANCE AS OUTLINED ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLANS WITH ORANGE CONSTRUCTION FENCING. LINEAR UTILITY TRENCHES, AS OUTLINED ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLANS, DO NOT NEED TO BE DELINEATED WITH FENCE. UTILITY TRENCHES SHALL BE BACKFILLED AT THE END OF EACH DAY AND TEMPORARILY STABILIZED. CONTRACTOR SHALL NOT PERFORM ANY OTHER WORK OUTSIDE OF THE APPROVED LIMITS OF DISTURBANCE 9. INSTALL INLET PROTECTION. 10. INSTALL ROCK CONSTRUCTION ENTRANCE AT THE SITE ENTRANCE AS SHOWN ON THE APPROVED PLAN. EXISTING SUBGRADE TO BE REMOVED WITHIN THE FOOTPRINT OF THE ROCK CONSTRUCTION ENTRANCE FOR CONSTRUCTION PER THE APPROVED DETAIL. CONTRACTOR SHALL EXCAVATE ONLY ENOUGH AREA FOR WHICH ROCK CONSTRUCTION ENTRANCE CAN BE INSTALLED BY THE END OF EACH WORK DAY. CONSTRUCTION VEHICLES SHALL ENTER AND EXIT THE SITE THROUGH THE ENTRANCE. ROCK CONSTRUCTION ENTRANCE TO BE RESTORED AND SEDIMENT IS TO BE REMOVED ON A DAILY BASIS. 11. INSTALL COMPOST FILTER SOCK DOWN GRADE AND ON CONTOUR OF DISTURBED AREAS PER THE APPROVED PLAN. DISTURBED AREAS SHALL BE IMMEDIATELY STABILIZED AND GRADED TO SLOPE TOWARDS THE SITE AND COMPOST FILTER SOCK. 12. STAKE OUT AND INSTALL ORANGE CONSTRUCTION FENCE AROUND THE LIMITS OF ANY PROPOSED, OR EXISTING TO BE PROTECTED, INFILTRATION AREA (TREE TRENCHES AND RAIN GARDENS). CONTRACTOR TO MINIMIZE THE COMPACTION OF SOIL WITHIN THE INFILTRATION AREA. HEAVY MACHINERY IS PROHIBITED TO ENTER WITHIN THE LIMITS OF THE PROPOSED INFILTRATION AREA. 13. THE STAGING AREA SHALL BE ESTABLISHED ON THE SITE AND SHALL NOT IMPEDE RUNOFF FROM REACHING THE EXISTING INLETS. STAGING AREAS NOT CREATED ON EXISTING PAVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPROVED DETAIL. 14. CONCRETE WASHOUT TO BE INSTALLED ADJACENT TO THE ROCK CONSTRUCTION ENTRANCE PER THE APPROVED PLANS. 15. CONTRACTOR SHALL TEMPORARILY STABILIZE THE SITE AT THE END OF EACH WORK DAY (WHENEVER POSSIBLE) AND AT THE START OF A RAINFALL EVENT. CESSATION OF EARTH DISTURBANCE ACTIVITIES FOR AT LEAST 4 DAYS REQUIRES TEMPORARY STABILIZATION. 16. CONTRACTOR TO HAVE PUMPED WATER FILTER BAG ONSITE AND AVAILABLE FOR DEWATERING OF EXCAVATED AREAS WHEN REQUIRED. FILTER BAG TO DISCHARGE OVER UNDISTURBED VEGETATED AREAS IN ACCORDANCE WITH THE APPROVED PLANS. 17. CONTRACTOR TO BEGIN DEMOLITION OF THE REMAINING EXISTING SITE FEATURES. REMOVE VEGETATION AND CONSTRUCTION OF THE FILL. DISTURBED AREAS SHALL BE STABILIZED WHENEVER POSSIBLE AND AS REQUIRED 18. PRIOR TO SMP INSTALLATION, THE INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) MUST BE CALLED TO SCHEDULE AN INSPECTION. 19. *INSTALL SUBSURFACE BASIN (SEE SUBSURFACE BASIN SEQUENCE OF CONSTRUCTION) AND OUTLET CONTROL STRUCTURE 20. *INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS. 21. FOLLOWING THE CONSTRUCTION OF THE SMP, THE SITE IMPROVEMENTS INCLUDING THE SYNTHETIC TURF FIELD, CONCRETE PATHWAYS, PLAYGROUND SURFACING AND LANDSCAPING SHALL BE CONSTRUCTED, ENSURING ALL SMPS AND E&S BMPS ARE PROTECTED AND MAINTAINTED THROUGHOUT THE CONSTRUCTION PROCESS. 22. REMOVE ROCK CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT WHEN CONCRETE WORK IS COMPLETE AND CONSTRUCTION EQUIPMENT NO LONGER NEEDS ACCESS. 23. ONCE THE SITE AREA HAS ACHIEVED A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION, REMOVE TEMPORARY EROSION AND SEDIMENTATION BMP'S INCLUDING ROCK CONSTRUCTION ENTRANCES AND INLET PROTECTION. ANY AREA DISTURBED DURING THE REMOVAL OF A TEMPORARY BMP SHALL BE IMMEDIATELY STABILIZED WITH SEEDING AND STRAW MULCH. 24. ENSURE THAT ALL POST-CONSTRUCTION STORMWATER MANAGEMENT BMP'S ARE IN PLACE AND FUNCTIONING ACCORDING TO THE APPROVED PCSM PLANS, DETAILS, AND NARRATIVE. CONTACT HE PHILADELPHIA WATER DEPARTMENT FOR A FINAL INSPECTION AND SUBMIT RECORD DRAWINGS TO COMPLETE THE PROJECT. 25. REMOVAL AND DISPOSAL OF BITUMINOUS MATERIAL SHALL BE IN COMPLETED IN ACCORDANCE WITH DETAILS AND REGULATIONS OF THE MUNICIPALITY. PADEP, AND PENNDOT, AS APPLICABLE AND IS SUBJECT TO INSPECTION AND APPROVAL AS APPROPRIATE 26. CONTRACTOR TO COLLECT AND REMOVE ALL TRASH/DEBRIS ON SITE. *CRITICAL STAGE - DURING THE BMP INSTALLATION, A LICENSED PROFESSIONAL ENGINEER, REGISTERED ARCHITECT/LANDSCAPE ARCHITECT, PROFESSIONAL LAND SURVEYOR, GEOLOGIST, OR LICENSED CONTRACTOR MUST DOCUMENT THE INFORMATION AND MEASUREMENTS REQUIRED ON THE BMP CONSTRUCTION CERTIFICATION FORMS WITHIN THE CERTIFICATION PACKAGE. SEQUENCE OF CONSTRUCTION: SUBSURFACE BASIN **SEQUENCE OF CONSTRUCTION: MEDIA FILTER** 1. AT LEAST 3 DAYS PRIOR TO THE CONSTRUCTION OF THE DETENTION BASIN, THE CONTRACTOR 1. AT LEAST 3 DAYS PRIOR TO THE INSTALLATION OF THE MEDIA FILTER. THE CONTRACTOR SHALL CONTACT PWD INSPECTIONS COORDINATOR (OFFICE 215-685-6387). SHALL CONTACT PWD INSPECTIONS COORDINATOR (OFFICE 215-685-6387). 2. CONTRACTOR TO NOTIFY DESIGN ENGINEER 3 DAYS PRIOR TO CONSTRUCTION OF BASIN. 2. CONTRACTOR TO NOTIFY DESIGN ENGINEER 3 DAYS PRIOR TO INSTALLATION OF MEDIA FILTER. 3. EXCAVATE FOOTPRINT TO SPECIFIED ELEVATION. 3. EXCAVATE FOOTPRINT TO SPECIFIED ELEVATION. 4. INSTALL STORMWATER BASIN, INCLUDING LOW FLOW DEVICE, AS SPECIFIED BY MANUFACTURER IN THE AREA SPECIFIED ON PLANS. 4. INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS. 5. INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS 5. CONNECT PIPES TO MEDIA FILTER WATER QUALITY DEVICE IN LOCATIONS SPECIFIED ON 6. CONNECT PIPES TO STORMWATER BASIN IN LOCATIONS SPECIFIED ON PLANS. 6. BACKFILL TO GRADE. 7. BACKFILL TO GRADE. **EROSION AND SEDIMENTATION CONTROL NOTES:** 1. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION. 2. AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER. APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING. 3. AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES. 4. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION. 5. AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL. 6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN. 7. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN. 8. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED, IF NECESSARY, AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 20 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER. 9. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION. THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT 10. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THIS SITE. 11. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED. 12. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING. 13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN. OVER UNDISTURBED VEGETATED AREAS. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS. 14. VEHICLES AND EQUIPMENT MAY NEITHER ENTER DIRECTLY NOR EXIT DIRECTLY FROM LOTS. VEHICLES AND EQUIPMENT MAY ONLY ENTER AND EXIT THE CONSTRUCTION SITE VIA A STABILIZED ROCK CONSTRUCTION ENTRANCES ON HAINES STREET. 15. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. THE OPERATOR WILL MAINTAIN AND MAKE AVAILABLE TO NORTHAMPTON COUNTY CONSERVATION DISTRICT COMPLETE, WRITTEN INSPECTION LOGS OF ALL THOSE INSPECTIONS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED. REPLACEMENT BMPS. OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED. 16. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION 17. SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER. 18. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, ELOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES. 19. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES - 6 TO 12 INCHES ON COMPACTED SOILS - PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL. 20. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION. SLIPPAGE. SETTLEMENT. SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS. STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES. 21. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN THICKNESS, UNLESS DIRECTED OTHERWISE BY ENGINEER. 22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS 23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS. 24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES. 25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD. 26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN. 27 IMMEDIATELY AFTER FARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT. THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS, DURING NON-GERMINATING MONTHS, MULCH OR OTHER PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.

 PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR MOTHER MOVEMENTS.
 EROSION AND SEDIMENT BMPS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT

30. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.

 AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON.
 UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL

CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION. 33. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION.

ADDITIONAL EROSION AND SEDIMENTATION CONTROL NOTES:

MAPS AND/OR DETAIL SHEETS

 CONCRETE WASH WATER SHALL BE HANDLED IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. IN NO CASE SHALL IT BE ALLOWED TO ENTER ANY SURFACE WATERS OR GROUNDWATER SYSTEMS.
 EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN

3. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED.

 THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.
 STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN

# **EROSION AND SEDIMENTATION MAINTENANCE:**

1. DURING THE LIFE OF THE PROJECT, ALL EROSION AND SEDIMENTATION CONTROL DEVICES MUST BE PROPERLY MAINTAINED. MAINTENANCE SHALL INCLUDE THE INSPECTION OF EROSION CONTROL FACILITIES AFTER EACH MEASURABLE RUNOFF EVENT (>0.25 INCH) AND ON A WEEKLY BASIS, UNLESS MORE FREQUENT INSPECTION IS REQUIRED. IMMEDIATELY PERFORM CLEANOUT, REPAIR AND REPLACEMENT OF THE FACILITIES AS NEEDED. (REGRADE, RESEED AND MULCH WASHED OUT AREAS AS NEEDED.)

 UNTIL THE SITE IS STABILIZED ALL EROSION AND SEDIMENTATION BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL SITE INSPECTIONS WILL BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE. THE COMPLIANCE ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE INSPECTION LOG WILL BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO PWD/DEP UPON REQUEST.
 WHERE BMP'S ARE FOUND TO FAIL TO ALLEVIATE EROSION OR SEDIMENT POLLUTION THE PERMITTEE OR CO-PERMITTEE NOTIFY THE PHILADELPHIA WATER DEPARTMENT OF THE FAILURE AND SHALL INCLUDE THE FOLLOWING INFORMATION:

3.1. THE LOCATION AND SEVERITY OF THE BMP'S FAILURE AND ANY POLLUTION EVENTS.

3.2. ALL STEPS TAKEN TO, REDUCE, ELIMINATE AND PREVENT THE RECURRENCE OF THE NON-COMPLIANCE.
3.3. THE TIME FRAME TO CORRECT THE NONCOMPLIANCE, INCLUDING THE EXACT DATES WHEN THE ACTIVITY WILL RETURN TO COMPLIANCE

ANCHORING METHOD DESCRIBED ON THE ATTACHED MULCH ANCHORING GUIDE, UNTIL IT HAS A CHANCE TO ROOT PROPERLY.

 ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENTATION BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S OR MODIFICATIONS OF THOSE INSTALLED WILL BE NEEDED.
 SEEDED AREAS THAT HAVE WASHED AWAY SHALL BE FILLED AND GRADED, AS NECESSARY, AND THEN RESEEDED. A STRAW COVER SHALL BE APPLIED TO RETAIN THE SEED ALONG WITH AN

6. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.

7. SEDIMENT REMOVED FROM BMPs SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES.

8. INLET FILTER BAGS SHALL BE CLEANED OUT OR REPLACED WHEN BAG IS HALF FULL.

9. SEDIMENT SHALL BE REMOVED FROM COMPOST FILTER SOCKS WHEN REACHING ONE HALF THE HEIGHT OF THE SOCK, IF USED.

 THE CONTRACTOR SHALL INSPECT ALL ROCK CONSTRUCTION ENTRANCES ON A DAILY BASIS AND SHALL ENSURE THAT SEDIMENT IS NOT BEING TRACKED ONTO PUBLIC STREETS. SEDIMENT THAT IS TRACKED ONTO PUBLIC STREETS SHALL BE COLLECTED AND RETURNED TO THE SITE OR OTHERWISE PROPERLY REMOVED BY A STREET SWEEPER.
 EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS, IF USED.

 FILL MATERIAL FOR EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE COMPACTED IN MAXIMUM 6 INCH LAYERED LIFTS AT 95% DENSITY.
 AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP'S MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMP'S MUST BE STABILIZED IMMEDIATELY.

 BEFORE INITIATING ANY REVISION TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY EFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE PA DEP. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
 ALL PUMPING OF SEDIMENT LADEN WATER OR POTENTIALLY SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, AND FILTRATION SYSTEM, SUCH AS A TIGG FILTRATION SYSTEM - CANSORB CP-2000 AND DISCHARGED OVER NON-DISTURBED AREAS.

DEWATERING OR PUMPING OF GROUNDWATER MUST DISCHARGE TO CITY OWNED INFRASTRUCTURE, IF REQUIRED, CONTRACTOR SHALL OBTAIN AN INDUSTRIAL DISCHARGE PERMIT THROUGH THE INDUSTRIAL WASTE UNIT. DISCHARGE MUST BE CONNECTED DIRECTLY TO A COMBINED OR SANITARY SEWER LATERAL.
 PWD SHALL NOT BE RESPONSIBLE FOR ANY CLEANUP OR REPAIRS NEEDED ON CITY-OWNED INFRASTRUCTURE OR REPAIRS DUE TO FAILURE OF APPROVED EROSION CONTROL MEASURES OF CITY

When the shall be readed of the shall be responsible for all cleanup and repairs due to failure of approved erosion control measures.
 18. IF CONTAMINATED SOILS ARE ENCOUNTERED DURING CONSTRUCTION, CONTACT OWNER.

ENTRANCES.

### RECYCLING AND DISPOSAL NOTE:

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 et seq. AND 287.1 et seq.

CONSTRUCTION WASTES INCLUDE, BUT NOT LIMITED TO: - INLET PROTECTION - PUMPED WATER FILTER BAGS

TEMPORARY SEEDING SITE PREPARATION :

TEMPORARY STABILIZATION OF ALL EXPOSED EARTH SURFACES WHERE CONSTRUCTION ACTIVITY HAS CEASE. INCLUDING TOPSOIL STOCKPILES SHALL BE STABILIZED IMMEDIATELY BY

THE FOLLOWING METHODS AND MATERIALS.

 APPLY ONE (1) TON OF AGRICULTURAL GRADE LIMESTONE PER ACRE PLUS FERTILIZER (10-10-10) AT THE RATE OF 1000 LBS PER ACRE AND WORK INTO SOIL WHEREVER POSSIBLE.
 APPLY 100% ANNUAL RYEGRASS SEED AT A RATE OF 4 TO 5 LBS PER 1000 SQUARE FEET.

3. AFTER SEEDING MULCH WITH HAY OR STRAW AT A RATE OF THREE (3) TONS PER ACRE.

PERMANENT SEEDING SITE PREPARATION:

PERMANENT STABILIZATION OF THE ALL EXPOSED EARTH SURFACES AFTER THE COMPLETION OF THE SITE GRADING AND IMPROVEMENTS SHALL BE ACCOMPLISHED BY THE FOLLOWING METHODS AND MATERIALS: 1. AFTER INSTALLATION OF THE NEEDED SURFACE WATER CONTROL MEASURES, PERFORM ALL

CULTURAL OPERATIONS AT RIGHT ANGLES TO THE SLOPE. OBTAIN SOILS TESTING FROM AN INDEPENDENT LABORATORY TO DETERMINE NECESSARY SOILS MODIFICATIONS.

 IN THE ABSENCE OF SOILS TESTING, APPLY AGRICULTURAL GRADE LIMESTONE AT THE MINIMUM RATE OF SIX TONS LIMESTONE PER ACRE (276 LBS. PER 1,000 SQUARE FEET).
 IN THE ABSENCE OF SOILS TESTING, WORK IN FERTILIZER AT THE RATE OF 1000 LBS. OF 10-20-20 OR EQUIVALENT PER ACRE.

SMOOTH AND FIRM SEEDED AREAS WITH CULTIPACKER, OR OTHER SIMILAR EQUIPMENT, PRIOR TO SEEDING. APPLY SEED.

COVER GRASS SEEDS WITH 1/4 INCH OF TOPSOIL WITH SUITABLE EQUIPMENT.

 APPLY STRAW MULCH AT A RATE OF 3.0 TON PER ACRE IMMEDIATELY AFTER SEEDING.
 USE SOD WHERE THERE IS A HEAVY CONCENTRATION OF WATER AND IT IS IMPORTANT TO GET A QUICK VEGETATIVE COVER IN ORDER TO PREVENT GULLYING. USE SOD AT THE DIRECTION OF THE MUNICIPAL ENGINEER OR HIS AUTHORIZED REPRESENTATIVE.
 HYDROSEEDING SHALL BE AN ACCEPTABLE ALTERNATIVE TO THE ABOVE SEEDING WHEN PERFORMED IN ACCORDANCE WITH PENNDOT PUB. 408 SECTIONS 804 AND 805 AND

### APPROVED BY THE SITE ENGINEER. PERMANENT SEEDING NOTES:

1. SPREAD AND FINE GRADE 12" TOPSOIL ON ALL AREAS TO BE PERMANENTLY SEEDED.

2. BEFORE SEEDING, APPLY APPROPRIATE SOIL MODIFICATIONS.

3. INSTALL EROSION/SEED BLANKET WHERE NEEDED.

4. WATER AND MAINTAIN ALL LAWN AREAS.

 RESEED BARE OR THIN AREAS AS DIRECTED BY THE ENGINEER.
 IF GROUND COVER IS NOT OTHERWISE SPECIFIED ON THE APPROVED LANDSCAPING PLANS, USE SEED MIXTURE 2, AS SHOWN IN TABLE 11.4.

7. APPLY STRAW MULCH AT 3.0 TON/ACRE IMMEDIATELY AFTER SEEDING.

8. APPLY STRAW AND MULCH DURING NON-GROWING SEASONS (NOVEMBER - MARCH)

![](_page_23_Picture_48.jpeg)

### CALL BEFORE YOU DIG BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA

CALL 1-800-242-1776 PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL OR BLAST PENNSYLVANIA ONE-CALL SYSTEM, INC. SERIAL NUMBER(S): 20212583950 UNFORSEEN EROSIVE CONDITIONS NOTES:

- 1. SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF AND/OR SEDIMENT DISPLACEMENT. STOCKPILES OF WOOD CHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.
- 2. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, D.E.P., SUB-PART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES,
- CHAPTER 102, EROSION CONTROL.
  CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PROTECT EXISTING TREES AND SHRUBS WHICH ARE TO REMAIN IN PLACE. CONTRACTOR SHALL BE RESPONSIBLE FOR
- REPAIRING ANY DAMAGES, INCLUDING REPLACING TREES OR SHRUBS IN KIND IF NECESSARY
  4. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING REGULARLY TRACKED ONTO PUBLIC STREETS, THE CONTRACTOR SHALL BE PREPARED, UPON WRITTEN NOTICE GIVEN BY THE CITY OF PHILADELPHIA, TO PROVIDE TIRE WASHING FACILITIES AT ALL ROCK CONSTRUCTION

# CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE:

STANDARD NOTE TO COMPLY WITH NPDES CHECKLIST ITEM #2.B.XV (#3.B.XV FOR AN INDIVIDUAL NPDES PERMIT)

IF THE SITE WILL NEED TO IMPORT OR EXPORT MATERIAL FROM THE SITE, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND DETERMINATION OF CLEAN FILL WILL REST WITH THE CONTRACTOR.

CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE). CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS

CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL". ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS. ENVIRONMENTAL DUE DILIGENCE: THE APPLICANT MUST PERFORM ENVIRONMENTAL DUE DILIGENCE TO DETERMINE IF THE FILL MATERIALS ASSOCIATED WITH THE PROJECT QUALIFY

AS CLEAN FILL. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF

THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".

FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE. THESE REGULATIONS ARE AVAILABLE ON-LINE AT <u>WWW.PACODE.COM <http://www.pacode.com></u>. CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE NOTES:

WITH THE EXCEPTION OF SITES ENROLLED IN DEP'S LAND RECYCLING AND ENVIRONMENTAL REMEDIATION STANDARDS (ACT 2) PROGRAM, ALL FILL MATERIAL EXCAVATED AND USED ON-SITE, IMPORTED TO THE SITE, AND EXPORTED FROM THE SITE, MUST MEET THE DEFINITION OF CLEAN FILL, AS DEFINED IN THIS PERMIT. REGULATED FILL MAY ONLY BE USED ON ACT 2 SITES, IN ACCORDANCE WITH STANDARDS ESTABLISHED BY THAT PROGRAM.

THE PERMITTEE SHALL CONDUCT ENVIRONMENTAL DUE DILIGENCE TO VERIFY THAT FILL EXCAVATED ON-SITE THAT IS USED TO ESTABLISH FINAL GRADE, FILL IMPORTED TO THE PROJECT SITE, AND FILL EXPORTED FROM THE PROJECT SITE IS CONSIDERED CLEAN FILL. IF DUE DILIGENCE RESULTS IN EVIDENCE OF A RELEASE, AS DEFINED IN DEP'S MANAGEMENT OF FILL POLICY (285-2182-773), THAT HAS AFFECTED THE FILL MATERIAL, THE PERMITTEE SHALL TEST THE MATERIAL TO DETERMINE WHETHER THE MATERIAL QUALIFIES AS CLEAN FILL, AND FORM FP-001 (CERTIFICATION OF CLEAN FILL) MUST BE COMPLETED, RETAINED BY THE PERMITTEE OR THE

IN THE EVENT THAT FILL EXCAVATED ON-SITE THAT IS USED TO ESTABLISH FINAL GRADE, FILL IMPORTED TO THE PROJECT SITE, OR FILL EXPORTED FROM THE PROJECT SITE IS FOUND TO BE REGULATED FILL DURING THE TERM OF PERMIT COVERAGE, WHERE THE UTILIZATION OF THE REGULATED FILL WILL REQUIRE A PERMIT FROM DEP'S WASTE MANAGEMENT PROGRAM, EARTH DISTURBANCE ACTIVITIES SHALL CEASE UNTIL SUCH TIME THAT THE PERMITTEE OBTAINS ALL

PROPERTY OWNER ON-SITE, AND BE MADE AVAILABLE TO DEP/PWD UPON REQUEST.

IF THE PERMITTEE BECOMES AWARE DURING EARTH DISTURBANCE ACTIVITIES THAT SOILS IN THE AREA OF EARTH DISTURBANCE CONTAIN CONCENTRATIONS OF REGULATED SUBSTANCES EXCEEDING THE RESIDENTIAL MEDIUM-SPECIFIC CONCENTRATIONS FOR SOIL IN 25 PA. CODE CHAPTER 250, THE PERMITTEE SHALL NOTIFY DEP IN ACCORDANCE WITH PART A III.D OF THIS PERMIT AND CEASE EARTH DISTURBANCE ACTIVITIES IN AREAS OF KNOWN SOIL CONTAMINATION

NECESSARY PERMITS OR APPROVALS FROM DEP, INCLUDING NEW NPDES PERMIT COVERAGE.

![](_page_23_Figure_69.jpeg)

![](_page_24_Figure_0.jpeg)

2 IN. x 2 IN. WOODEN STAKES PLACED 10

FT ON CENTER OR CONCRETE BLOCK

WHEN PROPOSED ON IMPERVIOUS

SURFACE

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

COMPOST FILTER SOCK \

**BLOWN/PLACED** 

FILTER MEDIA

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND

SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER. WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

**DETAIL-** PUMPED WATER FILTER BAG N.T.S.

![](_page_24_Figure_9.jpeg)

# NOTES:

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL MANUAL.

FABRIC WIDTH SHALL BE 30 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

![](_page_24_Picture_14.jpeg)

SYSTEM

NOTES:

IMMEDIATELY.

COMPACTION

**DETAIL-** SILT FENCE

**DETAIL-** CONSTRUCTION FENCE

![](_page_24_Figure_17.jpeg)

![](_page_24_Figure_18.jpeg)

- FIBERGLASS 'T' POST, 6'-6" LONG, SPACED AT 8' O.C. (MAX.) - FASTEN FENCE TO POST AS RECOMMENDED BY MANUFACTURER

- HIGH VISIBILITY ORANGE POLYETHYLENE SAFETY FENCE, 46" HIGH (MIN.) PRE-DRILL EXISTING SURFACE, IF REQUIRED, FOR POST INSTALLATION

----- EXISTING GRADE

NOTES: A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING THE SOCKS. INSTALL ON FLAT GRADE FOR OPTIMUM PERFORMANCE.

COMPOST SOCKS SHALL BE STAKED IN THE MANNER RECOMMENDED BY THE MANUFACTURER AROUND THE PERIMETER OF THE GEOMEMBRANE SO AS TO FORM A RING WITH THE ENDS OF THE DOCK LOCATED AT THE UPSLOPE CORNER.

CARE SHALL BE TAKEN TO ENSURE CONTINUOUS CONTACT OF THE SOCK WITH THE GEOMEMBRANE AT ALL LOCATIONS. 18" DIAMETER FILTER SOCK MAY BE STACKED ONTO DOUBLE 24" DIAMETER FILTER SOCKS IN PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT.

MAINTENANCE: ALL CONCRETE WASHOUT FACILITIES SHOULD BE INSPECTED DAILY. DAMAGED OR LEAKING WASHOUTS SHOULD BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY. ACCUMULATED MATERIALS SHALL BE REMOVED WHEN THEY REACH 50% CAPACITY. GEOMEMBRANE SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY.

![](_page_24_Figure_28.jpeg)

![](_page_25_Figure_0.jpeg)

SITE: 4901 KINGSESSING AVE PHILADELPHIA, PA 19143 OPA#783249500 CLIENT: CITY OF PHILADELPHIA PARKS AND RECREATION 1515 ARCH STREET, 10TH FLOOR PHILADELPHIA, PA 19102 ENGINEER: PENNONI ASSOICATES

### **REFERENCES:**

PLAN BY AMERICAN ENGINEERS GROUP, LLC ENTITLED "KINGSESSING RECREATION CENTER TOPOGRAPHIC SURVEY",

PRE-CONSTRUCTION DRAINAGE AREA (ON-SITE)							
	AREA (SF)	AREA (AC)	CN				
PRE-IMPERVIOUS (80% OF TRUE IMPERVIOUS)	20,618	0.47	98				
PRE-MEADOW (20% OF TRUE IMPERVIOUS MODELED AS MEADOW)	5,154	0.12	58				
GRASS (MODELED AS MEADOW)	138,324	3.18	58				
TOTAL	164,069	3.77					

	EXISTING PROPERTY LINE (APPROXIMATE)
	EXISTING RIGHT OF WAY LINE (APPROXIMATE)
	EXISTING BUILDING
	EXISTING CURB
a · · · ·	EXISTING SIDEWALK
	EXISTING EDGE OF MACADAM/GRAVEL
	EXISTING TRAFFIC MARKING
××	EXISTING FENCE
ALL ALL	EXISTING TREE
	EXISTING MAJOR CONTOUR
4	EXISTING MINOR CONTOUR
-0-	EXISTING SIGN
•	EXISTING BOLLARD
$\mathcal{Q}$	EXISTING UTILITY POLE
	EXISTING LIGHT
	EXISTING INLET
<i>s</i>	EXISTING SEWER
<i>D</i>	EXISTING STORM SEWER
<i>W</i>	EXISTING WATER LINE
UT	EXISTING UNDERGROUND TELEPHONE LINE
<i>UG</i>	EXISTING GAS LINE
UE	EXISTING UNDERGROUND ELECTRIC
OE	EXISTING OVERHEAD WIRES
. 🥵 🖓 E W T S D	EXISTING UTILITY STRUCTURES
	EXISTING ON-SITE DRAINAGE AREA BOUNDARY

EXISTING IMPERVIOUS AREA EXISTING PERVIOUS AREA

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

![](_page_25_Figure_10.jpeg)

![](_page_26_Figure_0.jpeg)

4901 KINGSESSING AVE PHILADELPHIA, PA 19143 OPA#783249500	PROPOS		AGE AREA -	UB-1	PROPOSED DRA	INAGE AREA - ST	ORMWATER TR	ADING BYPASS
CLIENT:	AREA (SF) AREA (AC) CN		CN					
CITY OF PHILADELPHIA PARKS AND RECREATION						AREA (SF)	AREA (AC)	CN
1515 ARCH STREET, 10TH FLOOR PHILADELPHIA, PA 19102	PERVIOUS	37,262	0.86	61	DCIA	1.131	0.03	98
ENGINEER:	SYNTHETIC TURF DCIA	92,891	2.13	98		, -		
PENNONI ASSOICATES					TOTAL	1,131	0.03	
1900 MARKET STREET, SUITE 300 PHILADELPHIA, PA 19103	DCIA	13,005	0.30	98				
	TOTAL	143,158	3.29					
REFERENCES:			1	1				

PLAN BY AMERICAN ENGINEERS GROUP, LLC ENTITLED

SHEET NO. 1	, DATED (	)3/12/20	21.				
				 	_		

PROPOSED DRAINAGE AREA - PLAYGROUND BYPASS						
	AREA (SF)	AREA (AC)	CN			
PERVIOUS	8,517	0.20	61			
POROUS PLAYGROUND SURFACE (DIC)	6,614	0.15	70			
DCIA	219	0.01	98			
PAVEMENT DIC	2,435	0.06	98			
TOTAL	17,785	0.41				

REA - LANDSCAPE BYPASS							
	AREA (AC)	CN					
	0.05	61					
	0.05						

EXIST	ING	LE	GEN	١D
				EX

	EXISTING PROPERTY LINE (APPROXIMATE) EXISTING RIGHT OF WAY LINE (APPROXIMATE) EXISTING BUILDING
· · · · · · · · · · · · · · · · · · ·	
A · · ·	
	EXISTING EDGE OF MACADAM/GRAVEL
	EXISTING TRAFFIC MARKING
××	EXISTING FENCE
and the second s	EXISTING TREE
	EXISTING MAJOR CONTOUR
<b></b> 4 <b></b>	EXISTING MINOR CONTOUR
	EXISTING SIGN
•	EXISTING BOLLARD
$\mathcal{Q}$	EXISTING UTILITY POLE
	EXISTING LIGHT
	EXISTING INLET
<i>s</i>	EXISTING SEWER
<i>D</i>	EXISTING STORM SEWER
W	EXISTING WATER LINE
UT	EXISTING UNDERGROUND TELEPHONE LINE
<i>UG</i>	EXISTING GAS LINE
UE	EXISTING UNDERGROUND ELECTRIC
OE	EXISTING OVERHEAD WIRES
. 候 🖓 E W T S D	EXISTING UTILITY STRUCTURES

PWD TRACKING #FY22-KING-6800-01

![](_page_26_Picture_12.jpeg)

![](_page_27_Figure_0.jpeg)

SITE: 4901 KINGSESSING AVE PHILADELPHIA, PA 19143 OPA#783249500 CLIENT: CITY OF PHILADELPHIA PARKS AND RECREATION 1515 ARCH STREET, 10TH FLOOR PHILADELPHIA, PA 19102 ENGINEER: PENNONI ASSOICATES

### **REFERENCES**:

1. BOUNDARY AND TOPOGRAPHIC INFORMATION TAKEN FROM A PLAN BY AMERICAN ENGINEERS GROUP, LLC ENTITLED "KINGSESSING RECREATION CENTER TOPOGRAPHIC SURVEY",

DRAINAGE AREA	IMPERVIOUS AREA SF (AC.)	PERVIOUS AREA SF (AC.)	то ⁻ ?
I-1	3,287 (0.08)	4,176 (0.10)	7,
I-2	2,473 (0.06)	847 (0.02)	3,
I-3	2,794 (0.06)	20,604 (0.47)	23
I-4	3,175 (0.07)	1,593 (0.04)	4,
MH-1 TO MH-2	60,244 (1.38)	7,682 (0.18)	67
MH-2 TO UB-1	13,724 (0.32)	629 (0.01)	14
MH-3 TO CO-6	20,199 (0.46)	1,731(0.04)	21
PLAYGROUND BYPASS	2,654 (0.06)	15,131 (0.35)	17
STORMWATER TRADING BYPASS	1,131 (0.03)	0 (0.00)	1,
LANDSCAPE BYPASS	0 (0.00)	2,022 (0.05)	2,
TOTAL	109,681 (2.52)	54,415 (1.25)	164

![](_page_27_Figure_8.jpeg)