



**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

# CITY OF PHILADELPHIA REBUILD / PHILADELPHIA PARKS AND RECREACTION

MAYOR - JAMES F. KENNEY

MANAGING DIRECTOR - TUMAR ALEXANDER

COMMISSIONER OF PUBLIC PROPERTY - BRIDGET COLLINS-GREENWALD

REBUILD PHILADELPHIA EXECUTIVE DIRECTOR - KIRA STRONG

PROJECT NO. 16368E-02-03

# PHILADELPHIA PARKS AND RECREATION KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS PACKAGE 2: INTERIOR REPAIRS AND SITE IMPROVEMENTS 4901 KINGSESSING AVE

LANDSCAPE ARCHITECT: SALT Design Studio 161 Leverington Ave, Suite 1005 Philadelphia, PA 19127 www.saltdesigns.com

STRUCTURAL / M.E.P. / F.P. ENGINEERS: PENNONI ASSOCIATES, INC. 1900 Market Street, Suite 300 Philadelphia, PA 19103 www.pennoni.com

CIVIL ENGINEERS: PENNONI ASSOCIATES, INC. 1900 Market Street, Suite 300 Philadelphia, PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103


	Sheet List PKG 2		Sheet List PKG 2
Sheet Number	Sheet Name	Sheet Number	Sheet Name
CS1-R.2	COVER SHEET	L-104-R.2	SITE LIGHTING LAYOUT PLAN - BASE SCOPE
00111.2	OG VER GILET	L-105-R.2	SITE PHOTOMETRY PLAN
C-021-R.2	EXISTING CONDTIONS PLAN	L-106-R.2	SITE PLANTING PLAN- BASE SCOPE
C-050-R.2	SITE UTILIZATION PLAN	L-401-R.2	PLAN ENLARGEMENT - SAFETY SURFACE
C-051-R.2	SITE DEMOLITION PLAN		LAYOUT PLAN
C-100-R.2	OVERALL SITE KEY PLAN	L-402-R.2	PLAN ENLARGEMENT - PLAY MOUND
C-101-R.2	SITE IMPROVEMENT PLAN SOUTH	L-501-R.2	SITE DETAILS
C-102-R.2	SITE IMPROVEMENT PLAN NORTH	L-502-R.2	PLANTING DETAILS
C-151-R.2	GRADING PLAN SOUTH	L-800-R.2	SITE ADD ALT OVERVIEW PLAN
C-152-R.2	GRADING PLAN NORTH	L-801-R.2	SITE ADD ALTERNATE S3 - TENNIS COURTS
C-153-R.2	DETAIL GRADING PLAN PLAYGROUND	L-802-R.2	SITE ADD ALTERNATE S4 - DIAGONAL PATH AMENITIES
C-154-R.2	SYNTHETIC TURF FIELD SPORTS STRIPING PLAN		AWILIVITILO
C-171-R.2	PCSM/UTILITY PLAN SOUTH	G101-R.2	GENERAL NOTES AND ABBREVIATIONS
C-172-R.2	PCSM/UTILITY PLAN NORTH	LS101-R.2	CODE REVIEW AND LIFE SAFETY PLANS
CS601-R.2	SITE DETAILS	LS102-R.2	LIFE SAFETY PLAN - FIRST FLOOR
CS602-R.2	SITE DETAILS	LS103-R.2	LIFE SAFETY PLAN - SECOND FLOOR
CS603-R.2	SITE DETAILS	Z101-R.2	SITE PLAN / ZONING
CS604-R.2	SITE DETAILS		
CS605-R.2	SITE DETAILS	AD101-R.2	DEMOLITION PLAN - LOWER LEVEL BASE
CS606-R.2	SITE DETAILS		SCOPE
CS607-R.2	SITE DETAILS	AD101B-R.2	DEMOLITION PLAN - LOWER LEVEL DEDUCT
CS608-R.2	SITE DETAILS	AD4040 D 0	ALT R-1
CS609-R.2	SITE DETAILS	AD101C-R.2	DEMOLITION PLAN - LOWER LEVEL ADD ALT F
		AD102-R.2	DEMOLITION PLAN - 1ST FLOOR
C-610-R.3	SITE IMPROVEMENT PLAN SOUTH	AD103-R.2	DEMOLITION PLAN - 2ND FLOOR
C-801-R.2	EROSION & SEDIMENTATION CONTROL PLAN	AD104-R.2	DEMOLITION PLAN - ATTIC
C-851-R.2	EROSION & SEDIMENTATION CONTROL NOTES	AD106-R.2	DEMOLITION RCP - LOWER LEVEL
C-852-R.2	EROSION & SEDIMENTATION CONTROL	AD107-R.2	DEMOLITION RCP - 1ST FLOOR
	DETAILS	AD108-R.2	DEMOLITION RCP - 2ND FLOOR
C-900-R.2	PRE-CONSTRUCTION DRAINAGE AREA MAP	AD201-R.2	DEMOLITION ELEVATION-EAST
C-901-R.2	POST CONSTRUCTION DRAINAGE AREA MAP	AD202-R.2	DEMOLITION ELEVATION-WEST
C-902-R.2	INLET DRAINAGE AREA MAP	AD203-R.2	DEMOLITION ELEVATIONS-SOUTH
		AD204-R.2	DEMOLITION ELEVATIONS-NORTH
L-100-R.2	SITE IMPROVEMENT OVERVIEW PLAN	A101-R.2	NEW WORK - LOWER LEVEL BASE SCOPE
L-101-R.2	SITE LAYOUT PLAN - BASE SCOPE	A101B-R.2	NEW WORK - LOWER LEVEL DEDUCT ALT R-1
L-102-R.2	SITE MATERIALS PLAN - BASE SCOPE	A101C-R.2	NEW WORK - LOWER LEVEL ADD ALT R-2
L-103-R.2	SITE FURNISHINGS AND EQUIPMENT PLAN -	A101C-R.2	NEW WORK - 1ST FLOOR
	BASE SCOPE	A102-R.2 A103-R.2	NEW WORK - 151 FLOOR


Rebuild


STAMP AREA


	Sheet List PKG 2		Sheet List PKG 2			
heet Number	Sheet Name	Sheet Number	Sheet Name	Sheet Numbe	r	
04-R.2	NEW WORK - ATTIC & ROOF	S105-R.2	ROOF FRAMING PLAN	E-200-R.2	ELE	
05-R.2	INTERIOR REPAIR - LOWER LEVEL	S301-R.2	TYPICAL DETAILS		LEV	
06-R.2	INTERIOR REPAIR - 1ST FL	S302-R.2	TYPICAL DETAILS	E-200B-R.2	ELE	
07-R.2	INTERIOR REPAIR - 2ND FL	S303-R.2	SECTIONS		LEV	
201-R.2	BUILDING ELEVATIONS - EAST	S304-R.2	SECTIONS	E-200C-R.2	ELE	
202-R.2	BUILDING ELEVATIONS - WEST	S305-R.2	SECTIONS		LEV	
203-R.2	BUILDING ELEVATIONS - NORTH	3337.1.12	020110110	E-201-R.2	ELE	
204-R.2	BUILDING ELEVATIONS - SOUTH	M-001-R.2	MECHANICAL INDEX SHEET	E-202-R.2	ELE	
801-R.2	BUILDING SECTIONS	M-002-R.2	MECHANICAL NOTES	E 000 D 0	FLO	
101-R.2	ENLARGED PLANS/ELEVATIONS - TOILET	M-100-R.2	MECHANICAL DEMOLITION - LOWER LEVEL	E-203-R.2	ELE	
	ROOMS		BASE SCOPE	E-204-R.2	ELE	
02-R.2	ENGLARGED PLANS/ELEVATIONS - TOILET ROOMS	M-100B-R	MECHANICAL DEMOLITION -LOWER LEVEL - DEDUCT ALT	E-300-R.2	ELE LEV	
50-R.2	VERTICAL CIRCULATION - STAIRS, PLANS &	M-101-R.2	MECHANICAL DEMOLITION -FIRST FLOOR	E-300B-R.2	LEV	
	SECTIONS	M-102-R.2	MECHANICAL DEMOLITION - SECOND FLOOR	E 3000 D 3		
51-R.2	VERTICAL CIRCULATION - STAIRS, PLANS & SECTIONS	M-200-R.2	MECHANICAL PROPOSED DUCTWORK - LOWER LEVEL BASE SCOPE	E-300C-R.2	LEV	
52-R.2	VERTICAL CIRCULATION - STAIRS, PLANS & SECTIONS	M-200B-R.2	MECHANICAL PROPOSED DUCTWORK - LOWER LEVEL DEDUCT ALT	E-301-R.2	FLC FLC	
53-R.2	VERTICAL CIRCULATION - ELEVATOR	M-200C-R.2	MECHANICAL PROPOSED DUCTWORK - LOWER	E-302-R.2	FLO	
54-R.2	VERTICAL CIRCULATION - RAMPS	2000 :2	LEVEL ADD ALT	E-303-R.2	ELE	
55-R.2	MECH ENCLOSURES	M-201-R.2	MECHANICAL PROPOSED DUCTWORK - FIRST	E-303-R.2 E-400-R.2	ELE	
501-R.2	INTERIOR ELEVATIONS		FLOOR	E-400-R.2 E-401-R		
502-R.2	INTERIOR ELEVATIONS	M-202-R.2	MECHANICAL PROPOSED DUCTWORK -	E-401-R	PRO	
511-R.2	ENLARGED PLAN, ELEV., DTLS - KITCHEN		SECOND FLOOR	E-500-R.2	ELE	
612-R.2	MASONRY REPAIR DETAILS	M-203-R.2	MECHANICAL PROPOSED DUCTWORK	E-501-R.2	ELE	
'01-R.2	REFLECTED CEILING PLAN - LOWER LEVEL		-ATTIC/ROOF	E-502-R.2	ELE	
'02-R.2	REFLECTED CEILING PLAN - 1ST FLOOR	M-300-R.2	MECHANICAL PROPOSED PIPING - LOWER LEVEL BASE SCOPE	E-503-R.2	ELE	
'03-R.2	REFLECTED CEILING PLAN - 2ND FLOOR	M 200D D 2		E-600-R.2	ELE	
301-R.2	FINISH PLAN - LOWER LEVEL	M-300B-R.2	MECHANICAL PROPOSED PIPING - LOWER LEVEL DEDUCT ALT	L-000-11.2		
302-R.2	FINISH PLAN - 1ST FLOOR	M-300C-R.2	MECHANICAL PROPOSED PIPING - LOWER	P-001-R.2	PLU	
303-R.2	FINISH PLAN - 2ND FLOOR	W-5000-11.2	LEVEL ADD ALT	P-100-R.2	PLU	
804-R.2	MATERIAL SCHEDULE & FINISH PLANS	M-301-R.2	MECHANICAL PROPOSED PIPING - FIRST	1 - 100-11.2	SCC	
305-R.2	SIGNAGE PLAN - LOWER LEVEL		FLOOR	P-100B-R.2	PLU	
306-R.2	SIGNAGE PLAN - 1ST FLOOR	M-302-R.2	MECHANICAL PROPOSED PIPING - SECOND		DEC	
307-R.2	SIGNAGE PLAN - 2ND FLOOR		FLOOR	P-101-R.2	PLU	
01-R.2	WINDOW, DOOR AND PARTITION SCHEDULES	M-303-R.2	MECHANICAL PROPOSED PIPING - ATTIC	P-102-R.2	PLU	
002-R.2	WINDOW SCHEDULE	M-400-R.2	MECHANICAL PARTITION PLANS & SECTIONS	P-103-R.2	PLU	
003-R.2	WINDOW DETAILS	M-500-R.2	MECHANICAL CONTROLS SEQUENCES	P-200-R.2	PLU	
004-R.2	WINDOW DETAILS	M-501-R.2	MECHANICAL DIAGRAMS		LEV	
)10-R.2	STOREFRONT ENTRANCE	M-600-R.2	MECHANICAL SCHEDULES	P-200B-R.2	PLU	
	0.01.2.110111 2.11102	M-601-R.2	MECHANICAL SCHEDULES		LEV	
001-R.2	STRUCTURAL GENERAL NOTES	M-700-R.2	MECHANICAL DETAILS	P-200C-R.2	PLU	
02-R.2	STRUCTURAL GENERAL NOTES	M-701-R.2	MECHANICAL DETAILS		LEV	
0101-R.2	DEMOLITION PLAN - LOWER LEVEL	M-702-R.2	MECHANICAL DETAILS	P-201-R.2	PLU FLC	
0102-R.2	DEMOLITION PLAN - FIRST FLOOR	E-001-R.2	ELECTRICAL INDEX SHEET	P-202-R.2	PLU	
0103-R.2	DEMOLITION PLAN - SECOND FLOOR	E-100-R.2	ELECTRICAL DEMOLITION - LOWER LEVEL		FLO	
D-104-R.2	DEMOLITION PLAN- ATTIC	L 100-11.2	BASE SCOPE	P-203-R.2	PLU	
04.5.0	LOWED LEVEL EDAMINO STAN	E-100B-R.2	ELECTRICAL DEMOLITION - LOWER LEVEL	P-300-R.2	PLU	
01-R.2	LOWER LEVEL FRAMING PLAN		DEDUCT ALT	D 0000 5 5	BAS	
02-R.2	FIRST FLOOR FRAMING PLAN	E-101-R.2	ELECTRICAL DEMOLTION - FIRST FLOOR	P-300B-R.2	PLU DEC	
03-R.2	SECOND FLOOR FRAMING PLAN					


	Sheet List PKG 2		Sheet List PKG 2
Sheet Number	Sheet Name	Sheet Number	Sheet Name
E-200-R.2	ELECTRICAL PROPOSED POWER - LOWER LEVEL BASE SCOPE	P-300C-R.2	PLUMBING SUPPLY PROPOSED - LOWER LEVEL ADD ALT
E-200B-R.2	ELECTRICAL PROPOSED POWER- LOWER LEVEL DEDUCT ALT	P-301-R.2 P-302-R.2	PLUMBING SUPPLY PROPOSED - FIRST FLOOR PLUMBING SUPPLY PROPOSED - SECOND
E-200C-R.2	ELECTRICAL PROPOSED POWER - LOWER LEVEL ADD ALT	P-400-R.2	FLOOR PLUMBING SANITARY RISER BASE SCOPE
E-201-R.2	ELECTRICAL PROPOSED POWER -FIRST FLOOR	P-400B-R.2	PLUMBING SANITARY RISER DEDUCT ALT
E-202-R.2	ELECTRICAL PROPOSED POWER - SECOND	P-400C-R.2	PLUMBING SANITARY RISER ADD ALT
	FLOOR	P-401-R.2	PLUMBING SUPPLY RISER BASE SCOPE
E-203-R.2	ELECTRICAL PROPOSED POWER -ATTIC/ROOF	P-401B-R.2	PLUMBING SUPPLY RISER DEDUCT ALT
E-204-R.2	ELECTRICAL PROPOSED POWER - SITE PLAN	P-401C-R.2	PLUMBING SUPPLY RISER ADD ALT
E-300-R.2	ELECTRICAL PROPOSED LIGHTING LOWER	P-500-R.2	PLUMBING SCHEDULES
	LEVEL BASE SCOPE	P-600-R.2	PLUMBING DETAILS
E-300B-R.2	ELECTRICAL PROPOSED LIGHTING - LOWER LEVEL DEDUCT ALT		
E-300C-R.2	ELECTRICAL PROPOSED LIGHTING - LOWER	FA-001-R.2	FIRE ALARM INDEX SHEET
E-301-R.2	LEVEL ADD ALT ELECTRICAL PROPOSED LIGHTING - FIRST	FA-100-R.2	FIRE ALARM DEMOLITION - LOWER LEVEL BASE SCOPE
E-302-R.2	FLOOR  ELECTRICAL PROPOSED LIGHTING - SECOND	FA-100B-R.2	FIRE ALARMT DEMOLITION - LOWER LEVEL DEDUCT ALT
L-302-IX.2	FLOOR	FA-101-R.2	FIRE ALARM DEMOLITION - FIRST FLOOR
E-303-R.2	ELECTRICAL PROPOSED LIGHTING- ATTIC	FA-102-R.2	FIRE ALARM DEMOLITION - SECOND FLOOR
E-400-R.2	ELECTRICAL SINGLE- DIAGRAMS - EXISTING	FA-200-R.2	FIRE ALARM PROPOSED- LOWER LEVEL BASE
E-401-R	ELECTRICAL SINGLE -LINE DIAGRAM-		SCOPE
	PROPOSED	FA-200B-R.2	FIRE ALARM PROPOSED - LOWER LEVEL
E-500-R.2	ELECTRICAL SCHEDULES	54 0000 D 0	DEDUCT ALT
E-501-R.2	ELECTIRCAL SCHEDULES	FA-200C-R.2	FIRE ALARM PROPOSED - LOWER LEVEL ADD ALT
E-502-R.2	ELECTRICAL SCHEDULES	FA-201-R.2	FIRE ALARM PROPOSED - FIRST FLOOR
E-503-R.2	ELECTIRCAL SCHEDULES	FA-201-R.2 FA-202-R.2	FIRE ALARM PROPOSED - FIRST FLOOR
E-600-R.2	ELECTRICAL DETAILS	FA-202-R.2	FIRE ALARM PROPOSED ATTIC
		FA-300-R.2	FIRE ALARM RISER&MATRIX
P-001-R.2	PLUMBING INDEX SHEET	1 A-300-11.2	THE ALARWINIOLIKAWATTA
P-100-R.2	PLUMBING DEMOLITION - LOWER LEVEL BASE SCOPE	FP-001-R.2	FIRE PROTECTION INDEX SHEET
P-100B-R.2	PLUMBING DEMOLITION - LOWER LEVEL	FP-100-R.2	FIRE PROTECTION PROPOSED - LOWER LEVEL
1 1005 1 1.2	DEDUCT ALT	FP-101-R.2	FIRE PROTECTION PROPOSED - FIRST FLOOR
P-101-R.2	PLUMBING DEMOLITION - FIRST FLOOR	FP-102-R.2	FIRE PROTECTION PROPOSED - SECOND
P-102-R.2	PLUMBING DEMOLITION - SECOND FLOOR		FLOOR
P-103-R.2	PLUMBING DEMOLITION - ATTIC	FP-103-R.2	FIRE PROTECTION PROPOSED -ATTIC
P-200-R.2	PLUMBING DRAINAGE PROPOSED - LOWER LEVEL BASE SCOPE	T-001-R	TELECOM GENERAL NOTES, ABBREVIATIONS &
P-200B-R.2	PLUMBING DRAINAGE PROPOSED - LOWER	TD 100 D	SYMBOLDS TELECOM DEMOLITION PASEMENT
	LEVEL DEDUCT ALT	TD-100-R	TELECOM DEMOLITION - BASEMENT
P-200C-R.2	PLUMBING DRAINAGE PROPOSED - LOWER	TD-101-R	TELECOM DEMOLITION - FIRST FLOOR TELECOM DEMOLITION - SECOND FLOOR
D 004 D 0	LEVEL ADD ALT	TD-102-R TD-103-R	TELECOM DEMOLITION - SECOND FLOOR
P-201-R.2	PLUMBING DRAINAGE PROPOSED - FIRST FLOOR	1D-103-R	TELECON DEMOLITION - SITE
P-202-R.2	PLUMBING DRAINAGE PROPOSED - SECOND	T-100-R.2	TELECOM PROPOSED - LOWER LEVEL
D 000 D 0	FLOOR	T-101-R	TELECOM PROPOSED - FIRST FLOOR
P-203-R.2	PLUMBING DRAINAGE PROPOSED - ROOF	T-102-R	TELECOM PROPOSED - SECOND FLOOR
P-300-R.2	PLUMBING SUPPLY PROPOSED - LOWER LEVEL BASE SCOPE	T-103-R	TELECOM PROPOSED - ATTIC
P-300B-R.2	PLUMBING SUPPLY PROPOSED - LOWER LEVEL	T-104-R	TELECOM PROPOSED - SITE
1 000D-1/.Z	DEDUCT ALT	T-301-R	TELECOM - ENLARGED PLANS
		T-401-R	TELECOM - DETAILS
		T-402-R	TELECOM - DETAILS
		T-403-R	TELECOM - DETAILS
		T-501-R	TELECOM - DIAGRAMS AND SCHEDULES


















DESCRIPTION 1 01/09/23 PWD PCSM/NPDES SUBMISSION 2 02/14/23 PWD PCSM RESUBMISSION 3 05/24/23 PWD PCSM RESUBMISSION



M.E.P./F.P./SITE CIVIL ENGINEERS:


DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET


KINGSESSING RECREATION CENTER




SITE IMPROVEMENT PLAN NORTH

C-102-R.2







PROPOSED LEGEND EXISTING LEGEND PROPOSED BUILDING EXISTING PROPERTY LINE (APPROXIMATE) —— — — EXISTING RIGHT OF WAY LINE (APPROXIMATI EXISTING BUILDING PROPOSED CONCRETE PAVEMENT EXISTING CURB PROPOSED ASPHALT PAVEMENT EXISTING SIDEWALK PROPOSED LANDSCAPED AREA EXISTING EDGE OF MACADAM/GRAVEL PROPOSED UNIT PAVERS ----- EXISTING TRAFFIC MARKING PROPOSED POROUS PLAYGROUND SAFETY SURFACE (DIC) ----×---- EXISTING FENCE PROPOSED SYNTHETIC TURF FIELD PROPOSED ADA RAMP EXISTING TREE PROPOSED CURB ---- 5---- EXISTING MAJOR CONTOUR PROPOSED DEPRESSED CURB - EXISTING MINOR CONTOUR PROPOSED WALL PROPOSED STOP BAR/PAVEMENT MARKING EXISTING SIGN PROPOSED FENCE EXISTING BOLLARD PROPOSED SIGN EXISTING UTILITY POLE ----- 5 ------ PROPOSED MAJOR CONTOUR EXISTING INLET ------ 6 ------ PROPOSED MINOR CONTOUR ——— s ——— EXISTING SEWER PROPOSED SPOT ELEV. ——— D ——— EXISTING STORM SEWER PROPOSED LOW POINT ELEV. ----- w ----- EXISTING WATER LINE PROPOSED TOP OF CURB ELEV. ——— ∪T——— EXISTING UNDERGROUND TELEPHONE LINE PROPOSED BOTTOM OF CURB ELEV. ----- UG----- EXISTING GAS LINE ----- UE ----- EXISTING UNDERGROUND ELECTRIC ----- OE ---- EXISTING OVERHEAD WIRES EXISTING UTILITY STRUCTURES



CALL BEFORE YOU DIG

BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA

CALL 1-800-242-1776

PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL OR BLAST PENNSYLVANIA ONE-CALL SYSTEM, INC. SERIAL NUMBER(S): 20212583952

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

ISSUE DATE DESCRIPTION

1 01/09/23 PWD PCSM/NPDES SUBMISSION
2 02/14/23 PWD PCSM RESUBMISSION
3 05/24/23 PWD PCSM RESUBMISSION

**REVISIONS** 



(IEWED BY:

ROJECT COORDINATOR

ALS

KELLY MAIELLO ARCHITECT 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT:
Salt Design Studio
4100 Main Street Suite 200
Philadelphia PA 19127
www.saltdesignstudio.com
M.E.P./F.P./SITE CIVIL ENGINEERS:
Pennoni Associates
1900 Market Street Suite 300
Philadelphia PA 19103
www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103


CITY OF PHILADELPHIA

DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING

KINGSESSING RECREATION CENTER



DETAIL GRADING PLAN PLAYGROUND

DATE 08/28/23
SCALE 1" = 10'
DRAWN BY: SDL

DRAWN BY: DR


MJM


SCALE: 1"=10'-0"

GRADING PLAN DETAIL - PLAYGROUND











MODIFIED AGGREGATE




8" CONCRETE SLAB WITH 6x6x#10 WWM

SUBBASE 8" DEPTH 2A MODIFIED STONE



**DETAIL-** CITY OF PHILADELPHIA - CROSSWALK / STOPBAR (PM0102)



**DETAIL-** LIGHT POLE BASE DETAIL

NEW GALV. STL. BOLTS, WASHERS

NEW 3" X 3" X 1 1/2" X 1/4" TH.

PAINTED STEEL ANGLES (BLACK, TYP.) W/ SLOTTED HOLES FOR BOLTS

AND NUTS, TYP.

EXISTING CHANNEL

**EXISTING PICKET** 

CONDUIT EQ SPA GROUND ROD TO NEXT HANDHOLE **TOP VIEW** HANDHOLE PROVIDE BUSSMAN EXPOSED GROUND ROD STYLE HEH SINGLE CONNECTION IN-LINE FUSEHOLDER OR - 1" DIA X 48" APPROVED EQUAL WITH ANCHOR BOLTS SEE MFGR'S TEMPLATE TYPE SC FUSE INSIDE ∠ 1" X 1" CHAMFER FOR DIMENSIONS OF FINISHED GRADE HANDHOLE FOR FEED TO BASE PLATE **LUMINAIRE** PENCELL MODEL PE-6 HANDHOLE OR APPROVED EQUAL PLASTIC IDENTIFICATION CONDUIT TO NEXT -SHEETS 1'-6" BELOW MANHOLE GRADE CONTINUOUS ABOVE CONDUIT AND <sup>5</sup>/<sub>8</sub>" Χ 8' COPPER UNDISTURBED SOIL OR BACKFILL COMPACTED TO 95% MAX DRY DENSITY - 6 - #6 BARS EQ SPA #3 TIES SPACED @ 12" OC

TO NEXT

HANDHOLE

PENCELL BURIED CABLE

**ENCLOSURE** 

SECTON

**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102

> LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS:

www.kmarchitects.com

**REVISIONS** 

01/09/23 PWD PCSM/NPDES SUBMISSION

ISSUE DATE

02/14/23

DESCRIPTION

PWD PCSM RESUBMISSION

PWD PCSM RESUBMISSION

www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting

1900 Market Street Suite 300

1635 Market Street Suite 1600 Philadelphia PA 19103

Pennoni Associates

Philadelphia PA 19103

REPLACE ALL CONNECTIONS AT CORNER AND END POSTS. REPLACE EXISTING CONNECTORS AS REQ'D AT TOP AND BOTTOM OF STRUCTURAL PICKETS. 1 1/2" SQUARE WROUGHT IRON STRUCTURAL PICKETT, TYP. 1" SQUARE WROUGHT IRON INTERMEDIATE PICKET, TYP. WELD SMOOTH TO WROUGHT IRON CHANNEL 1 1/2" x 3" WROUGHT IRON CHANNEL, TYP.

SECTION A-A

<u>DEPRESSED CURB</u>

**DETAIL-** WROUGHT IRON FENCE

N.T.S.

NOTE: CONSTRUCTION PER CITY OF PHILADELPHIA SPEC AND STANDARDS.


**DETAIL-** CONCRETE CURB

- EXISTING 1 1/2" X 3" IRON STRUCTURAL PICKET W.I. CHANNEL REMOVE EXISTING W.I. COLLAR NEW 3" X 3" X 1 1/2" X 1/4" TH. PAINTED STEEL ANGLES NOTE: AFTER INSTALLATION, PEEN ALL BOLTS DETAIL— NEW CONNECTOR @ STRUCTURAL PICKET N.T.S. EXISTING 1 1/2" X 3" EXISTING GATE OR W.I. CHANNEL NEW 3" X 3" X 1 1/2" X 1/4" TH.

EXISTING 1 1/2' X 1 1/2' WROUGHT

PAINTED STEEL ANGLES BOLT THROUGH EX. POST

DETAIL—NEW CONNECTORS @ GATE OR CORNER POST



AFTER REMOVING W.I. COLLAR,

RE-ATTACH EX. BRACE W/ NEW

GALV. STL. BOLTS

·----L---L------

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23

NPDES PERMIT #PAC510302


CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


KINGSESSING RECREATION CENTER

SITE DETAILS

KLMLX21003 CS601-R.2 AS NOTED

PWD TRACKING #FY22-KING-6800-01





STANDARD DETAIL

OFFLINE CONFIGURATION

www.ContechES.com 9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069

Jellyfish' Filter

**DETAIL-** CONTECH JELLYFISH FILTER

Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103 — 1.5" Wearing Course on 2.5" Binder Course ┌*Finish Grade* Full Depth Saw Cut Require <u>Tack Coat</u> min. Class A H.E.S. Concret 2A Stone, Compacted in 6" Layers or Acceptable Fill Selected Fill RESTORATION "A" CITY OF PHILADELPHIA Finish Grade
-1.5" Wearing Course on
2.5" Binder Course DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING *∖Tack Coat* KINGSESSING RECREATION CENTER Full Depth Saw Cut Required 2A Stone,Compacted in 6" Layers or Acceptable Fill Minimum Cover: No structures shall be placed **RESTORATION "B"** less than 24 inches below the cartway or 15 inches Replace all disturbed pavement markings with Pavement Markings must be restored within 7 days of in accordance with the latest Streets Department Restoration "B" shall be used for all streets within Center City and all arterial streets outside Center City. Elsewhere, Restoration "A" shall be used. Historic **DETAIL-** TRENCH RESTORATION WITHIN RIGHT-OF-WAY SITE DETAILS PACKAGE 2 - IFB KLMLX21003 NOT FOR CONSTRUCTION CS602-R.2 08/28/23 08/28/23 AS NOTED SDL NPDES PERMIT #PAC510302 MJM PWD TRACKING #FY22-KING-6800-01

PLAN VIEW

5/8"(MIN.)
INSIDE DIRECTION


INSIDE DIRECTION

4"(MIN.)

SECTION A-A

DESCRIPTION PWD PCSM/NPDES SUBMISSION PWD PCSM RESUBMISSION 05/24/23 PWD PCSM RESUBMISSION KELLY MAIELLO ARCHITECTS Philadelphia, PA 19102 www.kmarchitects.com LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200

**REVISIONS** 



**DETAIL-** UNDERGROUND BASIN - OUTLET CONTROL STRUCTURE

WITH CAP AND 1.7" ORIFICE.

ORIFICE INV. IN 66.50

ORIFICE TO BE CENTERED ON CAP.

EXCAVATE A DITCH WIDE ENOUGH TO ACCOMMODATE THE WYE AND THE CUT-OFF WALLS. CONTRACTORS SHOULD PERFORM THE CONNECTION IN A SAFE MANNER AND PER OSHA REGULATIONS.

SHORING SHALL BE INSTALLED IN DITCHES AND TRENCHES AS PER OSHA REGULATIONS OR AS REGULATED BY PWD. VIOLATION OF THIS PROVISION WILL RESULT IN A STOP WORK ORDER AND/OR PENALTIES PRESCRIBED BY LAW. (REFER TO PHILADELPHIA PLUMBING CODE 2004 SECTION P- 1503.2 SHORING).

10. FOR CONNECTIONS TO BRICK SEWER, CONSTRUCT A 2-FOOT WIDE BY 8-INCH HIGH, CONCRETE CUTOFF WALL TO THE SPRING LINE, ON BOTH SIDES OF THE WYE, 12-INCH FROM THE LOCATION TO CUT THE SEWER PIPE.

11. USE A MINIMUM OF 3,500 PSI CONCRETE FOR THE CONCRETE CUT-OFF WALL.

12. ALLOW AT LEAST 24 HOURS FOR THE CONCRETE TO CURE BEFORE CUTTING THE SEWER PIPE.

13. CUT THE SEWER PIPE SO THAT THE WYE SECTION WILL FIT IN TIGHTLY.


14. PREVENT ANY DEBRIS FROM FLOWING INTO THE SEWER. 15. CLEAN THE BOTTOM OF THE OPENED AREA FROM LOOSE AND SOFT SOIL IF NO CRADLE, AND PLACE STONE IN THE MIDDLE LEAVING 12 INCH BELOW THE JOINTS FOR CONCRETE COLLAR.

16. INSERT THE WYE SECTION IN PLACE IMMEDIATELY, SEAL THE JOINTS AND CONSTRUCT A 24-INCH CONCRETE COLLAR AROUND BOTH


17. USE A MINIMUM OF 3,500 PSI CONCRETE COLLAR, 12 INCH DEEP AND EXTENDING 24 INCH WIDE AROUND THE JOINT. 18. ALLOW AT LEAST 24 HOURS FOR THE CONCRETE TO CURE BEFORE BACKFILLING.

19. ANY OTHER PIPELINE EXPOSED AND UNDERMINED DURING THIS OPERATION MUST BE SUPPORTED IMMEDIATELY AND BACKFILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM) AFTER THE COMPLETION OF THE CONNECTION.


**DETAIL-** WYE CONNECTION



**DETAIL-** R-TANK INLET/OUTLET



**DETAIL-** R-TANK PIPE BOOT



24" MANHOLE LID

RIM 78.50 ± MIN.

4.00'


0 0 0 0

SECTION B-B N.T.S.

PROPOSED TRASH RACK

ELEV. 63.50

SEGMENT/TOTAL: 5/20 **DETAIL-** RTANK SD 7 MODULE




CONCRETE CURB WALL - 1/2" CHAMFER, TYP. — EXISTING GRADE VARIES, SEE GRADING PLAN PLAYGROUND SURFACE > 4" PERFORATED HDPE PIPE. DAYLIGHT OR CONCRETE OUT FRONT FACE OF WALL GEOTEXTILE FABRIC CLEAN-WASHED #57 AASHTO STONE 1/2" EXPANSION JOINT MATERIAL

**DETAIL-** ORIFICE PROTECTION

**DETAIL-** CONCRETE CURB WALL AT PLAYGROUND

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01



**REVISIONS** 

01/09/23 PWD PCSM/NPDES SUBMISSION

SSUE DATE

02/14/23

05/24/23

DESCRIPTION

PWD PCSM RESUBMISSION

PWD PCSM RESUBMISSION


**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


KINGSESSING RECREATION CENTER




SITE DETAILS

KLMLX2100 CS603-R.2 AS NOTED

MJM





**REVISIONS** DESCRIPTION SSUE DATE PWD PCSM/NPDES SUBMISSION PWD PCSM RESUBMISSION 02/14/23 05/24/23 PWD PCSM RESUBMISSION

KELLY MAIELLO ARCHITECTS

1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com


LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING

KINGSESSING RECREATION CENTER




SITE DETAILS

KLMLX21003 CS605-R.2 08/28/23

AS NOTED MJM

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01



**REVISIONS** DESCRIPTION 01/09/23 PWD PCSM/NPDES SUBMISSION 2 02/14/23 PWD PCSM RESUBMISSION 3 05/24/23 PWD PCSM RESUBMISSION




Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING

KINGSESSING RECREATION CENTER




SITE DETAILS


KLMLX21003 08/28/23

MJM


CS606-R.2 AS NOTED




1900 Market Street Suite 300 Verde Architecture Consulting 1635 Market Street Suite 1600 CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING KINGSESSING RECREATION CENTER SITE DETAILS CS607-R.2 08/28/23 AS NOTED NPDES PERMIT #PAC510302 MJM PWD TRACKING #FY22-KING-6800-01





# **DETAIL-** 4 ROW SPECTATOR BLEACHERS





DETAIL- CONCRETE BLEACHER PAD LAYOUT













DETAIL- 40" HIGH BALLSTOPPER NET







**DETAIL-** TRANSITION FROM ASPHALT TO CONCRETE PAVING

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23

NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

**REVISIONS** DESCRIPTION ISSUE DATE 01/09/23 PWD PCSM/NPDES SUBMISSION 2 02/14/23 PWD PCSM RESUBMISSION 3 05/24/23 PWD PCSM RESUBMISSION




KELLY MAIELLO ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


KINGSESSING RECREATION CENTER




SITE DETAILS


KLMLX21003 CS608-R.2 08/28/23 AS NOTED

MJM



**DETAIL-** LACROSS GOAL DETAIL





**DETAIL-** 40' HEIGHT BALL CONTROL NET CONCRETE FOOTING DETAIL N.T.S.

**REVISIONS** 

3 05/24/23 PWD PCSM RESUBMISSION

01/09/23 PWD PCSM/NPDES SUBMISSION 02/14/23 PWD PCSM RESUBMISSION

DESCRIPTION

PROJECT COORDINATOR

EALS

KELLY MAIELLO ARCHITECTS
1420 Walnut Street, 15th Floor
Philadelphia, PA 19102
www.kmarchitects.com

LANDSCAPE ARCHITECT:
Salt Design Studio
4100 Main Street Suite 200
Philadelphia PA 19127
www.saltdesignstudio.com
M.E.P./F.P./SITE CIVIL ENGINEERS:
Pennoni Associates
1900 Market Street Suite 300
Philadelphia PA 19103
www.pennoni.com


LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA
DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET
11TH FLOOR, ONE PARKWAY BUILDING
PHILADELPHIA PENNSYLVANIA

KINGSESSING RECREATION CENTER

KEY PLAN



WING TITLE

SITE DETAILS

PROJECT NO.

KLMLX21003


DATE 08/28/23

SCALE AS NOTED

MJM

PWD TRACKING #FY22-KING-6800-01


PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23 NPDES PERMIT #PAC510302





-1/2" PVC CONDUIT

# SHADE STRUCTURE NOTES:

- 1. COMFORT STATION SHADE STRUCTURE IS TO BE 20' OCTAGON SHELTER AS MANUFACTURED BY POLIGON (POLIGON.COM), MODEL #OTC20. - SINGLE TIER - STANDING SEAM ROOF
- 2. THE LAYOUT PROVIDED IS FOR INFORMATION ONLY. REFER TO WRITTEN INSTALLATION INSTRUCTIONS FROM POLIGON FOR DETAILED LAYOUT PLAN, COLUMN SPACING, TEMPLATES, AND LAYOUT INSTRUCTIONS FOR THE COLUMNS AND ANCHORS.
- 3. STEEL POWDERCOAT AND ROOF COLORS TO BE SELECTED BY OWNER.







PRODUCT CUT SHEET - LED LIGHT FIXTURE

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/23 NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

**REVISIONS** DESCRIPTION SSUE| DATE 01/09/23 PWD PCSM/NPDES SUBMISSION PWD PCSM RESUBMISSION 02/14/23 3 05/24/23 PWD PCSM RESUBMISSION 06/28/23 ADDENDUM #1 **KELLY MAIELLO ARCHITECTS** 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103 CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING KINGSESSING RECREATION CENTER SITE IMPROVEMENT PLAN SOUTH KLMLX21003 C-610-R.2 08/28/23 1" = 5' MJM

TOP OF FOUNDATION MUST BE FLUSH - EDGE OF ROOF (ABOVE) WITH FINISHED GRADE OF SLAB EDGE OF 4" CONCRETE, LIGHT COLUMN **BROOM FINISH** TOOLED RADIUS, TYP. WOVEN WIRE FABRIC (WWF) -SEE PLAN \_\_\_\_× 6" 2A COMPACTED SUBBASE STONE (2) #4 CIRCULAR TIES AROUND VERTICAL BARS WITHIN TOP 5" OF FOUNDATION (6) #6 VERTICAL BARS WITH #4 HÓRIZONTAL CIRCULAR TIES AT 8" O.C. FOUNDATION, CLASS AA CONCRETE

PAVILION RECEPTACLE MOUNTING DETAIL

GFI RECEPTACLE W/-WHILE-IN-USE COVER

PAVILION COLUMN -

SCALE: N.T.S.

STEEL BASE SHOE, POWDERCOATED,

WITH  $\frac{3}{4}$  DIA. ANCHOR BOLTS, (4) PER COLUMN, F1554 HEADED ANCHORS,

12" MINIMUM EMBEDMENT IN FOUNDATION


SHADE STRUCTURE PAD AND POST FOUNDATIONS

ALL REBAR 3" CLR.

COMPACTED

SUITABLE

SUBGRADE



### PWD STANDARD EROSION AND SEDIMENTATION CONTROL NOTES:

1. AN INDUSTRIAL WASTE PERMIT WILL BE REQUIRED SHOULD PUMPING TO CITY-OWNED INFRASTRUCTURE BECOME NECESSARY DURING CONSTRUCTION. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS.

PWD IS NOT RESPONSIBLE FOR ANY CLEANING OR REPAIRS NEEDED ON CITY-OWNED INFRASTRUCTURE DUE TO FAILURE OF ANY EROSION AND SEDIMENT CONTROL PRACTICES. CONTRACTOR

- INLET PROTECTION SHOULD BE PROVIDED FOR ALL INLETS OWNED BY PWD THAT ARE LOCATED WITHIN ONE BLOCK OF THE PROJECT SITE.
- SHALL BE RESPONSIBLE FOR ANY CLEANING OR REPAIRS NEEDED.

  4. INSPECTION AND MAINTENANCE OF ALL EROSION AND SEDIMENT BEST MANAGEMENT PRACTICES SHALL OCCUR ON A WEEKLY BASIS, BEFORE ANY ANTICIPATED PRECIPITATION EVENTS, AND
- AFTER ALL PRECIPITATION EVENTS.

  5. THE MAXIMUM HEIGHT FOR STOCKPILES AREAS SHALL BE 20 FEET. THE MAXIMUM SIDE SLOPE FOR STOCKPILE AREAS SHALL NOT EXCEED 2:1.
- 6. THE ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED ON-SITE. A STOCKPILE SHALL BE MAINTAINED ON-SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 7. FILTER FABRIC FENCE AND/OR COMPOST FILTER SOCK SHOULD BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE/SOCK SECTION SHOULD BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. SUPPORT STAKES SHALL BE SPACED AT A MAXIMUM OF 8 FEET. OBJECTS OF CONSIDERABLE MASS (E.G. CONCRETE BLOCKS, SAND BAGS, ETC.) SHALL BE USED IMMEDIATELY DOWNSLOPE OF COMPOST FILTER SOCKS PLACED ON PAVED SURFACES IN LIEU OF STAKES TO HOLD THE SOCK IN PLACE. OBJECTS TO BE PLACED AT INTERVALS PER THE COMPOST FILTER SOCK MANUFACTURER'S SPECIFICATION OR PA DEP MAXIMUM SPACING OF 10' ON CENTER. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE
- 3. ANY FENCE/SOCK SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.
- 9. EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN
- 10. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY PWD AND PA DEP.
- 11. UNTIL THE SITE IS STABILIZED, ALL E&S BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL E&S BMPS PRIOR TO ANY ANTICIPATED STORM EVENT, AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING. MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED. REPLACEMENT BMPS. OR MODIFICATIONS OF THOSE INSTALLED. WILL BE REQUIRED.
- 12. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING, AS WELL AS CUTS AND FILLS, SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. PWD SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. PWD MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
- 3. AT LEAST THREE(3) DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- 14. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING BY PWD AND THE PA DEP PRIOR TO IMPLEMENTATION.
- 15. AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.
- 6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING, AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE HAVE BEEN INSTALLED AND ARE FUNCTIONING
- 17. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.

  18. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOLIND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE.
- 18. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO PWD AT THE TIME OF INSPECTION.
- 19. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL STATE, FEDERAL, AND LOCAL REGULATIONS.
- 20. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF THREE TO FIVE INCHES -- SIX TO 12 INCHES ON COMPACTED SOILS -- PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM FOUR INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF TWO INCHES OF TOPSOIL.
- 21. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE, OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES, AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.22. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED NINE INCHES IN THICKNESS.

FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF

- SATISFACTORY FILLS.
- FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.
   FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.

GROUND HEIGHT OF THE FILTER FENCE/FILTER SOCK.

- 26. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED
- 27. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.
- 28. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN ONE YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN ONE YEAR SHALL BE STABILIZED IN ACCORDANCE
- 29. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING. SLIDING. OR OTHER MOVEMENTS.
- 30. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY PWD AND
- 31. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY E&S BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST-CONSTRUCTION STORMWATER MANAGEMENT PRACTICES. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE E&S BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS,
- SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON.

  32. SEDIMENT BASINS AND/OR TRAPS SHALL BE KEPT FREE OF ALL CONSTRUCTION WASTE, WASH WATER, AND OTHER DEBRIS HAVING POTENTIAL TO CLOG THE BASIN/TRAP OUTLET STRUCTURES
- AND/OR POLLUTE THE SURFACE WATERS.

  33. DURING CONSTRUCTION, THE SELECTED CONTRACTOR IS EXPECTED TO FOLLOW THE PCSMP APPROVED BY PWD. NO CHANGE OR DEVIATION FROM THE APPROVED PCSMP IS PERMITTED WITHOUT PRIOR APPROVAL FROM PWD.
- 34. ALL WORK ASSOCIATED WITH PWD WATER CONVEYANCE AND SEWER INFRASTRUCTURE SHALL BE DONE IN ACCORDANCE WITH THE CITY OF PHILADELPHIA WATER DEPARTMENT "WATER MAIN STANDARD DETAILS AND CORROSION CONTROL SPECIFICATIONS", 1985 EDITION, AND "STANDARD DETAILS AND STANDARD SPECIFICATIONS FOR SEWERS", 1985 EDITION.
- 35. CONTACT PWD WATER TRANSPORT RECORDS (1101 MARKET STREET, 2ND FLOOR, PHONE: 215-685-6271) FOR ADDITIONAL APPROVALS AND PERMITS REQUIRED FOR ALL WATER SERVICES, METERS, AND CONNECTIONS TO THE EXISTING AND/OR PROPOSED PWD FACILITIES.
- 36. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE PADEP'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET SEQ., 271.1, AND 287.1 ET SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- 37. A DUST CONTROL PERMIT WILL BE REQUIRED WHEN COMPLETELY DEMOLISHING A BUILDING OR STRUCTURE THAT IS MORE THAN THREE (3) STORIES, GREATER THAN FORTY (40) FEET TALL, OR ENCOMPASSES MORE THAN TEN THOUSAND (10,000) SQUARE FEET; COMPLETELY OR PARTIALLY DEMOLISHING ANY BUILDING OR STRUCTURE BY IMPLOSION; OR ENGAGING IN EARTHWORKS, DEFINED AS "CLEARING, GRUBBING, OR EARTH DISTURBANCE OF ANY LAND IN EXCESS OF 5,000 SQUARE FEET."

## DUST CONTROL MEASURES:

- 1. FUGITIVE DUST FROM CONSTRUCTION, DEMOLITION, AND EARTHWORKS ACTIVITIES MAY NOT BE VISIBLE AT THE POINT IT PASSES THE WORK SITE PROPERTY LINE.
- 2. USE OF VACUUM OR SIMILAR SUCTION SYSTEMS TO CAPTURE DUST KICKED UP BY POWER TOOLS WHEN GRINDING / CUTTING
- 3. APPLICATION OF WATER OR APPROVED DUST SUPPRESSANT TO A WORK SITE WITH ONGOING EXCAVATION, LAND CLEARING, DEMOLITION, OR OTHER EARTH DISTURBANCE RELATED ACTIVITIES TO SUPPRESS DUST FORMATION.
- GENERAL PROHIBITION AGAINST DRY ABRASIVE BLASTING OF EXTERIOR SURFACES OPEN TO THE OUTSIDE AIR WHEN TEMPERATURE IS ABOVE FREEZING.
   COVERING AND WETTING OF STOCKPILE EARTH, SAND, GRAVEL, AND OTHER SIMILAR CONSTRUCTION MATERIALS.
- 6. USE OF A MATERIAL CHUTE WHEN DROPPING MATERIAL OR DEBRIS MORE THAN 20 FT OUTSIDE OF THE EXTERIOR WALLS OF A BUILDING OR STRUCTURE. MATERIALS MUST BE WETTED WHEN DROPPED, AND / OR EXIT OF CHUTE MUST BE SEALED AGAINST THE TOP OF THE RECEIVING CONTAINER / DUMPSTER.
- 7. ALL TEMPORARY PERIMETER FENCING AROUND MUST HAVE A DUST CONTROL FABRIC; MUST MEASURE A MINIMUM OF 5FT IN HEIGHT FROM THE BOTTOM OF THE FENCING.
- 8. A 10 MILE PER HOUR SPEED LIMIT FOR ALL EQUIPMENT AND TRUCKS TRAVELING WITHIN THE WORK SITE.
- 9. WETTING AND SWEEPING OF ROADWAYS / ACCESS ROAD IN A WORK SITE TO PREVENT DUST FORMATION.
- 10. VEHICLE ACCESS POINTS MUST BE EQUIPPED WITH DUST SUPPRESSION MEASURES (I.E. WHEEL WASH SYSTEMS, RUMBLE GRATES, AND OR GRAVEL PADS).

## TEMPORARY EROSION AND SEDIMENT CONTROL:

- . INLET PROTECTION SHALL BE APPLIED, AS DETAILED ON THE PLAN, TO EVERY INLET WHICH HAS BEEN CONSTRUCTED TO THE ROADWAY SUBBASE ELEVATION. INLET PROTECTION MUST BE PROVIDED FOR ALL CITY OWNED INLETS LOCATED WITHIN ONE CITY BLOCK OF THE PROJECT SITE.
- 2. SILT FENCES/COMPOST FILTER SOCKS SHALL BE INSTALLED DOWNSLOPE OF ALL AREAS TO BE DISTURBED BEFORE ANY WORK BEGINS. SILT FENCE/COMPOST FILTER SOCKS AND ROCK FILTERS SHALL BE INSTALLED AS NEAR AS POSSIBLE TO THE LOCATIONS SHOWN ON THE PLAN. FILTER FABRIC/COMPOST FILTER SOCKS SHOULD BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION SHOULD BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. SUPPORT STAKES AND/OR OBJECTS OF CONSIDERABLE MASS SHALL BE SPACED AT A MAXIMUM OF 8 FEET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FILTER FENCE/FILTER SOCK.
- 3. STOCKPILED TOPSOIL MOUNDS SHALL BE STABILIZED BY APPLYING TEMPORARY SEED AND A PERIMETER SILT FENCE/FILTER SOCK SHALL BE INSTALLED AROUND EACH MOUND. TEMPORARY SEEDING SHALL BE PER PENNDOT FORM 408. SECTION 804(B).
- 4. ALL STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AS NEAR AS POSSIBLE TO THE LOCATION SHOWN ON THE PLAN. THE ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED ON SITE. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS
- SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.

  5. FREQUENT INSPECTION SHALL BE MADE ON THE FILTER FABRIC FENCE/COMPOST FILTER SOCK. DAMAGED FENCES/SOCK SHALL BE IMMEDIATELY REPLACED. SEDIMENT MUST BE REMOVED WHERE

# 6. FREQUENT INSPECTION SHALL BE MADE ON THE FILTER FABRIC FENCE/COMPOST FILTER SOCK. DAMAGED FENCES/SOCK SHALL BE IMMEDIATELY REPLACED. SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHTS OF FENCE/SOCK. SILT FENCE/COMPOST FILTER SOCK WHICH HAS BEEN TOPPED OR UNDERMINED IS TO BE REPLACED WITH A ROCK FILTER OUTLET. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.

## PROCEDURE FOR STABILIZATION OF SOILS FOUND OR SUSPECTED TO BE CONTAMINATED:

- DISTURBED EARTH TO BE IMMEDIATELY STABILIZED WITH SEEDING THROUGH THE USE OF HYDROSEEDING TECHNIQUES AND HAY OR STRAW MULCHING TO CONTAIN CONTAMINATED SOILS.
   PLASTIC LINER TO BE INSTALLED BELOW TEMPORARY TOPSOIL STOCKPILES. TOPSOIL STOCKPILE TO BE STABILIZED WITH SEEDING AND TO BE COVERED BY A TEMPORARY DAILY COVER
- IMMEDIATELY PER THE REQUIREMENTS OF THE PADEP E&S GUIDELINES.
- 3. EXPOSED SOILS TO BE SPRINKLED WITH WATER ON A DAILY BASIS UNTIL MOIST TO PREVENT DUST GENERATION AND TRANSPORT.

  4. LITHIZE APPROVED DA DEP EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT SOIL FROM LEAVING THE SITE METHODS INCLUDE BUT ARE NOT LIMITED TO WHEE
- 4. UTILIZE APPROVED PA DEP EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT SOIL FROM LEAVING THE SITE. METHODS INCLUDE, BUT ARE NOT LIMITED TO WHEEL WASH, SILT FENCE, INLET FILTER PROTECTION, ROCK CONSTRUCTION ENTRANCE, ETC.

## PWD STANDARD SEQUENCE OF CONSTRUCTION NOTES:

- AT LEAST SEVEN (7) DAYS PRIOR TO ANY EARTH DISTURBANCE, THE INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) MUST BE CALLED TO SCHEDULE A PRECONSTRUCTION MEETING.
   AT LEAST THREE (3) DAYS PRIOR TO RAIN GARDEN AND SUBSURFACE DETENTION BASIN INSTALLATION, THE INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) MUST BE CALLED TO SCHEDULE AN INSPECTION (FOR EACH SMP).
- 3. ALL STONE THAT MAKES UP THE (SUBSURFACE DETENTION BASIN) MUST REMAIN FREE OF SEDIMENT. IF SEDIMENT ENTERS THE STONE, THE CONTRACTOR MAY BE REQUIRED TO REMOVE THE SEDIMENT AND REPLACE IT WITH CLEAN-WASHED STONE.
- 4. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) FOR A FINAL INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.
- 5. AS SOON AS SLOPES, CHANNELS, DITCHES, AND OTHER DISTURBED AREAS REACH FINAL GRADE, THEY MUST BE STABILIZED. CESSATION OF ACTIVITY FOR FOUR (4) DAYS OR LONGER REQUIRES
- 6. THE NPDES NOTICE OF TERMINATION (N.O.T.) MUST BE SUBMITTED TO PA DEP UPON COMPLETION OF CONSTRUCTION (WHEN APPLICABLE).
- WATER PUMPED FROM WORK AREAS SHOULD BE TREATED FOR SEDIMENT REMOVAL PRIOR TO DISCHARGING TO A "SURFACE WATER" (WHEN APPLICABLE).

#### SEQUENCE OF CONSTRUCTION:

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE AND SHALL BE COMPLETED IN COMPLIANCE WITH PHILADELPHIA WATER DEPARTMENT AND CHAPTER 102 REGULATIONS.

AT LEAST 7 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LAND OWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND A REPRESENTATIVE FROM THE PHILADELPHIA WATER DEPARTMENT TO SCHEDULE A PRE-CONSTRUCTION MEETING. ALSO, AT LEAST 3 WORKING DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM, INC. AT

1-800-242-1776 FOR BURIED UTILITY LOCATIONS.

BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE PHILADELPHIA WATER DEPARTMENT AND PA DEPT. OF ENVIRONMENTAL PROTECTION (PADEP).

REGULATIONS AT 25 PA CODE 260.1 et seq. AND 287.1 et seq.

THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE PHILADELPHIA WATER DEPARTMENT AND PADEP AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL PROPOSED SOIL/ROCK SPOIL AND BORROW AREAS ON OR OFFSITE.

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT

- 1. CONSTRUCTION WILL BEGIN UPON RECEIPT OF ALL REQUIRED PERMITS FROM CITY OF PHILADELPHIA AND PADEP.
- 2. PRIOR TO PROCEEDING WITH CONSTRUCTION, CONFIRM THE LOCATION AND ELEVATION OF ALL EXISTING UTILITIES. MAINTAIN AND PROTECT ALL EXISTING UTILITIES TO REMAIN AT ALL TIMES.
- 3. AS SOON AS SLOPES, CHANNELS, DITCHES, AND OTHER DISTURBED AREAS REACH FINAL GRADE, THEY MUST BE STABILIZED. CESSATION OF ACTIVITY FOR FOUR (4) DAYS OR LONGER REQUIRES TEMPORARY STABILIZATION.
- 4. WATER PUMPED FROM WORK AREAS SHOULD BE TREATED FOR SEDIMENT REMOVAL PRIOR TO DISCHARGING TO A "SURFACE WATER".
- 5. DISTURBANCE OF THE PROJECT SITE MUST BE KEPT TO THE ABSOLUTE MINIMUM.6. ALL SOIL MOVEMENT SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND APPLICABLE MUNICIPAL, STATE, AND FEDERAL REGULATIONS.
- 7. EXISTING PEDESTRIAN TRAFFIC SHALL BE MAINTAINED OR PROPERLY DIRECTED AROUND THE SITE THROUGHOUT THE DURATION OF THE PROJECT.
- 8. DELINEATE LIMITS OF DISTURBANCE AS OUTLINED ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLANS WITH ORANGE CONSTRUCTION FENCING. LINEAR UTILITY TRENCHES, AS OUTLINED ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLANS, DO NOT NEED TO BE DELINEATED WITH FENCE. UTILITY TRENCHES SHALL BE BACKFILLED AT THE END OF EACH DAY AND TEMPORARILY STABILIZED. CONTRACTOR SHALL NOT PERFORM ANY OTHER WORK OUTSIDE OF THE APPROVED LIMITS OF DISTURBANCE.
- 10. INSTALL ROCK CONSTRUCTION ENTRANCE AT THE SITE ENTRANCE AS SHOWN ON THE APPROVED PLAN. EXISTING SUBGRADE TO BE REMOVED WITHIN THE FOOTPRINT OF THE ROCK CONSTRUCTION ENTRANCE FOR CONSTRUCTION PER THE APPROVED DETAIL. CONTRACTOR SHALL EXCAVATE ONLY ENOUGH AREA FOR WHICH ROCK CONSTRUCTION ENTRANCE CAN BE INSTALLED BY THE END OF EACH WORK DAY. CONSTRUCTION VEHICLES SHALL ENTER AND EXIT THE SITE THROUGH THE ENTRANCE. ROCK CONSTRUCTION ENTRANCE TO BE RESTORED AND
- SEDIMENT IS TO BE REMOVED ON A DAILY BASIS.

  11. INSTALL COMPOST FILTER SOCK DOWN GRADE AND ON CONTOUR OF DISTURBED AREAS PER THE APPROVED PLAN, DISTURBED AREAS SHALL BE IMMEDIATELY STABILIZED AND GRADED TO SLOPE
- 12. STAKE OUT AND INSTALL ORANGE CONSTRUCTION FENCE AROUND THE LIMITS OF ANY PROPOSED, OR EXISTING TO BE PROTECTED, INFILTRATION AREA (TREE TRENCHES AND RAIN GARDENS). CONTRACTOR TO MINIMIZE THE COMPACTION OF SOIL WITHIN THE INFILTRATION AREA. HEAVY MACHINERY IS PROHIBITED TO ENTER WITHIN THE LIMITS OF THE PROPOSED INFILTRATION AREA.
- 13. THE STAGING AREA SHALL BE ESTABLISHED ON THE SITE AND SHALL NOT IMPEDE RUNOFF FROM REACHING THE EXISTING INLETS. STAGING AREAS NOT CREATED ON EXISTING PAVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPROVED DETAIL.
- 14. CONCRETE WASHOUT TO BE INSTALLED ADJACENT TO THE ROCK CONSTRUCTION ENTRANCE PER THE APPROVED PLANS.
   15. CONTRACTOR SHALL TEMPORARILY STABILIZE THE SITE AT THE END OF EACH WORK DAY (WHENEVER POSSIBLE) AND AT THE START OF A RAINFALL EVENT. CESSATION OF EARTH DISTURBANCE
- ACTIVITIES FOR AT LEAST 4 DAYS REQUIRES TEMPORARY STABILIZATION.

  16. CONTRACTOR TO HAVE PUMPED WATER FILTER BAG ONSITE AND AVAILABLE FOR DEWATERING OF EXCAVATED AREAS WHEN REQUIRED. FILTER BAG TO DISCHARGE OVER UNDISTURBED
- 17. CONTRACTOR TO BEGIN DEMOLITION OF THE REMAINING EXISTING SITE FEATURES. REMOVE VEGETATION AND CONSTRUCTION OF THE FILL. DISTURBED AREAS SHALL BE STABILIZED WHENEVER POSSIBLE AND AS REQUIRED.
- 18. PRIOR TO SMP INSTALLATION, THE INSPECTIONS COORDINATOR OF PWD (OFFICE: 215-685-6387) MUST BE CALLED TO SCHEDULE AN INSPECTION.
- 19. \*INSTALL SUBSURFACE BASIN (SEE SUBSURFACE BASIN SEQUENCE OF CONSTRUCTION) AND OUTLET CONTROL STRUCTURE
- 20. \*INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS.
- 21. FOLLOWING THE CONSTRUCTION OF THE SMP, THE SITE IMPROVEMENTS INCLUDING THE SYNTHETIC TURF FIELD, CONCRETE PATHWAYS, PLAYGROUND SURFACING AND LANDSCAPING SHALL BE CONSTRUCTED. ENSURING ALL SMPS AND E&S BMPS ARE PROTECTED AND MAINTAINTED THROUGHOUT THE CONSTRUCTION PROCESS.
- 22. REMOVE ROCK CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT WHEN CONCRETE WORK IS COMPLETE AND CONSTRUCTION EQUIPMENT NO LONGER NEEDS ACCESS.
- 23. ONCE THE SITE AREA HAS ACHIEVED A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION, REMOVE TEMPORARY EROSION AND SEDIMENTATION BMP'S INCLUDING ROCK CONSTRUCTION ENTRANCES AND INLET PROTECTION. ANY AREA DISTURBED DURING THE
- REMOVAL OF A TEMPORARY BMP SHALL BE IMMEDIATELY STABILIZED WITH SEEDING AND STRAW MULCH.
- 24. ENSURE THAT ALL POST-CONSTRUCTION STORMWATER MANAGEMENT BMP'S ARE IN PLACE AND FUNCTIONING ACCORDING TO THE APPROVED PCSM PLANS, DETAILS, AND NARRATIVE. CONTACT THE PHILADELPHIA WATER DEPARTMENT FOR A FINAL INSPECTION AND SUBMIT RECORD DRAWINGS TO COMPLETE THE PROJECT.
   25. REMOVAL AND DISPOSAL OF BITUMINOUS MATERIAL SHALL BE IN COMPLETED IN ACCORDANCE WITH DETAILS AND REGULATIONS OF THE MUNICIPALITY, PADEP, AND PENNDOT, AS APPLICABLE AND
- 26. CONTRACTOR TO COLLECT AND REMOVE ALL TRASH/DEBRIS ON SITE.

IS SUBJECT TO INSPECTION AND APPROVAL AS APPROPRIATE.

TOWARDS THE SITE AND COMPOST FILTER SOCK.

VEGETATED AREAS IN ACCORDANCE WITH THE APPROVED PLANS.

#### \*CRITICAL STAGE - DURING THE BMP INSTALLATION, A LICENSED PROFESSIONAL ENGINEER, REGISTERED ARCHITECT/LANDSCAPE ARCHITECT, PROFESSIONAL LAND SURVEYOR, GEOLOGIST, OR LICENSED CONTRACTOR MUST DOCUMENT THE INFORMATION AND MEASUREMENTS REQUIRED ON THE BMP CONSTRUCTION CERTIFICATION FORMS WITHIN THE CERTIFICATION PACKAGE.

#### SEQUENCE OF CONSTRUCTION: SUBSURFACE BASIN

- AT LEAST 3 DAYS PRIOR TO THE CONSTRUCTION OF THE DETENTION BASIN, THE CONTRACTOR
   SHALL CONTACT PWD INSPECTIONS COORDINATOR (OFFICE 215-685-6387).
- CONTRACTOR TO NOTIFY DESIGN ENGINEER 3 DAYS PRIOR TO CONSTRUCTION OF BASIN.
   EXCAVATE FOOTPRINT TO SPECIFIED ELEVATION.

5. INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS

4. INSTALL STORMWATER BASIN, INCLUDING LOW FLOW DEVICE, AS SPECIFIED BY MANUFACTURER IN THE AREA SPECIFIED ON PLANS.

**EROSION AND SEDIMENTATION CONTROL NOTES:** 

WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION.

- SPECIFICATIONS.

  6. CONNECT PIPES TO STORMWATER BASIN IN LOCATIONS SPECIFIED ON PLANS.
- BACKFILL TO GRADE.

# SEQUENCE OF CONSTRUCTION: MEDIA FILTER

SHALL CONTACT PWD INSPECTIONS COORDINATOR (OFFICE 215-685-6387).

2. CONTRACTOR TO NOTIFY DESIGN ENGINEER 3 DAYS PRIOR TO INSTALLATION OF MEDIA

1. AT LEAST 3 DAYS PRIOR TO THE INSTALLATION OF THE MEDIA FILTER, THE CONTRACTOR

- FILTER.

  3. EXCAVATE FOOTPRINT TO SPECIFIED ELEVATION.
- 4. INSTALL MEDIA FILTER WATER QUALITY DEVICE IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS.
- 5. CONNECT PIPES TO MEDIA FILTER WATER QUALITY DEVICE IN LOCATIONS SPECIFIED ON

# 6. BACKFILL TO GRADE.

# 1. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.

- 2. AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.
- AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
   ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN
- 5. AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.
- 6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN.
- 7. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- 8. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED, IF NECESSARY, AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 20 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER.
- 9. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.
- REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THIS SITE.

  11. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.

10. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT

- ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.
   THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING.
- 13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS.
- VEHICLES AND EQUIPMENT MAY NEITHER ENTER DIRECTLY NOR EXIT DIRECTLY FROM LOTS. VEHICLES AND EQUIPMENT MAY ONLY ENTER AND EXIT THE CONSTRUCTION SITE VIA A STABILIZED ROCK CONSTRUCTION ENTRANCES ON HAINES STREET.
   UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. THE OPERATOR WILL MAINTAIN AND MAKE AVAILABLE TO NORTHAMPTON COUNTY CONSERVATION DISTRICT COMPLETE, WRITTEN INSPECTION
- RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED.

  16. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION.

LOGS OF ALL THOSE INSPECTIONS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND

- 17. SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 18. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES.
- 19. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES 6 TO 12 INCHES ON COMPACTED SOILS PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL.
- ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
   ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN THICKNESS, UNLESS DIRECTED OTHERWISE BY ENGINEER.
- 22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- 23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.

CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.

24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.

25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD.

26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED.

- SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.

  27. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR OTHER PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH
- 28. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR MOTHER MOVEMENTS.
- 29. EROSION AND SEDIMENT BMPS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.

30. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL

- 31. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON.
  - 32. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION.
  - 33. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION.

#### ADDITIONAL EROSION AND SEDIMENTATION CONTROL NOTES:

- 1. CONCRETE WASH WATER SHALL BE HANDLED IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. IN NO CASE SHALL IT BE ALLOWED TO ENTER ANY SURFACE WATERS OR GROUNDWATER SYSTEMS.
- 2. EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS.
- 3. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED.
- 4. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.
- 5. STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN

### **EROSION AND SEDIMENTATION MAINTENANCE:**

- 1. DURING THE LIFE OF THE PROJECT, ALL EROSION AND SEDIMENTATION CONTROL DEVICES MUST BE PROPERLY MAINTAINED. MAINTENANCE SHALL INCLUDE THE INSPECTION OF EROSION CONTROL FACILITIES AFTER EACH MEASURABLE RUNOFF EVENT (>0.25 INCH) AND ON A WEEKLY BASIS, UNLESS MORE FREQUENT INSPECTION IS REQUIRED. IMMEDIATELY PERFORM CLEANOUT, REPAIR AND REPLACEMENT OF THE FACILITIES AS NEEDED. (REGRADE, RESEED AND MULCH WASHED OUT AREAS AS NEEDED.)
- 2. UNTIL THE SITE IS STABILIZED ALL EROSION AND SEDIMENTATION BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL SITE INSPECTIONS WILL BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE. THE COMPLIANCE ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE INSPECTION LOG WILL BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO PWD/DEP UPON REQUEST.
- WHERE BMP'S ARE FOUND TO FAIL TO ALLEVIATE EROSION OR SEDIMENT POLLUTION THE PERMITTEE OR CO-PERMITTEE NOTIFY THE PHILADELPHIA WATER DEPARTMENT OF THE FAILURE AND SHALL INCLUDE THE FOLLOWING INFORMATION:
- 3.1. THE LOCATION AND SEVERITY OF THE BMP'S FAILURE AND ANY POLLUTION EVENTS.

8. INLET FILTER BAGS SHALL BE CLEANED OUT OR REPLACED WHEN BAG IS HALF FULL.

3.2. ALL STEPS TAKEN TO, REDUCE, ELIMINATE AND PREVENT THE RECURRENCE OF THE NON-COMPLIANCE.
3.3. THE TIME FRAME TO CORRECT THE NONCOMPLIANCE, INCLUDING THE EXACT DATES WHEN THE ACTIVITY WILL RETURN TO COMPLIANCE.

IS TRACKED ONTO PUBLIC STREETS SHALL BE COLLECTED AND RETURNED TO THE SITE OR OTHERWISE PROPERLY REMOVED BY A STREET SWEEPER.

- 4. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENTATION BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S OR MODIFICATIONS OF THOSE INSTALLED WILL BE NEEDED.
- 5. SEEDED AREAS THAT HAVE WASHED AWAY SHALL BE FILLED AND GRADED, AS NECESSARY, AND THEN RESEEDED. A STRAW COVER SHALL BE APPLIED TO RETAIN THE SEED ALONG WITH AN ANCHORING METHOD DESCRIBED ON THE ATTACHED MULCH ANCHORING GUIDE, UNTIL IT HAS A CHANCE TO ROOT PROPERLY.
- 6. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE
- APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.
- 7. SEDIMENT REMOVED FROM BMPs SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR
- PLACED IN TOPSOIL STOCKPILES.
- 9. SEDIMENT SHALL BE REMOVED FROM COMPOST FILTER SOCKS WHEN REACHING ONE HALF THE HEIGHT OF THE SOCK, IF USED.

  10. THE CONTRACTOR SHALL INSPECT ALL ROCK CONSTRUCTION ENTRANCES ON A DAILY BASIS AND SHALL ENSURE THAT SEDIMENT IS NOT BEING TRACKED ONTO PUBLIC STREETS. SEDIMENT THAT
- 11. EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS, IF USED.
- 12. FILL MATERIAL FOR EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE COMPACTED IN MAXIMUM 6 INCH LAYERED LIFTS AT 95% DENSITY.
   13. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP'S MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMP'S MUST BE STABILIZED IMMEDIATELY.
- 14. BEFORE INITIATING ANY REVISION TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY EFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE PA DEP. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
- 15. ALL PUMPING OF SEDIMENT LADEN WATER OR POTENTIALLY SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, AND FILTRATION SYSTEM, SUCH AS A TIGG FILTRATION SYSTEM CANSORB CP-2000 AND DISCHARGED OVER NON-DISTURBED AREAS.

16. DEWATERING OR PUMPING OF GROUNDWATER MUST DISCHARGE TO CITY OWNED INFRASTRUCTURE, IF REQUIRED, CONTRACTOR SHALL OBTAIN AN INDUSTRIAL DISCHARGE PERMIT THROUGH THE

INDUSTRIAL WASTE UNIT. DISCHARGE MUST BE CONNECTED DIRECTLY TO A COMBINED OR SANITARY SEWER LATERAL.

17. PWD SHALL NOT BE RESPONSIBLE FOR ANY CLEANUP OR REPAIRS NEEDED ON CITY-OWNED INFRASTRUCTURE OR REPAIRS DUE TO FAILURE OF APPROVED EROSION CONTROL MEASURES OF CITY OWNED INFRASTRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CLEANUP AND REPAIRS DUE TO FAILURE OF APPROVED EROSION CONTROL MEASURES.

### RECYCLING AND DISPOSAL NOTE:

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 et seq. AND 287.1 et seq.

CONSTRUCTION WASTES INCLUDE, BUT NOT LIMITED TO:
- INLET PROTECTION
- PUMPED WATER FILTER BAGS

# TEMPORARY SEEDING SITE PREPARATION:

ACTIVITY HAS CEASE, INCLUDING TOPSOIL STOCKPILES SHALL BE STABILIZED IMMEDIATELY BY

TEMPORARY STABILIZATION OF ALL EXPOSED EARTH SURFACES WHERE CONSTRUCTION

18. IF CONTAMINATED SOILS ARE ENCOUNTERED DURING CONSTRUCTION, CONTACT OWNER.

- THE FOLLOWING METHODS AND MATERIALS.

  1 APPLY ONE (1) TON OF AGRICULTURAL GRADE LIMESTONE PER ACRE PLUS FERTILIZER
- (10-10-10) AT THE RATE OF 1000 LBS PER ACRE AND WORK INTO SOIL WHEREVER POSSIBLE.
   APPLY 100% ANNUAL RYEGRASS SEED AT A RATE OF 4 TO 5 LBS PER 1000 SQUARE FEET.

# 3. AFTER SEEDING MULCH WITH HAY OR STRAW AT A RATE OF THREE (3) TONS PER ACRE.

CULTURAL OPERATIONS AT RIGHT ANGLES TO THE SLOPE.

PERMANENT SEEDING SITE PREPARATION:

PERMANENT STABILIZATION OF THE ALL EXPOSED EARTH SURFACES AFTER THE COMPLETION OF

THE SITE GRADING AND IMPROVEMENTS SHALL BE ACCOMPLISHED BY THE FOLLOWING METHODS

- AND MATERIALS:

  1. AFTER INSTALLATION OF THE NEEDED SURFACE WATER CONTROL MEASURES, PERFORM ALL
- OBTAIN SOILS TESTING FROM AN INDEPENDENT LABORATORY TO DETERMINE NECESSARY SOILS MODIFICATIONS.
- IN THE ABSENCE OF SOILS TESTING, APPLY AGRICULTURAL GRADE LIMESTONE AT THE MINIMUM RATE OF SIX TONS LIMESTONE PER ACRE (276 LBS. PER 1,000 SQUARE FEET).
   IN THE ABSENCE OF SOILS TESTING, WORK IN FERTILIZER AT THE RATE OF 1000 LBS. OF
- 10-20-20 OR EQUIVALENT PER ACRE.5. SMOOTH AND FIRM SEEDED AREAS WITH CULTIPACKER, OR OTHER SIMILAR EQUIPMENT,
- PRIOR TO SEEDING.
- COVER GRASS SEEDS WITH 1/4 INCH OF TOPSOIL WITH SUITABLE EQUIPMENT.
   APPLY STRAW MULCH AT A RATE OF 3.0 TON PER ACRE IMMEDIATELY AFTER SEEDING.
- USE SOD WHERE THERE IS A HEAVY CONCENTRATION OF WATER AND IT IS IMPORTANT TO GET A QUICK VEGETATIVE COVER IN ORDER TO PREVENT GULLYING. USE SOD AT THE DIRECTION OF THE MUNICIPAL ENGINEER OR HIS AUTHORIZED REPRESENTATIVE.
   HYDROSEEDING SHALL BE AN ACCEPTABLE ALTERNATIVE TO THE ABOVE SEEDING WHEN PERFORMED IN ACCORDANCE WITH PENNDOT PUB. 408 SECTIONS 804 AND 805 AND
- APPROVED BY THE SITE ENGINEER.
- PERMANENT SEEDING NOTES:

  1. SPREAD AND FINE GRADE 12" TOPSOIL ON ALL AREAS TO BE PERMANENTLY SEEDED.
- BEFORE SEEDING, APPLY APPROPRIATE SOIL MODIFICATIONS.
   INSTALL EROSION/SEED BLANKET WHERE NEEDED.
- 4. WATER AND MAINTAIN ALL LAWN AREAS.
- 6. IF GROUND COVER IS NOT OTHERWISE SPECIFIED ON THE APPROVED LANDSCAPING PLANS, USE SEED MIXTURE 2, AS SHOWN IN TABLE 11.4.

5. RESEED BARE OR THIN AREAS AS DIRECTED BY THE ENGINEER.

APPLY STRAW MULCH AT 3.0 TON/ACRE IMMEDIATELY AFTER SEEDING.
 APPLY STRAW AND MULCH DURING NON-GROWING SEASONS (NOVEMBER - MARCH)



CALL BEFORE YOU DIG

BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA

CALL 1-800-242-1776

PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS

NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL OR

BLAST PENNSYLVANIA ONE-CALL SYSTEM, INC.

SERIAL NUMBER(S): 20212583950

### UNFORSEEN EROSIVE CONDITIONS NOTES:

- 1. SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF AND/OR SEDIMENT DISPLACEMENT. STOCKPILES OF WOOD CHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.
- 2. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, D.E.P., SUB-PART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.
- SHRUBS WHICH ARE TO REMAIN IN PLACE. CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGES, INCLUDING REPLACING TREES OR SHRUBS IN KIND IF NECESSARY

IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING REGULARLY TRACKED ONTO PUBLIC

STREETS. THE CONTRACTOR SHALL BE PREPARED. UPON WRITTEN NOTICE GIVEN BY THE

CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PROTECT EXISTING TREES AND

# CITY OF PHILADELPHIA, TO PROVIDE TIRE WASHING FACILITIES AT ALL ROCK CONSTRUCTION ENTRANCES.

STANDARD NOTE TO COMPLY WITH NPDES CHECKLIST ITEM #2.B.XV (#3.B.XV FOR AN INDIVIDUAL NPDES PERMIT)

**CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE:** 

FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND DETERMINATION OF CLEAN FILL WILL REST WITH THE CONTRACTOR.

CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE). CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL

IF THE SITE WILL NEED TO IMPORT OR EXPORT MATERIAL FROM THE SITE. THE RESPONSIBILITY

MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL". ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS. ENVIRONMENTAL DUE DILIGENCE: THE APPLICANT MUST PERFORM ENVIRONMENTAL DUE DILIGENCE TO DETERMINE IF THE FILL MATERIALS ASSOCIATED WITH THE PROJECT QUALIFY

AS CLEAN FILL. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE

THE PAST LAND LISE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN

DATA BASE SEARCHES REVIEW OF PROPERTY OWNERSHIP REVIEW OF PROPERTY USE

HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS,

TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC

ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS

SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO

NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF

DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".

FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE. THESE REGULATIONS ARE AVAILABLE ON-LINE AT WWW.PACODE.COM <a href="https://www.pacode.com">https://www.pacode.com</a>.

CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE NOTES:

WITH THE EXCEPTION OF SITES ENROLLED IN DEP'S LAND RECYCLING AND ENVIRONMENTAL REMEDIATION STANDARDS (ACT 2) PROGRAM, ALL FILL MATERIAL EXCAVATED AND USED ON-SITE, IMPORTED TO THE SITE, AND EXPORTED FROM THE SITE, MUST MEET THE DEFINITION OF CLEAN FILL, AS DEFINED IN THIS PERMIT. REGULATED FILL MAY ONLY BE USED ON ACT 2 SITES, IN ACCORDANCE WITH STANDARDS ESTABLISHED BY THAT PROGRAM.

THE PERMITTEE SHALL CONDUCT ENVIRONMENTAL DUE DILIGENCE TO VERIFY THAT FILL

EXCAVATED ON-SITE THAT IS USED TO ESTABLISH FINAL GRADE, FILL IMPORTED TO THE PROJECT SITE, AND FILL EXPORTED FROM THE PROJECT SITE IS CONSIDERED CLEAN FILL. IF DUE DILIGENCE RESULTS IN EVIDENCE OF A RELEASE, AS DEFINED IN DEP'S MANAGEMENT OF FILL POLICY (285-2182-773), THAT HAS AFFECTED THE FILL MATERIAL, THE PERMITTEE SHALL TEST THE MATERIAL TO DETERMINE WHETHER THE MATERIAL QUALIFIES AS CLEAN FILL, AND FORM FP-001 (CERTIFICATION OF CLEAN FILL) MUST BE COMPLETED, RETAINED BY THE PERMITTEE OR THE PROPERTY OWNER ON-SITE, AND BE MADE AVAILABLE TO DEP/PWD UPON REQUEST.

IN THE EVENT THAT FILL EXCAVATED ON-SITE THAT IS USED TO ESTABLISH FINAL GRADE, FILL IMPORTED TO THE PROJECT SITE, OR FILL EXPORTED FROM THE PROJECT SITE IS FOUND TO BE

RECULATED FILL DURING THE TERM OF PERMIT COVERAGE, WHERE THE LITUZATION OF THE

DISTURBANCE ACTIVITIES SHALL CEASE UNTIL SUCH TIME THAT THE PERMITTEE OBTAINS ALL

NECESSARY PERMITS OR APPROVALS FROM DEP, INCLUDING NEW NPDES PERMIT COVERAGE.

REGULATED FILL WILL REQUIRE A PERMIT FROM DEP'S WASTE MANAGEMENT PROGRAM FARTH

IF THE PERMITTEE BECOMES AWARE DURING EARTH DISTURBANCE ACTIVITIES THAT SOILS IN THE AREA OF EARTH DISTURBANCE CONTAIN CONCENTRATIONS OF REGULATED SUBSTANCES EXCEEDING THE RESIDENTIAL MEDIUM-SPECIFIC CONCENTRATIONS FOR SOIL IN 25 PA. CODE CHAPTER 250, THE PERMITTEE SHALL NOTIFY DEP IN ACCORDANCE WITH PART A III.D OF THIS PERMIT AND CEASE EARTH DISTURBANCE ACTIVITIES IN AREAS OF KNOWN SOIL CONTAMINATION UNTIL AUTHORIZED TO RESUME BY DEP/PWD.

PACKAGE 2 - IFB

08/28/23

NPDES PERMIT #PAC510302

PWD TRACKING #FY22-KING-6800-01

NOT FOR CONSTRUCTION

REVISIONS

DESCRIPTION

PWD PCSM/NPDES SUBMISSION

PWD PCSM RESUBMISSION

PWD PCSM RESUBMISSION

SSUE DATE

01/09/23

02/14/23

05/24/23

REVIEWED BY:
PROJECT COORDINATOR

LANDSCAPE ARCHITECT:
Salt Design Studio
4100 Main Street Suite 200
Philadelphia PA 19127
www.saltdesignstudio.com
M.E.P./F.P./SITE CIVIL ENGINEERS:
Pennoni Associates
1900 Market Street Suite 300

Philadelphia, PA 19102

www.pennoni.com

LEED CONSULTANT:
Verde Architecture Consulting
1635 Market Street Suite 1600
Philadelphia PA 19103

Philadelphia PA 19103

CITY OF PHILADELPHIA


DEPARTMENT OF PUBLIC PROPERTY

DJECT TITLE

KINGSESSING RECREATION CENTER

1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING



EROSION & SEDIMENTATION CONTROL NOTES

KLMLX21003

DATE 08/28/23

SCALE

DRAWN BY: SDL


DRAWN BY:

SDL

CHECKED BY:

MJM

NOTE: ALL DIMENSIONS AND CONDITIONS SHALL BE VERIF CONTRACTOR AT THE SITE BEFORE PROCEEDING W



SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE

TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.


BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24

BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S


UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

WELL VEGETATED, GRASSY AREA

**DETAIL-** COMPOST FILTER SOCK



-EXISTING GROUND - AASHTO #57 (OR APPROVED EQUIVALENT UNLESS AREA IS ESTABLISHED ON EXISTING PAVEMENT) **DETAIL-** STAGING AREA



MAXIMUM DRAINAGE AREA = 1/2 ACRE.

INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS.

ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR REMAIN PERMANENTLY.


BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE. INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS, ALL NEEDED

REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT

AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS. **DETAIL-** FILTER BAG INLET PROTECTION - TYPE M INLET

AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.




SHALL BE REQUIRED FOR ALL INSTALLATIONS.

MAXIMUM DRAINAGE AREA = 1/2 ACRE. INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS

ROLLED EARTHEN BERM SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. SIX INCH MINIMUM HEIGHT ASPHALT BERM SHALL BE MAINTAINED UNTIL ROADWAY SURFACE RECEIVES FINAL COAT. AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS, A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS, ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE OF ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS. **DETAIL-** FILTER BAG INLET PROTECTIO - TYPE C INLET




REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE. RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

PUBLICATION 408, SECTION 735, CLASS 4, TYPE A GEOTEXTILE. MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT

GEOTEXTILE FOR ROCK CONSTRUCTION ENTRANCE TO MEET THE REQUIREMENTS OF PENNDOT

**DETAIL-** ROCK CONSTRUCTION ENTRANCE



**REVISIONS** 

SSUE DATE

02/14/23

05/24/23

DESCRIPTION

PWD PCSM/NPDES SUBMISSION

PWD PCSM RESUBMISSION

PWD PCSM RESUBMISSION

**KELLY MAIELLO ARCHITECTS** 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: Salt Design Studio 4100 Main Street Suite 200 Philadelphia PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103


www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600

Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING

KINGSESSING RECREATION CENTER




EROSION & SEDIMENTATION CONTROL DETAILS

KLMLX21003 [C-852-R.2]

MJM

NOT FOR CONSTRUCTION 08/28/23 NPDES PERMIT #PAC510302 PWD TRACKING #FY22-KING-6800-01

PACKAGE 2 - IFB



DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.


BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE. EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTÈXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND

SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER. WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.


FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

**DETAIL-** PUMPED WATER FILTER BAG




1. THOSE TREES WHICH ARE WITHIN TWENTY-FIVE (25) FEET OF ANY PROPOSED EXCAVATION OR GRADING OPERATION, OR IN ANY OTHER LOCATION DEEMED APPROPRIATE BY THE ENGINEER, SHALL BE PROTECTED BY INSTALLING AND MAINTAINING A FENCE AT THE DRIP LINE. 2. NO BOARDS OR OTHER MATERIAL SHALL BE NAILED TO TREES DURING CONSTRUCTION. 3. HEAVY EQUIPMENT OPERATORS SHALL AVOID DAMAGING EXISTING TREE TRUNKS. 4. TREE TRUNKS AND EXPOSED ROOTS DAMAGED DURING CONSTRUCTION SHALL BE PROTECTED FROM FURTHER DAMAGE BY BEING TREATED 5. TREE LIMBS DAMAGED DURING CONSTRUCTION SHALL BE PROPERLY PRUNED AND TREATED IMMEDIATELY. 6. THE OPERATION OF HEAVY EQUIPMENT OVER ROOT SYSTEMS OF SUCH TREES SHALL BE MINIMIZED IN ORDER TO PREVENT SOIL 7. DAMAGED TREES SHALL BE FERTILIZED TO AID IN THEIR RECOVERY. 8. CONSTRUCTION DEBRIS SHALL NOT BE DISPOSED OF NEAR OR AROUND TREES.

**DETAIL-** TREE PROTECTION FENCE



**DETAIL-** CONCRETE WASHOUT

A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING INSTALL ON FLAT GRADE FOR OPTIMUM PERFORMANCE. COMPOST SOCKS SHALL BE STAKED IN THE MANNER RECOMMENDED BY THE MANUFACTURER AROUND THE PERIMETER OF THE GEOMEMBRANE SO AS TO FORM A RING WITH THE ENDS OF THE DOCK LOCATED AT THE UPSLOPE CARE SHALL BE TAKEN TO ENSURE CONTINUOUS CONTACT OF THE SOCK WITH THE GEOMEMBRANE AT ALL LOCATIONS. 18" DIAMETER FILTER SOCK MAY BE STACKED ONTO DOUBLE 24" DIAMETER FILTER SOCKS IN PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT. MAINTENANCE: ALL CONCRETE WASHOUT FACILITIES SHOULD BE INSPECTED DAILY, DAMAGED OR LEAKING WASHOUTS SHOULD BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY. ACCUMULATED MATERIALS SHALL BE REMOVED WHEN THEY REACH 50% CAPACITY. GEOMEMBRANE SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT




FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL FABRIC WIDTH SHALL BE 30 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT


LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.


**DETAIL-** SILT FENCE




**DETAIL-** CONSTRUCTION FENCE










SITE IMPROVEMENTS OVERVIEW PLAN



- SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC TO SALT DESIGN STUDIO ON MAY 10, 2021.
- 2. SITE IMPROVEMENTS SHOWN ON THIS DRAWING AND NOT DELINEATED AS ALTERNATE SCOPE, SHALL BE CONSIDERED BASE SCOPE.
- 3. KINGSESSING LIBRARY PROJECT IS NOT INCLUDED IN THIS PROJECT SCOPE. SEE
- PLAN FOR PROJECT LIMITS.
- 4. SALT DESIGN STUDIO / LANDSCAPE (L-SERIES) SCOPE INCLUDES THE FOLLOWING:
- SITE PAVEMENTS (CONCRETE, ASPHALT, POURED-IN-PLACE SAFETY SURFACING). COLOR PAVEMENT COATINGS.
- CONCRETE CURBING. • SITE FURNISHINGS, INCLUDING BENCHES, TABLES, BIKE RACKS, RECEPTACLES,
- AND PPR STANDARD SIGNAGE.

• LAYOUT OF SITE LIGHTING, IN COORDINATION WITH MEP ENGINEER. PLAYGROUND EQUIPMENT.

PLANTING.

IMPORTANT NOTE: SITE IMPROVEMENT ADD ALTERNATES CAN BE FOUND IN L-800-R.2 DRAWING SERIES.

STAMP AREA

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/2023

		1	1	8
		100 A		
		DI		
G	YNG.			
R	13			
G	STATE OF		Mar.	KR

**REVISIONS** 

ISSUE DATE

DESCRIPTION

KELLY MAIELLO ARCHITECTS

Philadelphia, PA 19102 www.kmarchitects.com LANDSCAPE ARCHITECT: SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127


1420 Walnut Street, 15th Floor

www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


> KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS - PACKAGE 2



SITE IMPROVEMENTS **OVERVIEW PLAN** 

PROJECT NO.	DRAWING NO.
070	
2023	L-100-R.2
E HOWN	
/N BY: F	
KED BY:	

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE



**REVISIONS** 

ISSUE DATE DESCRIPTION



PROJECT COORDINATOR

**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT: SALT DESIGN STUDIO


161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

www.pennoni.com

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING

> KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS - PACKAGE 2




SITE LAYOUT PLAN -BASE SCOPE


KMA PROJECT NO.
21070
DATE
08/28/2023
SCALE

L-101-R.2

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE WORK

NOT FOR CONSTRUCTION 08/28/2023





SITE FURNISHINGS & EQUIPMENT NOTES:

1. SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC TO SALT DESIGN STUDIO ON MAY 10, 2021.

2. ALL CONSTRUCTION SHALL CONFORM TO CITY, COUNTY, STATE, AND FEDERAL REGULATIONS.

3. THESE CONTRACT DOCUMENTS MAKE NO REPRESENTATIONS

AS TO THE MEANS AND METHODS OF CONSTRUCTION. 4. CONTRACTOR TO OBTAIN THE LANDSCAPE ARCHITECT'S

APPROVAL OF LAYOUT OF ALL SITE FURNISHINGS AND EQUIPMENT PRIOR TO INSTALLATION. 5. DIMENSIONS ARE PROVIDED TO EDGE OF PAVEMENT, FACES OF

WALLS, EDGE OF SITE FURNISHING OR FENCE, OR CENTERLINE OF PLAY EQUIPMENT, UNLESS NOTED OTHERWISE. 6. ELEMENTS SHALL BE PARALLEL OR PERPENDICULAR, UNLESS

7. SEE FURNISHINGS & EQUIPMENT SCHEDULES BELOW FOR QUANTITIES, PRODUCT, AND MANUFACTURER INFORMATION.

NOTED OTHERWISE.

8. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR ALL EQUIPMENT FOUNDATIONS TO LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL IN COORDINATION WITH EQUIPMENT MANUFACTURER PRIOR TO INSTALLATION. SHOP DRAWINGS ALSO INCLUDE PLANS SHOWING LAYOUT OF ALL EQUIPMENT

9. FOUNDATIONS FOR ALL FURNISHINGS AND EQUIPMENT SHALL BE LOCATED ON SITE AND REVIEWED IN FIELD WITH LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. NO POURED-IN-PLACE SAFETY SURFACE SHALL BE INSTALLED UNTIL FOUNDATIONS FOR FURNISHINGS AND EQUIPMENT ARE INSTALLED.

FOUNDATIONS WITHIN SAFETY SURFACE AREA FOR PLAY AREA.

#### SITE FURNISHINGS SCHEDULE - BASE SCOPE:

EXTENTS OF KINGSESSING

PEDESTRIAN POST LIGHT

REMOVABLE BOLLARDS (RB)

FIXED PEDESTAL TABLE (T3 & T4)

TRASH AND RECYCLING

RECEPTACLES (TR & RR)

PICNIC TABLE (PT)

ASTM SAFETY ZONE

FOR PLAY EQUIPMENT

PLANT BED; SEE L-106-R.2 FOR MORE INFORMATION

EXISTING LIGHT TO REMAIN

PPR SIGN

LIBRARY IMPROVEMENTS

BACKED BENCH (BB)

BIKE RACKS (BR)

KEY	ITEM	QTY	PRODUCT NAME & MODEL NUMBER	MANUFACTURER	OPTIONS, FINISHES & COLORS	INSTALLATION
ВВ	BACKED BENCH	16	BENCH 165, MODEL NO. 165-60D, SERIES 69- 860-3-ART	IDLIMOR	6' CAST BENCH, DOUGLAS FIR SEAT; WITH CUSTOM CENTER AND END ARMRESTS; POWDERCOAT COLOR: BLACK	SURFACE MOUNT
BR	BIKE RACK	3	BIKE RACK SERIES 83, MODEL NO. 83-00/S-2	DU MOR	POWER COATED BIKE RACK; SURFACE MOUNT; POWERCOAT COLOR: BLACK	EMBEDDED IN CONCRET
Т3	FIXED PEDESTAL TABLE, 3 SEATS (ADA)	2	TABLE 76, MODEL NO. 76-43PL, SERIES 76-PL-3-S-1	DU MOR	4' SQUARE TABLE, 3 SEATS, 4 X 4 PLASTIC; PLASTIC COLOR: CEDAR; POWERCOAT COLOR: BLACK	EMBEDDED IN CONCRET
T4	FIXED PEDESTAL TABLE, 4 SEATS	3	TABLE 76, MODEL NO. 76-44PL, SERIES 76-PL- 3-S-1	DU MOR	4' SQUARE TABLE, 4 SEATS, 4X4 PLASTIC; RECYCLED PLASTIC COLOR: CEDAR; POWERCOAT COLOR: BLACK	EMBEDDED IN CONCRET
РТ	PICNIC TABLE	1	TABLE 72, MODEL NO. 72-80-PL	DU MOR	8' LENGTH GALVANIZED PICNIC TABLE; RECYCLED PLASTIC COLOR: CEDAR	SURFACE MOUNT
TR	TRASH RECEPTACLE	2	RECEPTACLE 157, MODEL NO. 157-32-BT	IDU MOR	32-GALLON STEEL RECEPTACLE WITH SHIELD AND BONNET COVER WITH 10" OPENING; POWERCOAT COLOR: BLACK	SURFACE MOUNT
RR	RECYCLING RECEPTACLE	2	RECEPTACLE 157, MODEL NO. 157-32-BT-RC	DU MOR	32-GALLON STEEL RECEPTACLE WITH SHIELD, RECYCLE LID WITH 4" OPENING, AND BONNET COVER WITH 10" OPENING; POWERCOAT COLOR: RECYCLE BLUE	SURFACE MOUNT
RB	REMOVABLE BOLLARD	5	BOLLARD 400, MODEL NO. 400-42/S-1SL	DU MOR	42" HEIGHT; S-1SL GROUND SLEEVE WITH CAP; POWDERCOAT COLOR: BLACK	EMBEDDED IN CONCRET

#### PLAY EQUIPMENT SCHEDULE - BASE SCOPE:

KEY	ПЕМ	QTY	PRODUCT NAME	PRODUCT NO.	MANUFACTURER	OPTIONS & COLORS	MAX. FALL HT.	INCLUSIVE
A	10-SEAT SWING FRAME	1	SWING FRAME, 10 SEAT, 8-FT. HEIGHT	KSW9210	KOMPAN	AATI-WRAP SUSPENSIONS; LEGS, CONNECTION & CROSSBEAM STEEL COLOR: ORANGE RAL2010	4'-8"	N/A
В	SWING SEAT: BABY SWINGS	4	SWING SEAT BABY	SW990023	КОМРАЛ	STAINLESS STEEL CHAINS; ANTI-WRAP MOUNT; SWING COLOR: BLACK	N/A	✓
с	SWING SEAT: ADA 2-5	1	SWING SEAT ADA 2-5	\$67860	KOMPAN	STAINLESS STEEL CHAINS; ANTI-WRAP MOUNT; SWING COLOR: YELLOW	N/A	✓
D	SWING SEAT: STANDARD BELT	4	SWING SEAT, STAINLESS, 8 FT	SW990011	KOMPAN	STAINLESS STEEL CHAINS; ANTI-WRAP MOUNT; SWING COLOR: BLACK	N/A	✓
E	SWING SEAT: ADA 5-12	1	SWING SEAT ADA 5-12	\$67855	КОМРАЛ	STAINLESS STEEL CHAINS; ANTI-WRAP MOUNT; SWING COLOR: YELLOW	N/A	✓
F	LITTLE KIDS OBSTACLE COURSE	1	DOUBLE ROPE TRAIL	COR20830	KOMPAN	COLOR: ULTRAMARI NE BLUE	6'-7"	✓
G	SPINNER BOWL	2	SPINNER BOWL	ELE400024	КОМРАЛ	COLOR: ORANGE RAI2010	2'-0"	✓
н	GOBLET DRUM	2	RHAPSODY <sup>S</sup> GOBLET DRUM JUNIOR	228215	LANDSCAPE STRUCTURES	COLORS: PRO SHIELD FINISH - II MON, RECYCLED PERMALENE - SKY	N/A	✓
ı	KETTLE DRUM	2	RHAPSODY <sup>®</sup> KETTLE DRUM JUNIOR	228217	LANDSCAPE STRUCTURES	COLORS: PRO SHIELD FINISH - II MON, RECYCLED PER MALENE - SKY	N/A	✓
1	KUNDU DRUM	2	RHAPSODY <sup>8</sup> KUNDU DRUM JUNIOR	228218	LANDSCAPE STRUCTURES	COLORS: PRO SHIELD FINISH - IJ MON, RECYCLED PERMALENE - SKY	N/A	✓
к	BIG KIDS OBSTACLE COURSE	1	GIANT REED	COR104402	KOMPAN	STEEL COLOR: ORANGE RAL2010; ROPE COLOR: ULTRAMARINE BLUE RAL5002; MEMBRANE COLOR(S): TBD	9'-0"	✓
ι	SPICA SPI \NER	2	SPICA 1	GXY8014	KOMPAN	COLORS: STANDARD	3'-3"	✓
						1		

## SITE SIGNACE SCHEDILLE BASE SCODE.

SIGN NO.	PPR CODE	SIGN TYPE	SITE LOCATION	NOTES
IDENTIFICA	ATION (ID) &	INFORMATION (INFO) SIGNS		
1	PID.4	PARK ID & INFO	KINGSESSING AVENUE SITE ENTRANCE	
2	PID.4	PARK ID & INFO	SITE ENTRANCE AT CORNER OF S. 51ST STREET & KINGSESSING AVENUE	IDENTIFIES PARK NAME, PPR BRAND, RULES/PERMITS,
3	PID.4	PARK ID & INFO	SITE ENTRANCE AT CORNER OF S. 51ST STREET & CHESTER AVENUE	HOURS/CONTACT, SECURITY, & REGULATORY INFO
3	PID.4	PARK ID & INFO	CHESTER AVENUE SITE ENTRANCE	
4	PLY.1	PLAYGROUND ID & INFO	BIG KIDS PLAY AREA	
5	PLY.1	PLAYGROUND ID & INFO	SWINGS AREA	IDENTIFIES PLAYGROUND, RULES OF USE, & EMERGENCY INFO
6	PLY.1	PLAYGROUND ID & INFO	LITTLE KIDS PLAY AREA	
7	RUL.1	COURT ID & INFO	TENNIS COURTS	
8	RUL.1	COURT ID & INFO	BASKETBALL COURTS	
9	RUL.1	FIELD ID & INFO	BASEBALL FIELD	IDENTIFIES COURT & COURT RULES, FIELD & FIELD RULES
10	RUL.1	FIELD ID & INFO	SOCCER FIELD	
11	RUL.1	COURT ID & INFO	WALLBALL COURT	
12	PID.1	POOL AREA ID & INFO	POOL ENTRANCE	IDENTIFIES POOL INFO
13	RUL.4	POOL AREA ID & INFO	POOL ENTRANCE	IDENTIFIES POOL AREA RULES
14	PWF.1	PARK WAYFINDING	PICNIC LAWN	PROVIDES PEDESTRIAN WAYFINDING
15	RUL.6	SINGLE MESSAGE RULE	PICNIC LAWN	NO ANIMALS
16	RUL.6	SINGLE MESSAGE RULE	PICNIC LAWN	NO ANIMALS
17	RUL.6	SINGLE MESSAGE RULE	KINGSESSING AVENUE SITE ENTRANCE	NO ANIMALS
18	RUL.6	SINGLE MESSAGE RULE	SITE ENTRANCE AT CORNER OF 51ST STREET & CHESTER AVENURE	NO ANIMALS
19	RUL.6	SINGLE MESSAGE RULE	SITE ENTRANCE AT CORNER OF 51ST STREET & KINGSESSING AVENURE	NO ANIMALS
20	RUL.6	SINGLE MESSAGE RULE	CHESTER AVENUE SITE ENTRANCE	NO ANIMALS
21	RUL.6	SINGLE MESSAGE RULE	MULTI-SPORTS FIELD	NO ANIMALS
22	RUL.6	SINGLE MESSAGE RULE	PLAYGROUND	NO ANIMALS

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/2023

**REVISIONS** 

DESCRIPTION

ISSUE DATE

PROJECT COORDINATOR

KELLY MAIELLO ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300


LANDSCAPE ARCHITECT:

Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


> KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS - PACKAGE 2




SITE FURNISHINGS AND **EQUIPMENT PLAN - BASE** 

L-103-R.2

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE







STAMP AREA

#### SCHEDULE:

1772.0	CVAADOL	07/		2474100			LANAS CUITOUT		
ITEM	SYMBOL	QTY	TABEL	CATALOG	MANUFACTURER	NOMBER LAMPS	LAMP OUTPUT	LLF	INPUT POWI
PEDESTRIAN SCALE POLE MOUNTED AREA LIGHT		6	PL1	DSC4Lx-R3W-5G350-30-XX-XX-UNV	SELUX	1	3409	0.95	32
PEDESTRIAN SCALE POLE MOUNTED AREA LIGHT		4	PL2	DSC4Lx-R3W-5G350-30-XX-XX-UNV	SELUX	1	3357	0.95	32
PEDESTRIAN SCALE POLE MOUNTED AREA LIGHT		3	PL3	DSC4Lx-R3W-5G350-30-XX-XX-UNV	SELUX	1	3624	0.95	32

iption Symbol Avg Max Min Max/Min Avg/Mi + 0.2 fc 5.8 fc 0.0 fc N/A N/A

#### NOTES:

- 1. FIXTURES MOUNTED AT 14' MINIMUM.
- 2. CALCULATION TAKEN AT GRADE.
- 3. CALCULATIONS ARE ESTIMATED BASED ON THE INFORMATION

**REVISIONS** DESCRIPTION ISSUE DATE

Control of		
EN S		
Le Late		
SA SEL	STATE OF THE PARTY	

DBO IECT COORDINATOR

KELLY MAIELLO ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT:


SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

www.pennoni.com

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


> KINGSESSING RECREATION CENTER BUILDING AND SITE **IMPROVEMENTS - PACKAGE 2**



SITE PHOTOMETRY PLAN -BASE SCOPE

DRAWING NO.
L-105-R.


ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE



LIBRARY IMPROVEMENTS

EXTENTS OF KINGSESSING

UNDERSTORY TREE



SEE NOTE #14 BELOW



— x—— x— EXISTING FENCE TO REMAIN

#### PLANTING NOTES:

- 1. SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC TO SALT DESIGN STUDIO ON MAY 10,
- 2. ALL CONSTRUCTION SHALL CONFORM TO CITY, STATE, AND FEDERAL REGULATIONS.
- 3. CONTRACTOR SHALL FIELD VERIFY LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND SUBTERRANEAN ELEMENTS PRIOR TO COMMENCING WORK. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT FOR RELOCATION INSTRUCTIONS IF A PLANT IS LOCATED WITHIN 3'-0" OF AN UNDERGROUND UTILITY.
- 4. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES PRIOR TO BEGINNING OR CONTINUING WORK.
- 6. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT IF SUBSOIL CONDITIONS SHOW EVIDENCE OF UNEXPECTED WATER RETENTION IN TREE OR SHRUB PITS.
- 7. CONTRACTOR SHALL PROVIDE EROSION CONTROL MEASURES TO PREVENT SOIL LOSS AS INDICATED ON CIVIL ENGINEERING DRAWINGS.
- 8. ALL IMPORTED PLANTING SOIL MUST BE TESTED AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. SEE SPECIFICATIONS.
- 9. SEE PLANT SCHEDULE FOR PLANT SIZES, QUANTITIES, SPECIES AND CONDITION.
- 10. TREE AND SHRUB LOCATIONS SHALL BE STAKED OR FLAGGED IN FIELD FOR REVIEW AND APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO STARTING PLANT INSTALLATION.
- 11. ALL TREES SHALL HAVE AT LEAST 24" APPROVED PLANTING SOIL AROUND ROOTBALL. ALL SHRUBS SHALL HAVE AT LEAST 18" APPROVED PLANTING SOIL AROUND ROOTBALL.
- 12. CONTRACTOR SHALL INSTALL IRRIGATION BAGS FOR ALL NEW TREES IMMEDIATELY UPON COMPLETION OF
- 13. MULCH, COMPOST AND/OR LEAF LITTER IS TO BE INSTALLED AS INDICATED ON DETAILS AND IN SPECIFICATIONS.
- 14. TEMPORARY DRIP IRRIGATION TO BE INSTALLED AND MAINTAINED FOR ONE FULL YEAR FROM PROJECT CLOSEOUT. SUBMIT SHOP DRAWINGS OF TEMPORARY DRIP IRRIGATION LAYOUT AND INFORMATION SUBMITTALS FOR REVIEW AND APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 15. TEMPORARY PLANT PROTECTION FENCING TO BE INSTALLED IMMEDIATELY UPON COMPLETION OF PLANT INSTALLATION. PROTECTION FENCING TO BE LOCATED ALONG ALL PLANT BED EDGES TO PROTECT PERENNIAL AND SHRUB PLANTINGS, SEE 8/L-5002-R.2 FOR DETAIL.
- 14. ANY EXISTING TURF LAWN THAT IS DISTURBED BY EARTHWORK OR OTHER CONSTRUCTION ACTIVITY SHALL BE

# PLANT SCHEDULE:

KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONDITION	SPACING				
CANOPY	ANOPY TREES									
CK	12	Cladrastis kentuckea	Yellowwood	3"-3.5" CAL.	B&B or CONTAINER	AS SHOWN				
FG	2	Fagus grandifolia	American Beech	3"-3.5" CAL.	B&B	AS SHOWN				
LT	3	Liriodendron tulipifera	Tulip Poplar	3"-3.5" CAL.	B&B	AS SHOWN				
TA	1	Tillia americana 'Redmond'	American Basswood	3"-3.5" CAL.	B&B	AS SHOWN				
	18	TOTAL CANOPY TREES								

UNDERS'	TORY TRE	REES					
CC	8	Cercis canadensis	Eastern Redbud	8'-10' HT.	B&B OR CONTAINER	AS SHOV	
CF	7	Cornus florida 'Appalachian Spring'	Flowering Dogwood	8'-10' HT.	B&B OR CONTAINER	AS SHOV	
	15	TOTAL UNDERSTORY TREES					
CHDLIBC							

Dwarf Fothergilla

Drooping Laurel

Dwarf Virginia Sweetspire #3

#3

**REVISIONS** 

DESCRIPTION ISSUE DATE



PROJECT COORDINATOR

**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT:

SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300

www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

Philadelphia PA 19103

AS SHOWN

AS SHOWN

AS SHOWN

CONTAINER


CONTAINER

CONTAINER

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING


> KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS - PACKAGE 2




SITE PLANTING PLAN -BASE SCOPE

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE

L-106-R.2





5'-0"

MEDIUM PLAY MOUND

SMALL PLAY MOUND


STAMP AREA

PLAY MOUNDS: TYPICAL ELEVATIONS

8'-0"

LARGE PLAY MOUND

SCALE: 1/4" = 1'-0"



#### LAYOUT AND GRADING NOTES:

HIGH POINT (HP)

- SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC TO SALT DESIGN STUDIO ON MAY 10, 2021.
- ALL CONSTRUCTION SHALL CONFORM TO CITY, COUNTY, STATE, AND FEDERAL REGULATIONS.
- 3. VERIFY DIMENSIONS AND ACCEPT CONDITIONS BEFORE PROCEEDING WITH ANY WORK. REPORT DISCREPANCIES TO LANDSCAPE ARCHITECT.
- THESE CONSTRUCTION DOCUMENTS MAKE NO REPRESENTATIONS AS TO THE MEANS AND METHODS OF CONSTRUCTION.
   DO NOT SCALE DRAWINGS; CONSULT LANDSCAPE ARCHITECT FOR ANSWERS TO
- ALL DIMENSIONAL QUESTIONS.

   CONTRACTOR TO OBTAIN THE LANDSCAPE ARCHITECT'S APPROVAL OF LAYOUT
- OF PAVEMENT PAINT AND SAFETY SURFACE PATTERNS PRIOR TO INSTALLATION.
- DIMENSIONS ARE PROVIDED TO EDGES OF PLAY MOUNDS, EDGES OF PAVEMENT, FRONT OF CURBS, OR FACES OF WALLS, UNLESS NOTED OTHERWISE.
   PROVIDE SLOPES ON PAVEMENT SURFACES AS INDICATED ON GRADING AND
- DRAINAGE PLAN TO ALLOW FOR POSITIVE DRAINAGE.

  9. PROVIDE A CONSISTENT SLOPE ON ALL PLAY MOUNDS.
- 10. SEE SHEET L-101-R.2 FOR LAYOUT OF SITE PAVEMENTS.
- 11. SEE DETAIL 5 / L-501-R.2 FOR TYPICAL PLAY MOUND INSTALLATION DETAIL.



**REVISIONS** 

DESCRIPTION

ISSUE DATE

EVIEWED BY:

PROJECT COORDINATOR

KELLY MAIELLO ARCHITECTS
1420 Walnut Street, 15th Floor
Philadelphia, PA 19102
www.kmarchitects.com

LANDSCAPE ARCHITECT:

SALT DESIGN STUDIO
161 Leverington Avenue, Suite 1005
Philadelphia, PA 19127
www.saltdesignstudio.com
M.E.P./F.P./SITE CIVIL ENGINEERS:

M.E.P./F.P./SITE CIVIL ENGINEERS:
Pennoni Associates
1900 Market Street Suite 300
Philadelphia PA 19103
www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA


DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING

KINGSESSING RECREATION
CENTER BUILDING AND SITE
IMPROVEMENTS - PACKAGE 2

IMPROVEMENTS





PLAN ENLARGEMENT
- PLAY MOUNDS

DATE 08/28/2023 SCALE DRAWING NO. DRAWING NO.

CKED BY:

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE






KELLY MAIELLO ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com LANDSCAPE ARCHITECT: SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103 CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY 1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING KINGSESSING RECREATION CENTER BUILDING AND SITE **IMPROVEMENTS - PACKAGE 2** PLANTING DETAILS L-502-R.2 ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE

REVIEWED BY:

PROJECT COORDINATOR

**REVISIONS** 

DESCRIPTION



1 SITE ADD ALTERNATES OVERVIEW PLAN

N 0' 15' 30' (

## GENERAL NOTES:

- SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC TO SALT DESIGN STUDIO ON MAY 10, 2021.
- 2. THE L-800 SERIES DRAWINGS DOCUMENT A SERIES OF ADD ALTERNATES FOR SITE IMPROVEMENTS. EACH ADD ALTERNATE TO BE PRICED/BID SEPERATELY FOR EVALUATION BY OWNER. OWNER TO SELECT INDIVIDUAL OR GROUPS OF SITE ADD ALTERNATES TO BE INSTALLED IN ADDITION TO SITE IMPROVEMENTS BASE SCOPE AS DESCRIBED ON PREVIOUS L-SERIES DRAWINGS.
- 3. SITE ADD ALTERNATES TO BE COORDINATED WITH CIVIL ENGINEERING SCOPE AND M/E/P ENGINEERING SCOPE, AS NEEDED.
- 4. IF FURTHER CLARIFICATION IS NEEDED FOR SITE ADD ALTERNATES NOTED IN L-800 SERIES DRAWINGS, CONTRACTOR TO COORDINATE WITH LANDSCAPE ARCHITECT.

SITE ADD ALTERNATES SCOPE OF WORK:

ADD ALTERNATE S3: TENNIS COURTS, SEE L-801 FOR MORE INFORMATION.
 ADD ALTERNATE S4: DIAGONAL PATH, SEE L-802 FOR MORE INFORMATION.

STAMP AREA

PACKAGE 2 - IFB NOT FOR CONSTRUCTION 08/28/2023

	æ	, λ	1/2	o	B
	/\chi_				
			77		
c	W		ATT.		
1			W.		
	19	SET BY		AN	CC

**REVISIONS** 

ISSUE DATE

DESCRIPTION

www.kmarchitects.com

LANDSCAPE ARCHITECT:
SALT DESIGN STUDIO
161 Leverington Avenue, Suite 1005
Philadelphia, PA 19127

1420 Walnut Street, 15th Floor

Philadelphia, PA 19102

www.saltdesignstudio.com

M.E.P./F.P./SITE CIVIL ENGINEERS:
Pennoni Associates
1900 Market Street Suite 300
Philadelphia PA 19103
www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA

DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET

11TH FLOOR, ONE PARKWAY BUILDING


KINGSESSING RECREATION
CENTER BUILDING AND SITE
IMPROVEMENTS - PACKAGE 2

SITE ADD ALTERNATES
OVERVIEW PLAN

D70

L-800-R.2

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE



LEGEND:

1 L-501-R.2 ASPHALT PAVEM

-x---x- EXISTING FENCE TO REMAIN

# SITE LAYOUT & MATERIALS NOTES:

1. SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC. TO SALT DESIGN STUDIO ON MAY 10, 2021.

- 2. ALL CONSTRUCTION SHALL CONFORM TO CITY, COUNTY, STATE, AND FEDERAL REGULATIONS.
- 3. VERIFY DIMENSIONS AND ACCEPT CONDITIONS BEFORE PROCEEDING WITH ANY WORK. REPORT DISCREPANCIES TO LANDSCAPE ARCHITECT.
- THESE CONSTRUCTION DOCUMENTS MAKE NO REPRESENTATIONS AS TO THE MEANS AND METHODS OF CONSTRUCTION.
- 5. DO NOT SCALE DRAWINGS; CONSULT LANDSCAPE ARCHITECT FOR ANSWERS TO ALL DIMENSIONAL QUESTIONS.
- LOCATE AND MARK EXISTING UTILITIES.

  7. COORDINATE ALL UTILITY WORK WITH THE LOCATIONS AND FINAL GRADES OF ALL OTHER WORK AS SHOWN

6. CONTACT UTILITY COMPANIES AS REQUIRED BY STATE AND LOCAL REGULATIONS BEFORE DIGGING TO

- 7. COORDINATE ALL UTILITY WORK WITH THE LOCATIONS AND FINAL GRADES OF ALL OTHER WORK AS SHOWN ON THE ENGINEER'S DRAWINGS. WHERE CONFLICTS OCCUR, NOTIFY THE ENGINEER AND LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF UTILITIES TO MAKE ADJUSTMENTS AS REQUIRED. IF NEW UTILITIES HAVE BEEN INSTALLED IN CONFLICT WITH CURBS, WALLS, PAVING, OR OTHER STRUCTURES AT DEPTHS TOO SHALLOW FOR PROPER COVER BENEATH NEW GRADES OR INCORRECT FINISHED GRADE, THEY SHALL BE ADJUSTED OR REMOVED AND REPLACED AS NECESSARY AT CONTRACTOR'S EXPENSE.
- 8. CONTRACTOR TO OBTAIN THE LANDSCAPE ARCHITECT'S APPROVAL OF LAYOUT OF ALL SITE IMPROVEMENTS PRIOR TO INSTALLATION.
- 9. DIMENSIONS ARE PROVIDED TO EDGE OF PAVEMENT, FRONT OF CURB, FACES OF WALLS, OR OBJECT CENTERLINE, UNLESS NOTED OTHERWISE.
- 10. ELEMENTS SHALL BE PARALLEL OR PERPENDICULAR, UNLESS NOTED OTHERWISE.
- 11. PROVIDE SLOPES ON PAVEMENT SURFACES AS INDICATED ON GRADING AND DRAINAGE PLAN TO ALLOW FOR POSITIVE DRAINAGE.
- 11.1. NO PONDING SHALL BE PERMITTED ON FINISHED GRADE OF SITE PAVEMENTS. AREAS WHERE PONDING OCCURS SHALL BE REGRADED AND REPAIRED AT CONTRACTOR'S EXPENSE.
- 12. COORDINATE INSTALLATION OF FURNISHINGS AND EQUIPMENT FOUNDATIONS PRIOR TO INSTALLING SITE PAVEMENTS.

REVISIONS

ISSUE DATE DESCRIPTION



EVIEWED BY:

PROJECT COORDINATOR

KELLY MAIELLO ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

LANDSCAPE ARCHITECT:
SALT DESIGN STUDIO
161 Leverington Avenue, Suite 1005
Philadelphia, PA 19127
www.saltdesignstudio.com

M.E.P./F.P./SITE CIVIL ENGINEERS: Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com


LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA

DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET
11TH FLOOR, ONE PARKWAY BUILDING
PHILADELPHIA PENNSYLVANI

KINGSESSING RECREATION CENTER BUILDING AND SITE IMPROVEMENTS - PACKAGE 2



DRAWING TITLE

SITE ADD ALTERNATE S3 - TENNIS COURTS

DRAWING NO.

21070

ATE

1/28/2023

CALE
2 SHOWN

RAWN BY:

1/AF

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE

#### SITE ADD ALTERNATE S4 - SITE FURNISHINGS SCHEDULE: OTY PRODUCT NAME MANUFACTURER OPTIONS, FINISHES & COLORS KEY ITEM INSTALLATION 6' CAST BENCH, DOUGLAS FIR SEAT; WITH CENTER BENCH 166, MODEL BB BACKLESS BENCH AND END ARMRESTS; POWDERCOAT COLOR: BLACK NO. 166-60D RECEPTACLE 157, 32-GALLON STEEL RECEPTACLE WITH SHIELD AND TR TRASH RECEPTACLE MODEL NO. 157- DU MOR BONNET COVER WITH 10" OPENING; POWERCOAT SURFACE MOUNT

32-GALLON STEEL RECEPTACLE WITH SHIELD, RECYCLE

10" OPENING; POWERCOAT COLOR: RECYCLE BLUE

LID WITH 4" OPENING, AND BONNET COVER WITH SURFACE MOUNT

RECEPTACLE 157,

32SH-BT-RC

RR RECYCLING RECEPTACLE

**GENERAL NOTE:** 

STAMP AREA

• SITE ADD ALTERNATE S4 IS ADDITION OF BENCH PADS, BENCHES, AND SHADE TREES.


MODEL NO. 157- DU MOR

SITE ADD ALTERNATE S4 - PLANT SCHEDULE:

KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONDITION	SPACING			
CANOPY TREES									
LT	5	Liriodendron tulipifera	Tulip Poplar	2"-2.5" CAL.	B&B	AS SHOWN			
	5	TOTAL CANOPY TREES			-				

LEGEND:

CONCRETE PAVEMENT



BACKLESS BENCH TRASH & RECYCLING RECEPTACLES

DESIGN STUDIO ON MAY 10, 2021.

SITE LAYOUT & MATERIALS NOTES:

 $\left(\frac{1}{L-502}\right)$  CANOPY TREE

# 1. SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC. TO SALT

2. ALL CONSTRUCTION SHALL CONFORM TO CITY, COUNTY, STATE, AND FEDERAL

3. VERIFY DIMENSIONS AND ACCEPT CONDITIONS BEFORE PROCEEDING WITH ANY WORK. REPORT DISCREPANCIES TO LANDSCAPE ARCHITECT.

4. THESE CONSTRUCTION DOCUMENTS MAKE NO REPRESENTATIONS AS TO THE MEANS AND METHODS OF CONSTRUCTION.

5. DO NOT SCALE DRAWINGS; CONSULT LANDSCAPE ARCHITECT FOR ANSWERS TO ALL DIMENSIONAL QUESTIONS.

6. CONTACT UTILITY COMPANIES AS REQUIRED BY STATE AND LOCAL REGULATIONS

BEFORE DIGGING TO LOCATE AND MARK EXISTING UTILITIES.

. COORDINATE ALL UTILITY WORK WITH THE LOCATIONS AND FINAL GRADES OF ALL OTHER WORK AS SHOWN ON THE ENGINEER'S DRAWINGS. WHERE CONFLICTS OCCUR. NOTIFY THE ENGINEER AND LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF UTILITIES TO MAKE ADJUSTMENTS AS REQUIRED. IF NEW UTILITIES HAVE BEEN INSTALLED IN CONFLICT WITH CURBS, WALLS, PAVING, OR OTHER STRUCTURES AT DEPTHS TOO SHALLOW FOR PROPER COVER BENEATH NEW GRADES OR INCORRECT FINISHED GRADE, THEY SHALL BE ADJUSTED OR REMOVED AND REPLACED AS

8. CONTRACTOR TO OBTAIN THE LANDSCAPE ARCHITECT'S APPROVAL OF LAYOUT OF ALL SITE IMPROVEMENTS PRIOR TO INSTALLATION.

9. DIMENSIONS ARE PROVIDED TO EDGE OF PAVEMENT, FRONT OF CURB, FACES OF WALLS, OR OBJECT CENTERLINE, UNLESS NOTED OTHERWISE.

10. ELEMENTS SHALL BE PARALLEL OR PERPENDICULAR, UNLESS NOTED OTHERWISE.

11. PROVIDE SLOPES ON PAVEMENT SURFACES AS INDICATED ON GRADING AND DRAINAGE PLAN TO ALLOW FOR POSITIVE DRAINAGE. 11.1. NO PONDING SHALL BE PERMITTED ON FINISHED GRADE OF SITE PAVEMENTS. AREAS WHERE PONDING OCCURS SHALL BE REGRADED AND REPAIRED AT

12. COORDINATE INSTALLATION OF FURNISHINGS AND EQUIPMENT FOUNDATIONS PRIOR TO INSTALLING SITE PAVEMENTS.

#### **GENERAL PLANTING NOTES:**

CONTRACTOR'S EXPENSE.

NECESSARY AT CONTRACTOR'S EXPENSE.

1. SITE SURVEY DATA WAS PROVIDED BY AMERICAN ENGINEERS GROUP, LLC. TO SALT DESIGN STUDIO ON MAY 10, 2021.

2. ALL CONSTRUCTION SHALL CONFORM TO CITY, COUNTY, STATE, AND FEDERAL

3. CONTRACTOR SHALL FIELD VERIFY LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND SUBTERRANEAN ELEMENTS PRIOR TO COMMENCING WORK. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT FOR RELOCATION INSTRUCTIONS IF A PLANT IS LOCATED WITHIN 3'-0" OF AN UNDERGROUND UTILITY.

4. CONTRACTOR SHALL PROTECT EXISTING TREES TO REMAIN WITH TREE PROTECTION FENCING AND MEASURES AS INDICATED ON ENGINEER'S PLANS.

5. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES PRIOR TO BEGINNING OR CONTINUING WORK.

6. ALL EXISTING GRASS AND ROOTS OF REMOVED VEGETATION SHALL BE COMPLETELY REMOVED FROM SITE PRIOR TO INSTALLATION OF NEW PLANTS.

7. THERE WILL BE NO PLANT SUBSTITUTIONS, DELETIONS, OR ADDITIONS WITHOUT THE APPROVAL OF LANDSCAPE ARCHITECT.

8. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT IF SUBSOIL CONDITIONS SHOW EVIDENCE OF UNEXPECTED WATER RETENTION IN TREE OR SHRUB PITS.

9. CONTRACTOR SHALL PROVIDE EROSION CONTROL MEASURES TO PREVENT SOIL LOSS AS INDICATED ON ENGINEER'S PLANS.

10. ALL IMPORTED PLANTING SOIL MUST BE TESTED AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. SEE SPECIFICATIONS.

11. SEE PLANT SCHEDULE FOR PLANT SIZES, QUANTITIES, SPECIES AND CONDITION.

12. CONTRACTOR SHALL STAKE ALL PLANTING AREAS, AND TREE AND SHRUB LOCATIONS IN FIELD FOR REVIEW AND APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO STARTING PLANT INSTALLATION. TREES TO BE SPACED EQUIDISTANT TO EACH OTHER. 13. ALL TREES AND SHRUBS SHALL HAVE AT LEAST 24" APPROVED PLANTING SOIL AROUND ROOTBALL.

14. CONTRACTOR SHALL INSTALL IRRIGATION BAGS FOR ALL NEW CANOPY AND UNDERSTORY TREES IMMEDIATELY UPON COMPLETION OF INSTALLATION. SEE SPECIFICATIONS.

15. MULCH, COMPOST AND/OR LEAF LITTER IS TO BE INSTALLED AS INDICATED ON DETAILS

# SITE FURNISHINGS NOTES:

CONTRACTOR TO OBTAIN THE LANDSCAPE ARCHITECT'S APPROVAL OF LAYOUT OF ALL

SITE FURNISHINGS AND EQUIPMENT PRIOR TO INSTALLATION. 2. DIMENSIONS ARE PROVIDED TO EDGE OF PAVEMENT, FACES OF WALLS, EDGE OF SITE FURNISHING OR FENCE, OR CENTERLINE OF PLAY EQUIPMENT, UNLESS NOTED

3. ELEMENTS SHALL BE PARALLEL OR PERPENDICULAR, UNLESS NOTED OTHERWISE.

4. SEE SITE FURNISHINGS SCHEDULE FOR QUANTITIES, PRODUCT, AND MANUFACTURER INFORMATION.

5. FOUNDATIONS FOR ALL FURNISHINGS SHALL BE LOCATED ON SITE AND REVIEWED IN FIELD WITH LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

REVISIONS

ISSUE DATE

DESCRIPTION

**KELLY MAIELLO** ARCHITECTS 1420 Walnut Street, 15th Floor Philadelphia, PA 19102 www.kmarchitects.com

SALT DESIGN STUDIO 161 Leverington Avenue, Suite 1005 Philadelphia, PA 19127 www.saltdesignstudio.com M.E.P./F.P./SITE CIVIL ENGINEERS:

LANDSCAPE ARCHITECT:


Pennoni Associates 1900 Market Street Suite 300 Philadelphia PA 19103 www.pennoni.com

LEED CONSULTANT: Verde Architecture Consulting 1635 Market Street Suite 1600 Philadelphia PA 19103

CITY OF PHILADELPHIA DEPARTMENT OF PUBLIC PROPERTY

1515 ARCH STREET 11TH FLOOR, ONE PARKWAY BUILDING

> KINGSESSING RECREATION CENTER BUILDING AND SITE **IMPROVEMENTS - PACKAGE 2**




SITE ADD ALTERNATE S4 -**DIAGONAL PATH AMENITIES** 

L-802-R.2

ALL DIMENSIONS AND CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE SITE BEFORE PROCEEDING WITH THE

PACKAGE 2 - IFB



SITE ADD ALTERNATE S4: DIAGONAL PATH AMENITIES LAYOUT & MATERIALS PLAN

SITE ADD ALTERNATE S4: DIAGONAL PATH AMENITIES FURNISHINGS & PLANTING PLAN

DIAGONAL PATH THROUGH SITE IS PART OF -

THE BASE SCOPE OF WORK. SEE L-101

AND L-102 FOR MORE INFORMATION.

TYP. OF 3

NOT FOR CONSTRUCTION 08/28/2023